NOTICE ANY WORK CONCEALED BEFORE THE NECESSARY INSPECTION HAS BEEN APPROVED WILL REQUIRE AN ENGINEERS EVALUATION SIGN-OFF OR TO BE PROPERLY EXPOSED FOR THE INSPECTION.

TYPES OF INSPECTIONS – RESIDENTIAL

• TEMPORARY POLE (Will release to Power Company)		
_		• •/
•	FOOTING	Before concrete is poured: Rebar properly tied and elevated. All mud, loose
	dirt, rocks, roots etc. removed	
•	FOUNDATION WALL	After forms set and any steel installed but before concrete is poured
•	SLAB PLUMBING	Work complete, water test on stack, before covering
•	SLAB ELECTRIC	After conduit installed/secure but before covering or concrete is poured
•	SLABS/ SLAB FOOTING	After form bds, gravel, poly, steel, grd stakes installed but B/F concrete
•	SLAB GARAGE	After rebar-rewire installed and secure but before concrete is poured
•	FOOTING - PIER COLUMN (ANYTIME)	For decks
•	DAMPROOF	Before back fill
•	FOUNDATION SURVEY	New Single Family Homes / Re-build on New Slab
•	EXTERIOR STRUCTURAL FRAME	If it is required – check approved plans
•	GAS LINE	Checked on Heat Rough unless it is a separate structure from main one
•	FIREPLACE	Checked on Heat Rough unless it is a separate structure from main one
•	ROUGH PLUMBING	Work complete – all vents through roof and plumbing boots installed
•	ROUGH HVAC	Work complete – gas lines & pressure
	ROUGH GENERATOR/ XFER SWITCH ROUGH ELECTRIC	Work complete, panels set, xfter switch set, wiring installed Work complete
•		•
•	ANCHORBOLTS	Installed and secure on sill plate
•	ENGINEERING DESIGNS	If it is required – check approved plans
•	FRAMING (MUST HAVE ROUGHS FIRST)	Work Complete, roof shingled, doors and windows installed.
•	INSULATION (MUST HAVE FRAMING FIRST)	Work Complete
•	RELEASE ELECTRIC (New Res. Only) Par	nel / Disconnects complete, Req. appliances, devices & fixtures set (Releases to Pwr Company)
•	FINAL PLUMBING	All fixtures set and water turned on

*****MUST PAY ALL RECALL FEES & ALL HOLDS CLEAR B/F SCHDULING*******************

FINAL HVAC

SEPTIC TANK

FINAL ELECTRIC

FINAL GENERATOR/XFER SWITCH

BUILDING FINAL Building ready for occupancy & landscaping complete

Furnace & A/C work complete

(No later then Elec. Final) Work complete on septic system

Work complete, service on & ready for testing

Work complete, generator set all wiring completed – ready for testing