

September 29, 2023

**Subject: ITB #2300-B: Parking Lot Resurfacing Project
Addendum #1**

Gentlemen/Ladies:

Below, please find responses to questions, clarification, or additional information for the above referenced ITB. You will need to consider this information when preparing your bid.

Please see the following updated Appendix A and the revised Price Sheet to include the McCurry Park new speed bumps.

Received by (Name): _____ Company _____


Note: If this addendum is not returned to the Fayette County Purchasing Department or if it is returned not signed, responding individuals, companies or other organizations will still be responsible for the requirements of this addendum and the specifications or changes herein.

The opening date for this ITB has not changed. **The opening time and date are 3:00p.m, Friday, October 6, 2023.** Bids must be received by the Purchasing Department at the address above, Suite 204, at or before the opening date and time.

The deadline for inquiries has passed, so the Purchasing Department will not be able to accept any additional questions after this time.

If you have questions, please contact Sherry White, Contract Administrator at (770) 305-5314, fax (770) 719-5544 or email at swhite@fayettecountyga.gov.

Sincerely,



Ted L. Burgess
Director of Purchasing

APPENDIX A (Project List)

1. **FIRE STATION #2** – This Fire Station is located on SR 92 North. This 2,045 SY parking lot will be edge milled next to the existing concrete pads, mill patched at 2", resurfaced with 1.5" of 12.5mm new asphalt and pavement markings. Sand will need to be placed on this existing concrete entrance driveway to prevent tracking of tack, there will be a pay item for this sand. There will be no restrictions on the scheduling for this parking lot. Due to this being an active fire station it will be required that fire apparatus will have the ability to leave through one of the entrances at all times to respond to emergency calls.
2. **FIRE STATION #5** – This Fire Station is located on SR 85 South near the intersection with Bernhard Road. This 3,700 SY parking lot will be split into 2 portions; 1 will be full milled and resurfaced with 1.5" of 12.5mm and the other portion will be edge milled and overlaid with 1.5" of 12.5mm. Due to this being an active fire station it will be required that fire apparatus will have the ability to leave through one of the entrances at all times to respond to emergency calls.
3. **FIRE STATION #6** – This Fire Station is located on 85 Connector in the town limits of Brooks, Georgia. This 3,500 SY parking lot will also be split into a full mill section and an edge mill section like Fire Station #5. Overlay will be 1.5" of 12.5mm. Parking lot shall be paved to promote overall positive drainage, additional milling and/or grading and/or reconstruction of subgrade and base may be needed to achieve this goal. Due to this being an active fire station it will be required that fire apparatus will have the ability to leave through one of the entrances at all times to respond to emergency calls.
4. **FIRE STATION #10** – This Fire Station is located on Seay Road near the roundabout on Highway 92, Seay Rd & Harp Rd. This 2,800 SY parking lot will be milled and resurfaced using 1.5" of 12.5mm. Due to this being an active fire station it will be required that fire apparatus will have the ability to leave through one of the entrances at all times to respond to emergency calls.
5. **FAYETTEVILLE LIBRARY PARKING LOT** – This parking lot is located off SR 54 (W. Stonewall Ave) behind Fayette County's Stonewall Facility. This 8,850 SY parking lot will be milled and resurfaced with 1.5" of 9.5mm. This work will need to happen when this facility will be open to the public which will require the 2/3rds of the parking lot to be always available for parking. COUNTY will be open to proposals for this CONTRACTOR to work nights or Sundays when this facility will be closed, and no restrictions will be in place.
6. **MCCURRY PARK SOCCER PARKING LOT** – This parking lot is located on McDonough Road near the intersection with SR 54. Edge milling next to existing curb and gutter will be required and all areas will be overlaid with 9.5mm at 1.5". Schedule restrictions during the active soccer season (Aug to Nov & Feb to May) may limit afternoon work after 5pm and on Saturdays. Speed bumps (6) need to be removed before resurfacing (by milling, grinding, etc..) and new asphalt speed bumps reinstalled (6) @ 25'x3'x4", painted yellow after resurfacing.

PRICING SHEET
ITB #2300-B: Parking Lot Resurfacing Project

ITEM NO.	DESCRIPTION	UNIT	QTY	Unit Cost	Total Cost
150-1000	Traffic Control	LS	1		
	Mobilization	EA	6		
402-3130	12.5mm	TN	1,154		
402-3103	9.5mm Type 2	TN	2,319		
	Asphalt Leveling	TN	94		
402-3190	19mm Patching	TN	915		
	Speed Humps (remove & replace)	EA	6		
	Sand – Concrete Protection	LS	1		
407-0010	Crack Sealing	LF	5,400		
413-0750	Bitum Tack Coat	GAL	3,748		
432-5010	Mill Asph Conc Pvmt, Variable Depth	SY	20,428		
	Pavement Markings – Fire Station #2	LS	1		
	Pavement Markings – Fire Station #5	LS	1		
	Pavement Markings – Fire Station #6	LS	1		
	Pavement Markings – Fire Station #10	LS	1		
	Pavement Marking - Library	LS	1		
	Pavement Markings – McCurry Park	LS	1		
TOTAL BID PRICE:					

NOTE: All applicable charges shall be included in your unit prices, including but not limited to all labor, administrative forces, materials, bond, mix design, testing, equipment, installation, and any other amounts. No additional charges will be allowed after the bid opening. All resurfacing must be complete by June 7, 2024. All work must be 100% completed by June 30, 2024.

State number of days needed to start after Notice to Proceed is issued. _____ Days

COMPANY NAME _____