

FAYETTE COUNTY EMERGENCY OPERATIONS CENTER 140 STONEWALL AVENUE WEST

FAYETTEVILLE, GA. 30214

TEL: (770) 305-5165

WAKEFIELD BEASLEY &ASSOCIATES 5155 PEACHTREE PARKWAY

BUILDING 300, SUITE 3220

DOUG SHAW, AIA

CELL:(678) 983-5992 FAX: (770) 209-7050

 $(\emptyset\emptyset)$ 

PARTAIN ENGINEERING, LLC 355 PEACHTREE DRIVE WHITE, GA 30184

SYMBOLS

CHRIS PARTAIN TEL: (770) 345-0589 FAX: (770) 720-2253 STRUCTURAL:

LBYD, INC. 900 CIRCLE 15 PARKWAY SUITE 1300 ATLANTA, GA 30339

DENNIS TOW, P.E.

TEL: (770) 857-1230

FAX: (205) 488-0226

FIRE PROTECTION 4 ELECTRICAL:

MECHANICAL, PLUMBING,

COYALENT CONSULTING, LLC 3414 PEACHTREE ROAD SUITE 3Ø1

ATLANTA, GA 30326 FRED GORDON TEL: (404) 355-9334

			4			
ΑT	MAT.	MATERIAL	4			
ACOUSTICAL TILE	H.M.	HOLLOW METAL			m m	
ABOVE FINISHED FLOOR	HŤ	HEIGHT	A-3.1	ELEVATION MARK	# # # *	PLYWOOD (LARGE SCALE)
ALUMINUM	I.B.C.	INSTALLED BY CONTRACTOR			<i>III III</i>	
BOTTOM OF	JT.	JOINT	1		The State of the S	
BOARD	L.L.	LANDLORD				PLASTER, GYPSUM WALLBOARD
BUILDING	MAX.	MAXIMUM		SECTION MARK	<u> 184 - 184 - 184 - 184 - 1</u>	
BRICK	MECH.	MECHANICAL	(A-4.I)	'SIM' - SIMILAR		
BEARING	MIN.	MINIMUM		'OH' - OPPOSITE HAND		RIGID INSULATION
CENTER LINE	MTL.	METAL	$\overline{}$		KXXXXXXXX	
CONTROL JOINT	NC.	NON-COMBUSTIBLE	/			
CONCRETE MASONRY UNIT	N.I.C.	NOT IN CONTRACT	1	ENLARGED PLAN / DETAIL MARK		BATT INSULATION
COORDINATE	N.T.S.	NOT TO SCALE	I I	DETAIL HARN		
			4 \			

**ABBREVIATIONS** 

OVERFLOW DRAIN OPPOSITE HAND

PLASTIC LAMINATE

SUPPLIED BY OWNER

TONGUE AND GROOVE

UNLESS NOTED OTHERWISE

STAINLESS STEEL

PLYWOOD

ON CENTER

SECTION

SCHEDULE

SIMILAR

STRUCTURA

TOP OF

TYPICAL

VERTICAL

WIDE

WOOD

VERIFY IN FIELD

WELDED WIRE FABRIC

STEEL

ROOF DRAIN

PAINT

A.F.F.

C.J.

C.M.U.

COL

DWG.

EA.

EXP.

F.D.

CONC.

COLUMN

DETAIL

CONCRETE

CONTINUOUS

CURTAINWAL

DIAMETER

DRAWING

EACH

DOWN SPOUT

ELEVATION

EXPANSION

FLOOR DRAIN

FINISH FLOOR

FRANCHISEE

FLOOR

EQUIPMENT SUPPLIER

FURNISHED BY OWNER

FIBERGLASS REINFORCED

GENERAL CONTRACTOR

GYPSUM WALL BOARD

FIRE RETARDANT

ELECTRIC WATER COOLER

FIRE EXTINGUISHER CABINET


ROOM NAME & NUMBER

DOOR REFERENCE NUMBER SEE SHEET AS.I


CONCRETE

STEEL, IRON

FLOOR FINISH



WOOD DIMENSIONAL



Clearbrook Way

VICINITY MAP BUILDING SECTIONS & VERTICAL CIRCULATION WALL SECTIONS WALL SECTIONS ARCHITECTURAL STEEL DETAILS & NOTES A400 PLAN DETAILS A600 DOOR SCHEDULE & DETAILS STRUCTURAL SIOO STRUCTURAL - GENERAL NOTES STRUCTURAL - GENERAL NOTES STRUCTURAL - GENERAL NOTES & ABBREVIATIONS STRUCTURAL - TYPICAL DETAILS S1Ø4 STRUCTURAL - TYPICAL DETAILS STRUCTURAL - TYPICAL DETAILS STRUCTURAL - SCHEDULE - SPECIAL INSPECTIONS 5200 STRUCTURAL - FOUNDATION PLAN

A1Ø2

A1Ø3 A1Ø4 EXISTING CONDITIONS PLAN

C501 GRADING AND DRAINAGE PLAN

DEMOLITION FLOOR PLAN

DIMENSION FLOOR PLAN

REFERENCE FLOOR PLAN

REFLECTED CEILING PLAN

EXTERIOR ELEVATIONS

A000 ARCHITECTURAL SITE PLAN

ROOF PLAN

C831 CONSTRUCTION DETAILS

FOUNDATION LANDSCAPE PLAN - ALTERNATE \*1

ARCHITECTURAL

FINISH PLAN, FINISH SCHEDULE, & NOTES

NTERIOR ELEVATIONS & MILLWORK DETAILS

EES&PC PLAN

ESPC DETAILS

C4ØI SITE PLAN

C701 PROFILES

C800 ESPC DETAILS

C802 ESPC DETAILS

S2Ø1	STRUCTURAL - ROOF FRAMING PLAN
53 <i>00</i>	STRUCTURAL - SECTIONS AND DETAILS
53Ø1	STRUCTURAL - SECTIONS AND DETAILS
	MECHANICAL
M001	MECHANICAL - SPECIFICATIONS, SCHEDULES
MØØ2	MECHANICAL - COMCHECK REPORT
M1Ø1	MECHANICAL - FLOOR PLAN
	FIRE PROTECTION
FP001	FIRE PROTECTION - SPECIFICATIONS
FP1Ø1	FIRE PROTECTION - FLOOR PLAN
	PLUMBING PLUMBING
P001	PLUMBING - SPECIFICATIONS
PIØI	PLUMBING - FLOOR PLANS, DEMO & WASTE
P102	PLUMBING - WATER & GAS PLAN
	ELECTRICAL

EDDI ELECTRICAL - LEGEND, GENERAL NOTE AND ABREVIATIONS

E302 | ELECTRICAL - ROOF PLAN - POWER & LIGHTNING PROTECTION SYSTEM

ELECTRICAL - DEMO PLAN & NEW GROUND LOOP

ELECTRICAL - FLOOR PLAN-POWER & SIGNAL

ELECTRICAL - FLOOR PLAN - LIGHTING

E801 ELECTRICAL - PANELBOARD SCHEDULES

ELECTRICAL - RISER DIAGRAM - EXISTING

ELECTRICAL - SITE PLAN

ETØI ELECTRICAL - DETAILS

Sheet Title SHEET

Sheet No. G100

FOR CONSTRUCTION

WAKEFIELD BEASLEY & ASSOCIATES ARCHITECTS INTERIORS Atlanta Office:

Jacksonville Office.

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia



are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

12/02/13 ADDENDUMS AND CLARIFICATIONS

2013-09-23 1207007000

COVER

+ (80 - 50) OCCUPANTS x 1(WC) PER 50 OCCUPANTS = 0.75 (WC) TOTAL(WC) = 2.75

> 2.75/2 = 1.38 MALE (WC)2.75/2 = 1.38 FEMALE (WC)

LAVATORIES (LAV)

50 OCCUPANTS x I(LAY) PER 40 OCCUPANTS = 1.25 (LAY) + (80 - 50) OCCUPANTS x I(LAY) PER 80 OCCUPANTS = 0.38 (LAY) TOTAL(LAV) = 1.63(LAV)

> 1.63/2 = 0.82 MALE (LAV)1.63/2 = 0.82 FEMALE (LAV)

DRINKING FOUNTAINS (DF)

80 OCCUPANTS x I(DF) PER 100 OCCUPANTS = 0.80 (DF)

ASSEMBLY OCCUPANCY - GROUP A-3

123 OCCUPANTS

123 OCCUPANTS/ 2 = 61.5 MALE OCCUPANTS 123 OCCUPANTS/ 2 = 615 FEMALE OCCUPANTS

WATER CLOSETS (WC):

61.5 MALE OCCUPANTS x 1(WC) PER 125 OCCUPANTS = 0.49 MALE (WC) 61.5 FEMALE OCCUPANTS x I(WC) PER 65 OCCUPANTS = 0.94 FEMALE(WC)

LAVATORIES (LAV)

123 OCCUPANTS x I(LAY) PER 200 OCCUPANTS = 0.62 (LAY) 0.62/2 = 0.31 MALE (LAV) $\emptyset$ 62/2 =  $\emptyset$ .31 FEMALE (LAV)

DRINKING FOUNTAINS (DF)

123 OCCUPANTS x I(DF) PER 500 OCCUPANTS = 0.25 (DF)

SUMMARY =

WATER CLOSETS (WC)

MALE: 1.38 GROUP B (WC) + 0.49 GROUP A-3 (WC) = 1.87 = 2 MALE (WC)

1.38 GROUP B (WC) + 0.94 GROUP A-3 (WC) = 2.32 = 3 FEMALE (WC)

203 OCCUPANTS

LAVATORIES (LAV)

SERVICE SINK = 1

MALE: 0.82 GROUP B (LAV) + 0.62 GROUP A-3 (LAV) = 1.44 = 2 MALE (LAV)

082 GROUP B (LAY) + 062 GROUP A-3 (LAY) = 1.44 = 2 FEMALE (LAY)

080 GROUP B (DE) + 025 GROUP  $\Delta$ -3 (DE) = 105 = 2 (DE)

0.80 GROUP D (DF) + 0.25 GRO	$\frac{1}{2} \frac{1}{2} \frac{1}$
REQUIRED	PROVIDED
WATER CLOSETS (WC): MALE (WC) = 2 FEMALE (WC) = 3	WATER CLOSETS (WC): MALE (WC) = 3 FEMALE (WC) = 3
LAVATORIES (LAV) MALE (LAV) = 2 FEMALE (LAV) = 2	LAVATORIES (LAV) MALE (LAV) = 3 FEMALE (LAV) = 3
DRINKING FOUNTAINS (DF) = 2	DRINKING FOUNTAINS (DF) = 2

SERVICE SINK = 1

# PROJECT DATA

#### APPLICABLE CODES:

STANDARD BUILDING CODE (INTERNATIONAL BUILDING CODE) 2006 EDITION WITH GEORGIA AMENDMENTS

NATIONAL ELECTRICAL CODE, 2011 EDITION WITH GEORGIA AMENDMENTS

STANDARD PLUMBING CODE (INTERNATIONAL PLUMBING CODE.) 2006 EDITION WITH GEORGIA AMENDMENTS STANDARD MECHANICAL CODE (INTERNATIONAL MECHANICAL CODE,) 2006 EDITION WITH GEORGIA AMENDMENTS

STANDARD FIRE PREVENTION CODE (INTERNATIONAL FIRE CODE,) 2006 EDITION WITH GEORGIA AMENDMENTS

STANDARD GAS CODE (INTERNATIONAL FUEL GAS CODE,) 2006 EDITION WITH GEORGIA AMENDMENTS

INTERNATIONAL ENERGY CONSERVATION CODE, 2009 EDITION WITH GEORGIA AMENDMENTS

NFPA 101 LIFE SAFETY CODE, 2000 EDITION.

2010 GEORGIA ACCESSIBILITY CODE. CHAPTER 120-3-20

#### CLASSIFICATIONS:

OCCUPANCY CLASS: BUSINESS & A-3 ASSEMBLY

CONSTRUCTION TYPE: IIB, SPRINKLERED

# BUILDING AREA:

BUILDING AREA EXISTING BUSINESS AREA: 5,711 SQ.FT. ADDITION (NEW CONSTRUCTION) 2,326 SQ.FT. BUSINESS AREA: ASSEMBLY AREA: <u>1,840 SQ.FT.</u>

CODE LIMITS: BUILDING AREA: 23,000 SQ.FT. PER FLOOR SECT. 506.3 AUTO SPRINK. INCREASE 200%

TOTAL: 69,000 SQ.FT

## BUILDING HEIGHT

TOTAL:

ACTUAL:	CODE LIMITS:
I STORY	4 STORY
HEIGHT ABOVE GRADE: 19'-0"	HEIGHT ABOVE GRADE: 55'-0"

9,877 SQFT.

#### CONSTRUCTION ELEMENTS

ITEM	CODE \$ SECTION	RATING (MIN.)	DESIGN NUMBER	COMMENTS
STRUCTURAL FRAME	IBC T 601	Ø		
BEARING WALLS				
EXTERIOR	IBC T 601	0		
INTERIOR	IBC T 601	Ø		
NON BEARING WALLS				
EXTERIOR	IBC T 602	Ø		
INTERIOR	IBC T 601	Ø		
FLOOR CONSTRUCTION	IBC T 601	0		
ROOF CONSTRUCTION	IBC T 601	Ø		

# ZONING INFORMATION:

CURRENT ZONING: ----LANDLOT: --- DISTRICT: --- PARCEL ID: ------

# 2000 NFPA LIFE SAFETY CODE

OCCUPANCY: EXISTING BUISINESS (CH. 39)

MEANS OF EGRESS CAPACITY

MINIMUM STAIR WIDTH: 36", LSC 7.3.4.1 CAPACITY FACTORS: LSC TBL. 7.3.3.1

LEVEL COMPONENTS & RAMPS: 0.2" PER PERSON

STAIR: 0.3" PER PERSON

MINIMUM NUMBER OF EGRESS: THREE, L.S.C. 7.4.1.2 (1)

TRAYEL DISTANCE LIMITATIONS, SPRINKLERED:

OCCUPANCY	COMMON PATH LIMIT	DEAD END	TRAVEL DISTANCE
BUISINESS (CH. 39)	100' (W/ SPRNKLR.)	50'	3ØØ'
A-3 ASSEMBLY	100' (W/ SPRNKLR.)	5Ø'	200'

# GENERAL NOTES

#### EXIT DOORS SHALL NOT BE SUBJECT TO THE USE OF A KEY OR REQUIRE SPECIAL KNOWLEDGE TO OPERATE PER THE NFPA 101 LIFE SAFETY CODE 2000 EDITION, CHAPTER 5-2.15.1.

- PANIC HARDWARE SHALL BE PROVIDED FOR ALL EXIT DOORS PER THE REQUIREMENTS OF NFPA LIFE SAFETY CODE 2000 EDITION, CHAPTER 5-2.1.7.
- COMBUSTIBLE INTERIOR FINISH PRODUCTS SHALL BE PROVIDED PER THE REQUIREMENTS OF THE CHAPTER 39 OF THE NFPA 101 LIFE SAFETY CODE 2000 EDITION. VERIFICATION WILL BE PROVIDED AT THE TIME OF FINAL INSPECTION THAT THE PRODUCTS COMPLY WITH THE REQUIREMENTS.
- 4. CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSPECTIONS W/ THE DEPARTMENT OF FIRE \$ EMERGENCY SERVICES FOR INSPECTIONS AT 50%, 80% \$ 100%,
- DETECTABLE WARNINGS ON WALKING SURFACES SHALL COMPLY WITH RULE 120-120-3-20-.40, GEORGIA ACCESSIBILITY CODE.
- PROTRUDING OBJECTS SHALL NOT REDUCE THE CLEAR WIDTH OF AN ACCESSIBLE ROUTE AND SHALL BE INSTALLED IN ACCORDANCE WITH RULE 120-3-20-.15 OF THE GEORGIA ACCESSIBILITY CODE.
- MECHANICAL, ELECTRICAL, & PLUMBING SUBCONTRACTORS SHALL SUBMIT AFFIDAYITS FOR EACH BUILDING PERMIT TO THE BUILDING PERMITS SECTION BEFORE REQUESTING INSPECTIONS.
- G.C. TO PROVIDE FIRE EXTINGUISHERS AT ALL FIRE EXTINGUISHER CABINET LOCATIONS MARKED F.E.C. ON PLANS AND IN ACCORDANCE WITH THE REQUIREMENTS OF NEPA 10.
- ALL MATERIALS EXPOSED WITHIN PLENUMS, (IF USED) ARE REQUIRED TO BE NONCOMBUSTIBLE OR SHALL HAVE A FLAME-SPREAD INDEX OF NOT MORE THAN 25 AND A SMOKE -DEVELOPED INDEX OF NOT MORE THAN 50 AS DETERMINED IN ACCORDANCE W/ ASTM E84 (IBC 716.5, 10004.3.2.4, IMC SECTION
- 10. ALL WORK TO COMPLY W/ STATE & FEDERAL CODES, SEE APPLICABLE CODE ON THIS SHEET.
- CONTRACTOR SHALL DOCUMENT THAT INSULATION MATERIALS IN CONCEALED OR EXPOSED SPACES SHALL HAVE A FLAME SPREAD INDEX OF NO MORE THAN 25 AND A SMOKE-DEVELOPED INDEX OF NOT MORE THAN 450. REFER TO IBC SECTION 118.1, 118.2, 118.3. FOR EXCEPTIONS.
- 12. SIGNS, LOCATION, NUMBER AND SIZE ARE NOT APPROVED UNDER THIS BUILDING PERMIT. A SEPARATE SIGN LOCATION PERMIT IS REQUIRED FOR EACH SIGN.
- 13. ALL WOOD LUMBER AND PLYWOOD OR O.S.B. USED IN EXTERIOR CONSTRUCTION SHALL BE PRESSURE PRESERVATIVE - TREATED, THAT COMES IN CONTACT W/ CONCRETE OR WITHIN 12" OF GRADING/SOIL.
- PRIOR TO INSTALLATION THE CONTRACTOR SHALL SUBMIT DETAILS FOR REVIEW AND APPROVAL WHICH CLEARLY INDICATE LATERIAL BRACING TO BUILDING STRUCTURE FOR ALL PARTITIONS OF LIGHT GUAGE METAL FRAMING, WHICH EXCEED NINE FEET IN HEIGHT, TO ADEQUATELY RESIST THE APPLICABLE LATERAL SEISMIC DESIGN FORCES IN COMPLIANCE WITH IBC SECTIONS 16212.1 AND
- 15. ALL METAL FRAMING SHOWN ON THE DRAWINGS IS DIAGRAMMATIC ONLY. MEMBER SIZE, CONFIGURATION, DETAILS, AND CONNECTIONS ARE THE RESPONSIBILITY OF THE CONTRACTOR'S METAL FRAMING ENGINEER. METAL FRAME SHOP DRAWINGS COMPLETE WITH CALCULATIONS, ARE TO BE SIGNED AND SEALED BY METAL STUD ENGINEER AND SUBMITTED FOR REVIEW AND APPROVAL.
- 16. GENERAL CONTRACTOR SHALL COORDINATE W/ THE OWNER ALL SCHEDULE SEQUENCING TO AVOID CONFLICTS W/ DAILY OPERATIONS AND SPECIAL EVENTS OF THE EXISTING FACILITIES AND ACCESS. CONTRACTOR SHALL MAINTAIN AND PROTECT EXISTING EGRESS PATHS.
- 17. (DOORS/HARDWARE) HANDLES, PULLS, LATCHES, LOCKS, AND OTHER OPERATING DEVICES ON ACCESSIBLE DOORS SHALL HAVE A SHAPE THAT IS EASY TO GRASP WITH ONE HAND AND DOES NOT REQUIRE TIGHT GRASPING, TIGHT PINCHING, OR TWISTING OF THE WRIST TO OPERATE. LEVER-OPERATED MECHANISMS, PUSH-TYPE MECHANISMS, AND U-SHAPED HANDLES ARE ACCEPTABLE DESIGNS. RULE 120-3-20-24 (9) SHALL BE PROVIDED, GEORGIA ACCESSIBILITY CODE, 1998 EDITION.
- 18. SELF CLOSING DEVICES SHALL MEET THE REQUIREMENTS OF THE NFPA 101 LIFE SAFETY CODE, CHAPTER 1, SECTION 1.2.1.4, 2000 EDITION.
- 19. EMERGENCY LIGHTING COMPLYING WITH NFPA 101 LIFE SAFETY CODE, CHAPTER 1, SETION 7.9. 2000 EDITION, SHALL BE INSTALLED. ADDITIONAL EMERGENCY LIGHTING MAY BE REQUIRED UPON FIELD INSPECTION.
- 20. AUDIBLE/ VISUAL SIGNAL APPLIANCES COMPLYING WITH THE REQUIREMENTS OF RULE 120-3-20-39 GEORGIA ACCESSIBILITY CODE AND NFPA 72, 2002 EDITION SHALL BE PROVIDED.
- 21. ILLUMINATION OF THE MEANS OF EGRESS SHALL BE PROVIDED PER THE REQUIREMENTS OF NFPA 101 LIFE SAFETY CODE, CHAPTER 1, SECTION 1.8, 2000 EDITION.
- 22. DO NOT SCALE DRAWINGS USE DIMENSIONS ONLY. FOR DIMENSIONS NOT SHOWN OR IN QUESTION, CONTRACTOR SHALL REQUEST CLARIFICATION FROM ARCHITECT BEFORE
- 23. UNLESS OTHERWISE NOTED, INTERIOR PARTITION DIMENSIONS ARE GIVEN FROM FACE OF METAL STUD FRAMING/CMU TO FACE OF METAL STUD FRAMING/CMU, OR FROM FACE OF METAL STUD FRAMING/CMU TO COLUMN CENTERLINE. EXCEPTION: MILLWORK DETAILS WHERE DIMENSIONS ARE FROM FACE OF FINISH SURFACES (GWB, PLASTER, ETC.).
- 24. ELEVATIONS AND LEVELS ARE SHOWN FROM FINISH FLOOR ELEVATIONS AND ARE BASED ON A "REFERENCE BENCHMARK ELEVATION" - COORDINATE ELEVATION OF FINISHED FLOOR HEIGHT WITH CIVIL DRAWINGS, AND EXISTING BUILDING FINISH FLOOR HEIGHTS.
- 25. ELECTRIC PANELS, ALARM BOXES, FIRE EQUIPMENT CABINETS, AND OTHER RECESSED BOXES GREATER THAN 16 SQUARE INCHES THAT ARE LOCATED IN RATED WALLS SHALL BE BACKED BY GYPSUM WALLBOARD LAYERS SUFFICIENT TO MAINTAIN THE DESIGNATED RATING. FEC'S MAY BE PROVIDED WITH A RATED CABINET TO MATCH THE DESIGNED RATING.
- 26. ATTIC ACCESS FROM AN ADJACENT SPACE SHALL BE PROVIDED WHERE THE BELOW ITEMS OCCUR OVER GWB CEILINGS: A. YALYES B. FLOW MEASURING DEVICES C. MIXING BOXES D. POWER OPERATED DAMPERS E. ACCESS PANELS IN DUCTWORK F. VOLUME AND BALANCING DEVICES G. WATER FLOW SWITCHES H. SPRINKLER SYSTEM DRAINS AND TEST CONNECTIONS I PRESSURE SWITCHES
- 27. PATCH AND REPAIR ALL ITEMS DAMAGED OR ALTERED DURING CONSTRUCTION. ALL PATCHES SHALL BLEND WITH ADJACENT MATERIAL, COLOR, FINISH, AND TEXTURE. ALL EXISTING WORK FURNISHINGS, EQUIPMENT OR MATERIAL TO REMAIN THAT ARE DAMAGED BY THE CONTRACTOR'S OPERATION SHALL BE REPAIRED AT NO ADDITIONAL COST TO THE OWNER.
- 28. SLOPE ALL SLABS AT EXTERIOR BUILDING ENTRANCES I" FT MIN AWAY FROM BUILDING IN ALL

- 29. ISOLATE DISSIMILAR METALS BY MEANS OF A HEAVY BITUMINOUS COATING, APPROVED PAINT, ADHERED POLYETHYLENE SHEET, OR OTHER MEANS APPROVED BY THE ARCHITECT.
- 30. PRIME AND PAINT ALL STEEL LINTELS, HANDRAILS, AND ANY AND ALL OTHER INTERIOR OR EXTERIOR EXPOSED FERROUS METAL SURFACES NOT OTHERWISE INDICATED AS COATED OR
- 31. MATERIAL AND EQUIPMENT STORAGE SHALL BE ON SITE AND AS DIRECTED BY THE OWNER.
- 32. CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND CONDITIONS SHOWN ON THE DRAWINGS AND IMMEDIATELY NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO ORDERING OR FABRICATING MATERIALS OR OTHERWISE PROCEEDING WITH THE WORK.
- 33. PROVIDE LABOR, MATERIAL, EQUIPMENT, AND SERVICES REQUIRED TO EXECUTE AND COMPLETE ALL ITEMS OF WORK AS SHOWN, OR INDICATED ON THE DRAWINGS AND AS SPECIFIED, INCLUDING INCIDENTAL ITEMS TO EFFECT A FINISHED AND COMPLETE JOB.
- 34. STRUCTURAL WORK, INCLUDING MATERIAL STRESSES AND METHODS OF CONSTRUCTION, SHALL BE IN COMPLIANCE WITH THE LATEST ADOPTED BUILDING CODE, OSHA AND GOVERNING AGENCIES HAVING JURISDICTION.
- 35. CONTRACTOR SHALL USE CONSTRUCTION METHODS THAT ARE IN STRICT ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- 36. MAINTAIN PREMISES FREE FROM ACCUMULATIONS OF WASTE MATERIALS, DEBRIS AND RUBBISH CAUSED BY OPERATIONS
- 31. AFTER COMPLETION OF WORK ALL ADDITIONAL MATERIALS REMAINING DUE TO CONSTRUCTION SHALL BECOME THE PROPERTY OF THE GENERAL CONTRACTOR AND SHALL BE DISPOSED OF/REMOVED FROM THE SITE IN ACCORDANCE WITH ALL APPLICABLE LAWS, ORDINANCES RULES, AND REGULATIONS UNLESS NOTIFIED OTHERWISE. CONTRACTOR SHALL ALSO REMOVE ALL WASTE DEBRIS, RUBBISH, TOOLS, EQUIPMENT, AND SURPLUS MATERIALS UPON COMPLETION OF WORK. THROUGHOUT CONSTRUCTION, SITE SHALL BE ORGANIZED AND CLEANED BY CONTRACTOR ON A DAILY BASIS
- 38. THE CONTRACTOR SHALL RESTORE TO ITS ORIGINAL CONDITION ALL SITE APPURTENANCES DAMAGED UNDER THIS CONTRACT AT NO ADDITIONAL COST TO THE OWNER
- 39. ANY MATERIAL SCHEDULED FOR DEMOLITION SHALL BECOME THE PROPERTY OF THE CONTRACTOR UNLESS NOTED OTHERWISE AND SHALL BE DISPOSED OF LEGALLY.
- 40. ALL DETAILS, SECTIONS AND NOTES SHOWN ON THE DRAWINGS ARE INTENDED TO BE TYPICAL AND SHALL APPLY TO SIMILAR SITUATIONS ELSEWHERE, UNLESS SPECIFICALLY SHOWN OTHERWISE.
- 41. INTERIOR FINISH PRODUCTS SHALL BE PROVIDED PER THE REQUIREMENTS OF THE RESPECTIVE OCCUPANCY CHAPTER 39 OF THE NFPA 101 LIFE SAFETY CODE 2000 EDITION, THAT THE PROJECT IS BEING PERMITTED UNDER PROVIDE VERIFICATION AT THE TIME OF FINAL INSPECTION THAT THE PRODUCTS COMPLY WITH THE REQUIREMENTS.
- 42. EMERGENCY LIGHTING COMPLYING WITH SECTION 5-9 OF THE NFPA 101 LIFE SAFETY CODE 2000 EDITION SHALL BE INSTALLED.
- 43. SEATS, TABLES, AND WORK SURFACES COMPLYING WITH THE REQUIREMENTS OF RULE 120-3-20-.43 SHALL BE PROVIDED WHERE APPLICABLE.
- 44. THE FLOOR LEVEL SHALL BE THE SAME ON BOTH SIDES OF ALL UNIT INTERIOR DOORS, NFPA 101
- 45. EXIT DOORS SHALL OPERATE PER NFPA IØI LIFE SAFETY CODE 2000 EDITION CHAPTER 5-2.15.1.
- 46. PENETRATIONS INTO OR THROUGH, OF EITHER VERTICAL OR HORIZONTAL EXISTING FIRE RATED BARRIERS SHALL BE PROJECTED BY A SYSTEM LISTED BY A RECOGNIZED TESTING AGENCY PROVIDE A DETAIL AND LISTING NUMBER PER NFPA 101 LIFE SAFETY CODE 2000 EDITION.
- 47. STORAGE, MECHANICAL, FURNACE ROOM, JANITOR CLOSET, IN EXCESS OF 100 SQFT SHALL BE SEPERATED FROM THE REST OF THE BUILDING BY A 1 HOUR FIRE RATED CONSTRUCTION. ALL OPENINGS SHALL BE PROTECTED BY A 45 MINUTES LABELED FIRE DOORS. (2006 IBC.) DOORS TO INCLUDE SELF-CLOSER AND POSITIVE LATCHING (NFPA 101 LIFE SAFETY CODE 2000 EDITION)
- 48. SIGNAGE ON REST ROOM DOORS SHALL BE RAISED AND BRAILLE CHARACTERS AND PICTORAL SYMBOL SIGNS. SIGNS SHALL BE INSTALLED ON THE WALL ADJACENT TO THE LATCH SIDE OF THE DOOR. WHERE THERE IS NO WALL SPACE TO THE LATCH SIDE OF THE DOOR, INCLUDING AT DOUBLE LEAF DOORS, SIGNS SHALL BE PLACED ON THE NEAREST ADJACENT WALL. MOUNTING HEIGHT SHALL BE 60 INCHES ABOVE THE FINISH FLOOR TO THE CENTERLINE OF THE SIGN. 120-3-20-.41(4)(5)(6) GEORGIA ACCESSIBILITY CODE.
- 49. CONTRACTOR SHALL BE COMPLETELY RESPONSIBLE FOR BRACING AND SHORING OF THE STRUCTURE DURING CONSTURCTION TO ENSURE STABILITY
- 50. CENTERLINE OF FOOTINGS, WALLS, GRADE BEAMS, COLUMNS, AND BEAMS SHALL COINCIDE, UNLESS OTHERWISE NOTED.
- 51. COMPLETE SHOP DRAWINGS FOR ALL SPECIALITY ITEMS INCLUDING BUT NOT LIMITED TO ORNAMENTAL GUARDRAILS AND MODULAR RETAINING WALLS SHALL BE SEALED AND SIGNED SIGNIFYING REVIEW AND APPROVAL BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF GEORGIA, AND SHALL BE MADE AVAILABLE AT THE JOBS DURING TIMES OF INSPECTION.
- 52. ALL FINAL MATERIAL FINISH SELECTIONS TO BE APPROVED BY OWNER PRIOR TO ORDERING, TYPICAL
- 53. THIS BUILDING WILL BE A NONSMOKING FACILITY.
- 54. THE CONTRACTOR SHALL PROVIDE ADAQUATE BRACING & SHORING FOR ALL WORK DURING THE CONSTRUCTION PERIOD
- 55. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR BUILDING THIS PROJECT IN ACCORDANCE WITH DRAWINGS, SPECIFICATIONS & STATE & LOCAL CODES, UNLESS WRITTEN NOTIFICATION IS RECEIVED FROM THE ARCHITECT



ARCHITECTS INTERIORS

Atlanta Office. 5155 Peachtree Parkway Building 300, Suite 3220 Vorcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



110 Volunteer Mau Fauetteville, Georgia



are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written conser of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

1207007000 2013-09-23

GENERAL NOTES

Sheet No. G101

Nonbearing Wall Ratings - 1, 2, 3 or 4 Hr (See Items 3 & 4)

Design No. U419 October 27, 2005

1. Floor and Ceiling Runners - (Not shown) - Channel shaped, fabricated from min 25 MSG corrosion-protected steel, min width to accommodate stud size, with min 1 in. long legs, attached to floor and ceiling with fasteners 24 in. OC max.

2. Steel Studs - Channel shaped, fabricated from min 25 MSG corrosion-protected steel, min width as indicated under Item 4, min 1-1/4 in. flanges and 1/4 in. return, spaced a max of 24 in. OC. Studs to be cut 3/8 to 3/4 in. less than assembly height.

3. Batts and Blankets\* - (Required as indicated under Item 4) - Mineral wool batts, friction fitted between studs and runners. Min nom thickness as indicated under Item 4. See Batts and Blankets (BKNV or BZJZ) Categories for names of Classified companies.

3A. Batts and Blankets\* - (Optional) - Placed in stud cavities, any glass fiber or mineral wool insulation bearing the UL Classification Marking as to Surface Burning Characteristics and/or Fire Resistance. See Batts and Blankets (BKNV or BZJZ) Categories for names of Classified companies.

4. Gypsum Board\* - Gypsum panels with beveled, square or tapered edges, applied vertically or horizontally. Vertical joints centered over studs and staggered one stud cavity on opposite sides of studs. Vertical joints in adjacent layers (multilayer systems) staggered one stud cavity. Horizontal joints need not be backed by steel framing. Horizontal edge joints and horizontal butt joints on opposite sides of studs need not be staggered. Horizontal edge joints and horizontal butt joints in adjacent layers (multilayer systems) staggered a min of 12 in. The thickness and number of layers for the 1 hr, 2 hr, 3 hr and 4 hr ratings are as

Wallboard Protection on Each Side of Wall

Rating Min Stud DepthNo. of Layers & Thkns of PanelMin Thkns of Insulation (Item 3)13-1/21 layer, 5/8 in. thickOptional12-1/21 layer, 1/2 in. thick1-1/2 in.11-5/81 layer, 3/4 in. thickOptional21-5/82 layers, 1/2 in. thickOptional21-5/82 layers, 5/8 in. thickOptional23-1/21 layer, 3/4 in. thick3 in.31-5/83 layers, 1/2 in. thickOptional31-5/82 layers, 3/4 in. thickOptional31-5/83 layers, 5/8 in. thickOptional41-5/84 layers, 5/8 in. thickOptional41-5/84 layers, 1/2 in. thickOptional42-1/22 layers, 3/4 in. thick2 in.CANADIAN GYPSUM COMPANY - 1/2 in. thick Type C, IP-X2 or IPC-AR; WRC, 5/8 in. thick Type AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, WRX or WRC; 3/4 in. thick Types IP-X3 or ULTRACODE

UNITED STATES GYPSUM CO - 1/2 in. thick Type C, IP-X2, IPC-AR or WRC; 5/8 in. thick Type SCX, SHX, WRX, IP-X1, AR, C, WRC, FRX-G, IP-AR, IP-X2, IPC-AR; 3/4 in. thick Types IP-X3 or ULTRACODE

USG MEXICO S A DE C V - 1/2 in. thick Type C, IP-X2, IPC-AR or WRC; 5/8 in. thick Type AR, C, IP-AR, IP-X1, IP-X2, IPC-AR, SCX, SHX, WRX, WRC or; 3/4 in. thick Types IP-X3 or ULTRACODE

When Item 6B, Steel Framing Members\*, is used, Nonbearing Wall Rating is limited to 1 Hr. Min. stud depth is 3-1/2 in., min. thickness of insulation (Item 3) is 3 in., and two layers of gypsum board panels (1/2 in. or 5/8 in. thick) shall be attached to furring channels as described in Item 5. One layer of gypsum board panels (1/2 in. or 5/8 in. thick) attached to opposite side of stud without furring channels as described in

4A. Gypsum Board\* - (As an alternate to Item 4) - 5/8 in. thick, 2 ft. wide, tongue and groove edge, applied horizontally as the outer layer to one side of the assembly. Secured as described in Item 5. Joint covering (Item 7) not required. CANADIAN GYPSUM COMPANY - Type SHX.

UNITED STATES GYPSUM CO - Type SHX

USG MEXICO S A DE C V - Type SHX.

5. Fasteners - (Not shown) - Type S or S-12 steel screws used to attach panels to stude (Item 2) or furring channels (Item 6). Single layer systems: 1 in. long for 1/2 and 5/8 in. thick panels or 1-1/4 in. long for 3/4 in. thick panels, spaced 8 in. 0C when panels are applied horizontally, or 8 in. 0C along vertical and bottom edges and 12 in. OC in the field when panels are applied vertically. Two layer systems: First layer- 1 in. long for 1/2 and 5/8 in. thick panels or 1-1/4 in. long for 3/4 in. thick panels, spaced 16 in. 0C. Second layer- 1-5/8 in. long for 1/2 in., 5/8 in. thick panels or 2-1/4 in. long for 3/4 in. thick panels, spaced 16 in. OC with screws offset 8 in. from first layer. Three-layer systems: First layer- 1 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. 0C. Second layer- 1-5/8 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. OC. Third layer- 2-1/4 in. long for 1/2 in., 5/8 in. thick panels or 2-5/8 in. long for 5/8 in. thick panels, spaced 12 in. OC. Screws offset min 6 in. from layer below. Four-layer systems: First layer- 1 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. 0C. Second layer- 1-5/8 in. long for 1/2 in., 5/8 in. thick panels, spaced 24 in. 0C. Third layer- 2-1/4 in. long for 1/2 in. thick panels or 2-5/8 in. long for 5/8 in. thick panels, spaced 24 in. OC. Fourth layer- 2-5/8 in. long for 1/2 in. thick panels or 3 in. long for 5/8 in. thick panels, spaced 12 in. OC. Screws offset min 6 in. from layer below. 6. Furring Channels - (Optional, not shown, for single or double layer systems) - Resilient furring channels fabricated from min 25 MSG corrosion-protected steel, spaced vertically a max of 24 in. OC. Flange portion attached to each intersecting stud with 1/2 in, long Type S-12 steel screws. Not for use with Item 4A. 6A. Steel Framing Members (Not Shown)\* - (Optional on one or both sides, not shown, for single or double

a. Furring Channels - Formed of No. 25 MSG galv steel. 2-3/8 in. wide by 7/8 in. deep, spaced max. 24 in. OC perpendicular to studs. Channels secured to studs as described in Item b. Gypsum board attached to furring channels as described in Item 5. Not for use with Item 4A. b. Steel Framing Members\* - Used to attach furring channels (Item 6Aa) to stude (Item 2). Clips spaced

layer systems) - As an alternate to Item 6, furring channels and Steel Framing Members as described below:

max. 48 in. OC., and secured to study with No. 8 x 1-1/2 in. minimum self-drilling, S-12 steel screw through the center grommet. Furring channels are friction fitted into clips. PAC INTERNATIONAL INC - Type RSIC-1.

6B. Steel Framing Members (Optional, Not Shown)\* - As an alternate to Item 6, furring channels and Steel Framing Members on only one side of studs as described below:

a. Furring Channels - Formed of No. 25 MSG galv steel, spaced 24 in. OC perpendicular to studs. Channels secured to stude as described in Item b. Batts and Blankets placed in stud cavity as described in Item 4. Two layers of gypsum board attached to furring channels as described in Item 4. Not for use with Item 4A.

b. Steel Framing Members\* - Used to attach furring channels (Item 6Ba) to one side of studs (Item 2) only. Clips spaced 48 in. OC., and secured to study with two No. 8 x 2-1/2 in. coarse drywall screws, one through the hole at each end of the clip. Furring channels are friction fitted into clips. KINETICS NOISE CONTROL INC - Type Isomax


7. Joint Tape and Compound - Vinyl or casein, dry or premixed joint compound applied in two coats to joints and screw heads of outer layers. Paper tape, nom 2 in. wide, embedded in first layer of compound over all joints of outer layer panels. Paper tape and joint compound may be omitted when gypsum panels are supplied with a square edge.

8. Siding, Brick or Stucco - (Optional, not shown) - Aluminum, vinyl or steel siding, brick veneer or stucco, meeting the requirements of local code agencies, installed over gypsum panels. Brick veneer attached to studs with corrugated metal wall ties attached to each stud with steel screws, not more than each sixth

9. Caulking and Sealants\* - (Optional, not shown) - A bead of acoustical sealant applied around the partition perimeter for sound control. UNITED STATES GYPSUM CO - Type AS

\*Bearing the UL Classification Mark Reprinted from the Online Certifications Directory with permission from Underwriters Laboratories Inc. Copyright © 2006 Underwriters Laboratories Inc.®





Design No. U905 March 17, 2004 Bearing Wall Rating - 2 HR.

Nonbearing Wall Rating - 2 HR

1. Concrete Blocks\* - Various designs. Classification D-2 (2 hr). See Concrete Blocks category for list of eligible manufacturers. 2. Mortar - Blocks laid in full bed of mortar, nom. 3/8 in. thick, of not less than 2-1/4 and not more than 3-1/2 parts of clean sharp sand to 1 part Portland cement (proportioned by volume) and not more

than 50 percent hydrated lime (by cement volume). Vertical joints staggered. 3. Portland Cement Stucco or Gypsum Plaster - Add 1/2 hr to classification if used. Where combustible members are framed in wall, plaster or stucco must be applied on the face opposite framing to achieve a max. Classification of 1-1/2 hr. Attached to concrete blocks (Item 1). 4. Loose Masonry Fill - If all core spaces are filled with loose dry expanded slag, expanded clay or shale

(Rotary Kiln Process), water repellant vermiculite masonry fill insulation, or silicone treated perlite loose fill insulation add 2 hr to classification. 5. Foamed Plastic\* - (Optional-Not Shown) - 1-1/2 in. thick max, 4 ft wide sheathing attached to concrete blocks (Item 1).

THE DOW CHEMICAL CO - Type Thermax

\*Bearing the UL Classification Mark Reprinted from the Online Certifications Directory with permission from Underwriters Laboratories Inc. Copyright © 2006 Underwriters Laboratories Inc.®"





PIPE, CONDUIT, SLEEVE,

WIRE, OR CABLE

THE BELOW DETAIL IS A GENERIC SYSTEM SHOWN

SUBMIT THE EXACT DETAILS & SYSTEMS TO THE

ARCHITECT FOR REVIEW. ANY SYSTEMS BY THE

MAJOR MANUFACTURERS IN THE SPECIFICATION


WHICH SUIT THE EXACT SITUATION MAY BE USED.

RATING

- I HR. FIRE RATED GWB-NUMBER

OF LAYERS AS REQUIRED BY

FOR REFERENCE ONLY. THE GENERAL CONTRACTOR (AT THEIR DISCRETION) MUST





EXISTING CMU WALL

# FIRE EXTINGUISHER CABINET DETAIL (FEC)

SCALE: 1 1/2" = 1'-0"

SCALE: 1/8" = 1'-0"





ARCHITECTS INTERIORS

Atlanta Office. 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Print Record

Revisions


2013-09-23 1207007000 Sheet Title

LIFE SAFETY SHEET

Sheet No.

SCALE: 1/8" = 1'-0"

G 102




NOTE: SYMBOL SIZE SHALL BE AS SCHEDULED IN SIGN LAYOUT STROKE WIDTH TO HEIGHT RATIO SHALL BE BETWEEN

SIGN LETTERS/ NUMBERS WIDTH TO HEIGHT RATIO SHALL BE BETWEEN 1:5 &

1:5 \$ 1:10.

A. SYMBOL PROPORTIONS



1'-Ø"

OCCUPANT LOAD SIGN

SCALE: 3" = 1'-0"

REF: ADA 4.30, FIG. 30, ANSI 703.6 A990-11A

- MAX OCCUPANT LOAD,

· 1/4" RADIUS - TYP

MATTE ACRYLIC

SURFACE

(CENTERED)

W/BACKGROUND

- SIGN BACKGROUND - 1/4"

BACKGROUND COLOR TO

CORRESPONDING GRADE II BRAILLE TO BE LOCATED

SIGN COLOR TO CONTRAST

DIRECTLY UNDER THE SIGNAGE

A990-10J

CONTRAST W/ MOUNTING

PER IBC 1004.3 & ANSI AII7.1 - 703.1 REFER TO "PATH OF TRAVEL"

DIAGRAM FOR OCCUPANT LOAD





PHOTOPOLYMER, ARCHITECT TO SELECT COLOR FROM MANUFACTURER STANDARDS (TYP.)

REMOVABLE 6 1/4"x5/8" VINYL STRIP W/ 3/8" WHITE UPPERCASE HELVETICA MEDIUM

SURFACES, AND MIN (2) FH SCREWS. FOR CONC., CMU BLOCK, AND OTHER ROUGH SURFACES. A990-11G

WALL MOUNTED ROOM SIGNAGE

SCALE: 3" = 1'-0"

BACK PLATE

2 GRADE II BRAILLE

SCALE: 3" = 1'-0"

3 ACRYLIC BONDED SHEET W/ COLOR BACKGROUND

TEXT, CENTERED, AND COLOR BACKGROUND.

NOTE: MOUNT 2" FROM OPEN SIDE OF DOOR FRAME AND 60" FROM FLOOR TO CENTER

OF SIGN. FOAM TAPE AND SILICONE FOR DRYWALL, WOOD, AND OTHER SMOOTH

FRONT

PLATE

1'-0" 5QUARE

- CLEAR ACRYLIC PLASTIC

- OPAQUE WHITE ACRYLIC

PAINT BACKGROUND ON

INTERIOR FACE OF CLEAR

PLASTIC BACKING

RADIUS CORNERS


BACKGROUND COLOR


SHALL CONTRAST WITH

A990-11D

WALL COLOR


PLASTIC





# EXIT STAIR IDENTIFICATION SIGN

5. BRAILLE: GRADE II BRAILLE SHALL BE USED WHENEVER BRAILLE IS REQUIRED IN OTHER PORTIONS OF THESE STANDARDS. DOTS SHALL BE 1/10"(2.54mm) ON CENTERS IN EACH CELL WITH 241"(5.08mm) SPACE BETWEEN CELLS, MEASURED M CELL. DOTS SHALL BE RAISED A MINIMUM OF 1/4" (0635mm) ABOVE THE BACKGROUND.



A990-11C

I. CHARACTER TYPE: CHARACTERS ON SIGNS SHALL BE RAISED 1/32 "MINIMUM AND SHALL BE SANS SERIF UPPERCASE CHARACTERS ACCOMPANIED BY GRADE II BRAILLE.


SCALE: 3' = 1'-0"

- 2. CHARACTER SIZE: RAISED CHARACTERS SHALL BE A MINIMUM OF 5/8"(15.9mm) AND A MAXIMUM OF 2" (51mm) HIGH.
- 3. FINISH AND CONTRAST: CONTRAST BETWEEN CHARACTERS, SYMBOLS AND THEIR BACKGROUND MUST BE 70% MINIMUM AND HAVE A NON-GLARE FINISH.

4. PROPORTIONS: CHARACTERS ON SIGNS SHALL HAVE A WIDTH-TO-HEIGHT RATIO OF BETWEEN 3.5 AND 1:1 AND A STROKE WIDTH-TO-HEIGHT RATIO OF BETWEEN 1:5 AND 1:10. ALL LETTERS MEASURED MUST BE UPPERCASE. AFTER CHOOSING A TYPESTYLE TO TEST, BEGIN BY PRINTING THE LETTERS I, X AND O AT I INCH HIGH. PLACE THE TEMPLATE'S 1:1 SQUARE OVER THE X


OR O, WHICHEVER IS NARROWER. IF THE CHARACTER IS NOT SMALLER THAN I INCH, NOR NARROWER THAN THE 3:5 RECTANGLE TO DETERMINE IF THE STROKE OF THE I IS TOO BROAD, AND THE 1:10 RECTANGLE TO SEE IF IT IS TOO NARROW. IF ALL THE TESTS ARE PASSED, THE TYPESTYLE IS COMPLIANT WITH PROPORTION CODE.


TEMPLATE FOR CHECKING CHARACTER AND STROKE WIDTH TO HEIGHT PROPORTIONS








SCALE: NTS












SCALE: 3/8" = 1'-0"



WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Vorcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23 1207007000

Sheet Title **TYPICAL MOUNTING** HEIGHTS/ ADA

Sheet No.

G103

BE MADE DIRECTLY BY THE SURVEYOR.

MANAGEMENT AGENCY (F.E.M.A.), 3. PARTAIN ENGINEERING, LLC, ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OR COMPLETENESS OF THE SURVEY(S) REFERENCE (SEE SHEET COO5). THE INFORMATION SHOWN HEREON IS FOR INFORMATION ONLY. THE CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS AFFECTING THE WORK PRIOR TO CONSTRUCTION. ALL INTERPRETATIONS OR CLARIFICATIONS OF THE SURVEY SHALL

13113C 0108E DATED 09-26-06 AS PUBLISHED BY THE FEDERAL EMERGENCY

4. GEOTECHNICAL REPORT PREPARED BY PIEDMONT GEOTECHNICAL CONSULTANTS, INC. ENTITLED REPORT OF SUBSURFACE EXPLORATION AND GEOTECHNICAL ENGINEERING EVALUATION PROPOSED ADDITION TO EMERGENCY OPERATIONS CENTER, DATED 7-17-13. THE GEOTECHINICAL ENGINEER'S CONTACT INFORMATION IS AS FOLLOWS: P.O. BOX 1997, ROSWELL, GA 30077.

### **GENERAL NOTES**

- 1. DIRT FOR FILL SHALL BE CLEAN, COHESIVE CLAY OR SANDY CLAY FREE OF DEBRIS, ORGANICS, DELETERIOUS MATERIAL AND ROCKS GREATER THAN THREE INCHES IN DIAMETER OR AS
- 2. MAX CUT AND FILL SLOPES SHALL BE 2:1 (H: V) OR AS ALLOWED BY THE AUTHORITY HAVING JURISDICTION (AHJ).
- 3. ALL CONSTRUCTION MUST CONFORM TO ALL APPLICABLE CITY/COUNTY/STATE/FEDERAL STANDARDS AND SPECIFICATIONS.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL SITE SAFETY, MEANS AND METHODS OF COMPLETING THE WORK INCLUDING ALL REQUIRED EQUIPMENT, TESTING AND MATERIALS. THE CONSTRUCTION SHALL BE IN CONFORMANCE WITH THE PLANS AND SPECIFICATIONS.
- 5. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS NECESSARY FOR CONSTRUCTION, INCLUDING CLEARING AND DEMOLITION PERMITS. THE CONTRACTOR IS ALSO RESPONSIBLE FOR CONFIRMING THAT ALL APPROVALS HAVE BEEN OBTAINED PRIOR TO BEGINNING CONSTRUCTION.
- 6. ALL DIMENSIONS ON THESE PLANS ARE FROM FACE OF CURB, FACE OF BUILDING, CENTER OF PIPE, OR CENTER OF STRUCTURE UNLESS OTHERWISE NOTED.
- 7. ALL MANHOLE TOPS SHALL BE SET FLUSH TO GRADE IN PAVED AND LANDSCAPED AREAS UNLESS REQUIRED TO BE SET ABOVE GRADE BY THE AHJ.
- 8. EQUIPMENT AND MATERIALS SHALL BE STORED IN AREAS DESIGNATED BY THE OWNER. CONSTRUCTION AND STORAGE AREAS SHALL BE KEPT NEAT AND CLEAN. TREE SAVE AREAS SHALL NOT BE USED FOR STORAGE OR PARKING.
- 9. CONTRACTOR SHALL VERIFY THE ELEVATION OF ALL TIE-IN POINTS FOR PAVING, UTILITIES, AND
- 10. THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF ANY DISCREPANCIES BETWEEN PLAN AND FIELD CONDITIONS PROMPTLY UPON DISCOVERY.
- 11. ALL EXISTING UTILITY BOXES, WATER METER, VALVE BOXES, WHICH ARE INTENDED TO BE FLUSH WITH GRADE ARE TO BE ADJUSTED SO THAT THE ARE FLUSH WITH THE PROPOSED FINISH GRADE
- 12. CONDUITS FOR SITE LIGHTING SHALL BE INSTALLED, BACKFILLED AND PROPERLY COMPACTED PRIOR
- 13. THE CONTRACTOR SHALL NOTIFY THE CIVIL ENGINEER OF ANY DISCREPANCY BETWEEN THE CIVIL CONSTRUCTION DOCUMENTS AND/OR SPECIFICATIONS AND THE DOCUMENTS OF ANY OTHER
- 14. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING DIMENSIONS SHOWN HEREON WITH THE ARCHITECTURAL DRAWINGS AND EXISTING BUILDINGS PRIOR TO ANY CONSTRUCTION AND SHALL PROMPTLY NOTIFY THE ENGINEER OF ANY DISCREPANCY.

TO THE PLACEMENT OF BASE, PAVEMENT, AND CURB AND GUTTER.

DISCIPLINE IMMEDIATELY UPON DISCOVERY.

- 15. LANDSCAPING AND IRRIGATION TO BE COMPLETED AT THE DIRECTION OF THE OWNER/DEVELOPER.
- 16. PROPOSED SPOT ELEVATIONS ALONG CURBS ARE TO INDICATE THE PROPOSED ELEVATION OF THE
- 17. PROPOSED BUILDING LOCATIONS SHOWN ARE FOR REFERENCE ONLY BASED ON PLANS PROVIDED BY
- 18. OFF-STREET PARKING SHALL BE PROVIDED AND MAINTAINED THROUGHOUT CONSTRUCTION.
- 19. APPROVAL OF THESE PLANS IN NO WAY CONSTITUTES PERMISSION TO DISTURB WETLANDS OR
- 20. ALL BUFFERS, WETLANDS AND TREE SAVE AREAS ARE TO BE CLEARLY MARKED BY USE OF


### FLAGGING, SIGNAGE, OR FENCING BEFORE BEGINNING LAND DISTURBING ACTIVITY. SITE CLEARING & DEMOLITION NOTES

- 1. CONTRACTOR SHALL CLEARLY MARK AND MAINTAIN PROPERTY BOUNDARY MONUMENTATION AND BENCHMARKS AND BE RESPONSIBLE FOR THE COST OF REPLACING THEM IF DISTURBED OR DAMAGED
- 2. THE CONTRACTOR SHALL OBTAIN WRITTEN VERIFICATION FROM ALL UTILITY COMPANIES THAT ALL APPLICABLE UTILITIES HAVE BEEN REMOVED PRIOR TO CLEARING AND DEMOLITION.
- 3. THE CONTRACTOR SHALL PROTECT ANY UTILITY, STRUCTURE OR OTHER IMPROVEMENT THAT IS TO REMAIN AND IS RESPONSIBLE FOR ANY REPAIR COSTS FOR DAMAGE TO THEM.
- 4. UTILITIES MAY EXIST WHICH ARE NOT SHOWN ON THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES WITH UTILITIES WITHIN OR ADJACENT TO THE
- 5. ALL VEGETATION, EXISTING PAVEMENT, ORGANICS, AND UNSUITABLE BEARING SOILS SHALL BE STRIPPED FROM THE SURFACE WITH THE CONSTRUCTION LIMITS AND DISPOSED OF OFFSITE UNLESS OTHERWISE NOTED. CLEAN TOPSOIL MAY BE STOCKPILED AND REUSED LATER IN LANDSCAPED AREAS. ALL DEBRIS THAT IS HAULED OFFSITE SHALL BE DISPOSED OF AT A DISPOSAL AREA APPROVED BY THE JURISDICTION HAVING AUTHORITY FOR THE HANDLING OF DEMOLITION DEBRIS.
- 6. EXCESS TOPSOIL SHALL BE DISPOSED OFFSITE OR AS DIRECTED BY THE OWNER.
- 7. THE CONTRACTOR SHALL THE LEAVE THE SITE IN NEAT AND CLEAN CONDITION. ANY CONSTRUCTION DEBRIS OR VEGETATION SHALL BE DISPOSED OF OFFSITE.
- 8. CONTRACTOR SHALL HAVE THE LIMITS OF CLEARING AND ALL BUFFERS STAKED WITH FLAGGING TO INSURE THE PROPER LOCATION OF TREE SAVE FENCE AND PROPOSED IMPROVEMENTS.
- 9. CONTRACTOR SHALL PROTECT ALL AREAS ADJACENT TO THE LIMITS OF CLEARING AND DEMOLITION FROM DAMAGE DURING DEMOLITION. ANY OFFSITE AREAS DISTURBED SHALL BE RETURNED TO RETURNED TO A CONDITION EQUAL OR BETTER TO THE EXISTING CONDITION. NO TRESPASSING IS ALLOWED ON ADJACENT PROPERTY UNLESS WRITTEN AUTHORIZATION IS OBTAINED FROM THE
- 10. ALL STRUCTURES TO BE DEMOLISHED SHALL BE COMPLETELY REMOVED ABOVE AND BELOW GRADE. ABANDONED SERVICE LINES TO THE STRUCTURES SHALL ALSO BE REMOVED.
- 11. DISCONNECT AND SEAL OFF ABANDONED UTILITIES AND UTILITIES TO BE REMOVED PRIOR TO START OF DEMOLITION. UTILITIES SHALL BE DISCONNECTED BELOW EXISTING GRADE OR OUTSIDE OF CONTRACT LIMITS BY THE APPLICABLE PUBLIC UTILITY. ALL COSTS FOR THIS WORK SHALL BE BORNE BY THE CONTRACTOR.
- 12. CONTRACTOR SHALL FIELD-VERIFY EXACT HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING UTILITIES PRIOR TO BEGINNING SITE DEMOLITION.

# SITE CONSTRUCTION PLANS

FOR

# FAYETTE COUNTY EOC ADDITIONS/ RENOVATIONS C830 C831



# LOCATION MAP

N.T.S.

# ADDRESS:

110 VOLUNTEER WAY FAYETTEVILLE, GA 30215 L.L. 139, DIST. 5TH JURISDICTION: FAYETTE COUNTY

SITE AREA = ±30 ACRES DISTURBED AREA = ±0.46 ACRES

EXISTING SITE USE: GOVERNMENT COMPLEX PROPOSED PROJECT: ADDITION TO EXISTING BUILDING AND PARKING

SITE ZONING: R-20

PREPARED BY:



White, Georgia 30184 770.345.0589 office 770.720.2253 fax www.PartainEngineering.com

JOB NO. 13-105

remain the property of Partain Engineering, LLC and no part may

# DRAWING LIST

**COVERSHEET AND GENERAL NOTES EXISTING CONDITIONS PLAN** 

ES&PC PLAN

**DEMOLITION PLAN** SITE PLAN

**GRADING & DRAINAGE PLAN** 

UTILITY PLAN **PROFILES ESPC DETAILS ESPC DETAILS ESPC DETAILS** 

CONSTRUCTION DETAILS

COUNTY

110 Volunteer Way Fayetteville, Georgia 30215

Print Record

08/29/2013: 80% CD Set for Review Ø9/23/13: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

OWNER/DEVELOPER: **FAYETTE COUNTY EMERGENCY** 

**OPERATIONS CENTER** 140 STONEWALL AVENUE WEST FAYETTEVILLE, GA 30214

**CONTACT: THOMAS BARTLETT** 770-305-5165

Know what's **below**.

Call before you dig.

**ARCHITECT:** 

WAKEFIELD BEASLEY & ASSOCIATES

5155 PEACHTREE PARKWAY BUILDING 300, SUITE 3220

NORCROSS, GA 30092

CONTACT: JENNIFER FRANKLIN 770-209-9393

**24-HOUR EMERGENCY CONTACT:** CHERYL ROGERS 770-320-6051

WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIOR

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092

770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office:

©2013, Wakefield Beasley & Associates Architects, Inc. These drawing are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written conse of Wakefield Beasley.


12/02/13 ADDENDUMS AND CLARIFICATIONS

1207007000 2013-09-23

Sheet Title COVERSHEET AND

**GENERAL NOTES** 

C001



WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

FAYETTE COUNTY EOC


110 Volunteer Way Fayetteville, Georgia 30215


08/29/2013: 80% CD Set for Review Ø9/23/I3: RELEASE FOR BID


12/02/13 ADDENDUMS AND CLARIFICATIONS


1207007000


**EXISTING CONDITIONS PLAN** 


















STORM LINE B1-B2 SCALE: 1"=20' HOR. 1"=10' VERT.

# STORM STRUCTURE LEGEND

- 1	<u> </u>		
	ABBREVIATION DI	DESCRIPTION DROP INLET	GADOT STD NO. 1019A TYPE "A"
	нw	HEADWALL	1001B
	HOODED DI	HOODED DROP INLET	1019A TYPE "E"
	SWCB	SINGLE WING CATCH BASIN	1033D
	DWCB	DOUBLE WING CATCH BASIN	1034D
	W	WEIR INLET	1011A
	МН	STORM MANHOLE	1011A
	FES	FLARED END SECTION	1120
	SSES-C,M	SAFETY SLOPE END SECTION— C=CONCRETE, M=METAL	1122
	HW-ED	HEADWALL W/ENERGY DISSIPATION	1125
	OCB	OUTLET CONTROL STRUCTURE	

# PROFILE NOTES

- 1. STORM SEWER PIPE IS TO BE EITHER:
  1.1. CORRUGATED METAL (CMP), HELICAL, MIN. 12 GAUGE, ALUMINIZED TYPE-2, PER GADOT STD 1030D
- 1.2. REINFORCED CONCRETE (RCP), CLASS III, PER GADOT STD 1030D
- 1.3. HIGH DENSITY POLYETHYLENE (HDPE) ADVANCED DRAINAGE SYSTEMS N-12, SMOOTH/DUAL WALL CORRUGATED PIPE OR APPROVED EQUIVALENT UNLESS OTHERWISE NOTED
- 2. ALL DIMENSIONS ARE FROM CENTER OF STRUCTURE TO CENTER OF STRUCTURE. CONTRACTOR TO VERIFY ALL DIMENSIONS BEFORE ORDERING PIPES AND STRUCTURES.
- 3. ALL FILL PLACED AROUND PIPES IS TO BE COMPACTED TO 98% STANDARD PROCTOR.
- CONTRACTOR TO FIELD VERIFY ALL PROPOSED TIE—IN POINTS AND THE PRESENCE OF ANY CONFLICTS WITH OTHER UTILITIES BEFORE ORDERING MATERIALS. ANY CONFLICTS OR DISCREPANCIES BETWEEN THE PLANS AND ACTUAL FIELD CONDITIONS ARE TO IMMEDIATELY BE BROUGHT TO THE ATTENTION OF THE ENGINEER.



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



FAYETTE EOC

110 Volunteer Way Fayetteville, Georgia 30215

08/29/2013: 80% CD Set for Review 09/23/13: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

\ 12/02/13 ADDENDUMS AND CLARIFICATIONS

2013-09-23

Sheet Title

**PROFILES** 

1207007000

DRAWING PREPARED BY:

PROJECT NO. 13-105

CIVIL ENGINEERING • LAND PLANNING • CONSULTING

355 Peachtree Drive White, Georgia 30184

770.345.0589 office 770.720.2253 fax www.PartainEngineering.com

PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

SPECIES		DCAST / - PLS 2/	RESOURCE PLANTING DATES BY RESOURCE AREAS AREA 3/ PLANTING DATES								REMARKS					
	PER ACRE	PER 1000			go.	tted	lin-	es i	ndic	ate cate es.)					s	
	7.5	sq. ft.		J	F	М	Α	М	J	J	Α	s	0	N	D	
BAHIA, PENSACOLA (Paspalum notatum)			Р								••••					166,000 seed per pound. Low growing. Sod forming. Slow to
alone or with temporary cover	60 lbs	1.4 lb	С						••••		••••	•••••	••••	••••		establish. Plant with a companio crop. Will spread into bermuda pastures and lawns. Mix with
with other perennials	30 lbs	0.7 lb		J	F	м	A	м	J	J	Α	S	0	N	D	Sericea lespedeza or weeping lovegrass.
BAHIA, WILMINGTON (Paspalum notatum)			M-L													
alone or with temporary cover	60 lbs	1.4 lb	Р		ļ				••••		••••	••••	••••			Same as above
with other perennials	30 lbs	0.7 lb		J	F	м	A	м	J	J	Α	S	0	N	D	
BERMUDA, COMMON (Cynodon dactylon)			Р													1,787,000 seed per pound.
Hulled seed	10 lbs	0.2 lb	С		• •	<u> </u>			••••							Quick cover. Low growing and sod forming. Full sun.
alone with other perennials	6 lbs	0.1 lb														Good for athletic fields

DISTURBED AREA STABILIZATION

(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

TABLE 6-5.2 continued

PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

<u>SPECIES</u>		DCAST / - PLS 2/	RESOURCE AREA 3/	<u>PL</u>	<u>4N7</u>	<u>ING</u>	D/	<u>ATES</u>	: BY		SOL PLA					<u>REMARKS</u>
	PER ACRE	PER 1000 sq. ft.			do bu	tted t m	lir arg	es in ies i inal	indic dat	es.)	ре	rmi	dies	e		
LESPEDEZA SERICEA (Lespedeza cuneata) scarified	60 lbs.	1.4 lb.	M-L P C	J			<u>A</u>	M	J 	J	A	S	0	N	D	350,000 seed per pound. Widely adapted. Low maintenance. Mix with Weeping lovegrass, Common bermuda, bahia, or tall fescue. Takes 2 to 3 years to become fully established. Excellent on roadbanks. Inoculate seed with EL inoculant
unscarified	75 lbs.	1.7 lb.	M-L P C													Mix with Tall fescue or winter annuals.
seed-bearing hay	3 tons	138 lbs.	M-L P C										_			Cut when seed is mature, but before it shatters. Add Tall fescue or winter annuals.

DISTURBED AREA STABILIZATION

(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

TABLE 6-5.2 continued

PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

SPECIES	BROADCAST RATES 1/ - PLS 2	RESOURCE AREA 3/									<u>REMARKS</u>				
	PER PER ACRE 1000		(Solid lines indicate optimum dates dotted lines indicate permissible but marginal dates.)												
	sq.	ft.	J	F	М	Α	М	J	J	Α	s	0	N	D	]
BERMUDA, COMMON (Cynodon dactylon) Unhulled seed		P C													-
with temporary cover	10 lbs 0.2 l	_													Plant with winter annuals
with other perennials	6 lbs 0.1 lb	,	J	F	М	A	м	J	J	<b>A</b>	s	0	N N	D	Plant with Tall fescue
BERMUDA SPRIGS (Cynodon dactylon)	40 cu. ft 0.9 cu.	ft. M-L						ļ							A cubic foot contains approximately 650 sprigs.
Coastal, Common, Midland, or Tift 44	or sod plugs 3' x 3'														A bushel contains 1.25 cubic feet or approximately 800 sprigs.
Coastal, Common, or Tift 44		P C	ļ	ļ				<u></u>	 	ļ	ļ		ļ	ļ	Same as above
Tift 78		С													Southern Coastal Plain only
CENTIPEDE (Eremochloa ophiuroides)	Block sod only	P C													Drought tolerant. Full sun or partial shade. Effective adjacen to concrete and in concentrated
															flow areas. Irrigation is needed until fully established. Do not plant near pastures. Winterhard as far north as Athens and Atlanta.

DISTURBED AREA STABILIZATION

(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

TABLE 6-5.2 continued

PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

<u>SPECIES</u>	_	ROADCAST S 1/ – PLS 2/	RESOURCE AREA 3/	<u>PL</u>				ATES			PLA	NTIN	IG [	DAT	<u> </u>	<u>REMARKS</u>
	PER ACRE	PER 1000			do	tted	llin	es ir ies inal	indic	ate	pe	mui mis	n d sibl	late e	S	
	AONE	sq. ft.		J	F	М	Α	М	J	J	Α	S	0	N	D	]
LESPEDEZA Ambro virgata (Lespedeza virgata DC) or Appalow (Lespedeza cuneata [Dumont] G. Don) scarified unscarified	60 lbs 75 lbs	1.4 lb 1.7 lb	M-L P C M-L P C													300,000 seed per pound. Height of growth is 18 to 24 inches. Advantageous in urban areas. Spreading—type growth. New growth has bronze coloration. Mix with weeping lovegrass, common bermuda, bahia, tall fescue or winter annuals. Do not mix with Sericea lespedeza. Slow to develop solid stands. Inoculate seed with EL inoculant.
LESPEDEZA, SHRUB (Lespedeza bicolor) (Lespedeza thumbergii) plants		3' × 3'	M-L P C	J	F	м	A	м	J	J	A	S	0	- N	D	Provide wildlife food and cover
LOVEGRASS, WEEPING (Eragrostis curvula) alone with other perennials	4 lbs 2 lbs	0.1 lb 0.05 lb	M-L P C													1,500,000 seed per pound. Quick cover. Drought tolerant. Grows well with Sericea lespedeza on roadbanks

Ds3 DISTURBED AREA STABILIZATION

(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

TABLE 6-5.2 continued

PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

<u>SPECIES</u>		BROADCAST RATES 1/ - PLS 2/		PLANTING DATES BY RESOURCE AREAS PLANTING DATES									<u>REMARKS</u>			
	PER ACRE	PER 1000	(Solid lines indicate optimum dates dotted lines indicate permissible but marginal dates.)													
	ACKE	sq. ft.		J	F	М	Α	М	J	J	Α	s	0	N	D	
CROWNVETCH (Coronilla varia) with winter annuals or cool	15 lbs	0.3 lb	M-L P													100,000 seed per pound. Dense growth. Drought tolerant and fire resistant. Attractive rose, pink, and white blossoms spring to late fall. Mix with 30 pounds of Tall fescue or 15 pounds of Inoculate seed with M inoculant.
season grasses				J	F	м	Α	М	J	J	Α	s	0	N	D	Use from North Atlanta and Northward
FESCUE, TALL (Festuca arundinacea)																227,000 seed per pound. Use alone only on better sites. Not for droughty soils. Mix with perennial lespedezas or
alone	50 lbs.	1.1 lb.	M-L P				_						_::  _::			Crownvetch. Apply topdressing in spring following fall plantings.
with other perennials	30 lbs.	0.7 lb.	·	J	F	м	A	М	J	J	A	s	0	N	D	Not for heavy use areas or athletic fields.
KUDZU (Pueraria thumbergiana) plants or crowns	3' - 7	'– apart	ALL						,							Rapid and vigorous growth. Excellent in gully erosion control. Will climb. Good

Ds3 DISTURBED AREA STABILIZATION

(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

TABLE 6-5.2 continued

PLANTS, PLANTING RATES, AND PLANTING DATES FOR PERMANENT COVER

REAS DATES ates N D	<u>DAT</u> date le	r <u>ES</u>	7	REMARKS  FOR VERY WET SITES. MAY CLOG CHANNELS. DIG SPRIGS
e 	le	_		CLOG CHANNELS. DIG SPRIGS
N D	N	D		CLOG CHANNELS. DIG SPRIGS
				CLOG CHANNELS. DIG SPRIGS
				FROM LOCAL SOURCES. USE ALONG RIVER BANKS AND
	-		П	SHORELINES.
			П	GROWS WELL ON COASTAL SAND DUNES, BORROW AREAS, AND GRAVEL PITS. PROVIDES WINT
N D	N			COVER FOR WILDLIFE. MIX WI SERICEA LESPEDEZA EXCEPT ON SAND DUNES.
	<del>  '`</del>	۲	П	
				GROWS SIMILAR TO TALL
	1	FESCUE.	FESCUE.	
,				
			$\prod$	227,000 SEED PER POUND. MIX WITH WEEPING LOVEGRASS
				OR OTHER LOW-GROWING GRASSES OR LEGUMES.
		_	<u> </u>	

Ds3 DISTURBED AREA STABILIZATION

(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office:

208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

FAYETTE

110 Volunteer Way Fayetteville, Georgia 30215

Print Record

08/29/2013: 80% CD Set for Review 09/23/13: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions 12/02/13 ADDENDUMS AND CLARIFICATIONS



PROJECT NO. 13-105

355 Peachtree Drive White, Georgia 30184 770.345.0589 office 770.720.2253 fax www.PartainEngineering.com

ESPC DETAILS

2013-09-23 Sheet Title

Sheet No.

C800

1207007000

TYPE OF SPECIES	YEAR	ANALYSIS OR EQUIVALENT N-P-K	RATE	N TOP DRESSING RATE
. COOL SEASON GRASSES	FIRST SECOND MAINTENANCE	6-12-12 6-12-12 10-10-10	1500 lbs./ac. 1000 lbs./ac. 400 lbs./ac.	50-100 lbs./ac. 1/ 2/ 
. COOL SEASON GRASSES AND LEGUMES	FIRST SECOND MAINTENANCE	6-12-12 0-10-10 0-10-10	1500 lbs./ac. 1000 lbs./ac. 400 lbs./ac.	0-50 lbs./ac. 1/  
. GROUND COVERS	FIRST SECOND MAINTENANCE	10-10-10 10-10-10 10-10-10	1300 lbs./ac. 3/ 1300 lbs./ac. 3/ 1100 lbs./ac.	=======================================
. PINE SEEDLINGS	FIRST	20–10–5	one 21—gram pellet per seedling placed in the closing hole	
. SHRUB LESPEDEZA	FIRST MAINTENANCE	0-10-10 0-10-10	700 lbs./ac. 700 lbs./ac. 4/	
. TEMPORARY COVER CROPS SEEDED ALONE	FIRST	10–10–10	500 lbs./ac.	30 lbs./ac. 5/
. WARM SEASON GRASSES	FIRST SECOND MAINTENANCE	6-12-12 6-12-12 10-10-10	1500 lbs./ac. 800 lbs./ac. 400 lbs./ac.	50-100 lbs./ac. 2/ 6, 50-100 lbs./ac. 2/ 30 lbs./ac.
. WARM SEASON GRASSES AND LEGUMES	FIRST SECOND MAINTENANCE	6-12-12 0-10-10 0-10-10	1500 lbs./ac. 1000 lbs./ac. 400 lbs./ac.	50 lbs./ac. 6/


- 1/ APPLY IN SPRING FOLLOWING SEEDING.
  2/ APPLY IN SPLIT APPLICATIONS WHEN HIGH RATES ARE USED.
- APPLY IN 3 SPLIT APPLICATIONS. 4/ APPLY WHEN PLANTS ARE PRUNED.
- APPLY TO GRASS SPECIES ONLY.
  APPLY WHEN PLANTS GROW TO A HEIGHT OF 2 TO 4 INCHES.




# DISTURBED AREA STABILIZATION


(WITH PERMANENT VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.









SLOTTED BOARD DAM WITH STONE FILTER

SLOTTED BOARD DAM W/ STONE

SPECIES	BNOA	DCAST	RESOURCE	PLANTING DATES REMARI		REMARKS												
		/ - PLS 3/	AREA 4/	(SC	DLID TTEI	LIN	<b>NES</b>	IN	DIC	ATE	F I	PTI	MUI	M I	DA1	ES,		
	PER ACRE	PER 1000 S.F.		BU	ТМ	ARC	GIN/	AL	DA.	TES.	.)					_		
				J	F	М	4	М	1	1	4	3	0	N	٦			
BARLEY (Hordeum vulgare)			M-L											••••			14,000 SEED PER POUND.	
ALONE	144 LBS.	3.3 LBS.	C														WINTERHARDY. USE ON PRODUCTIVE SOILS.	
IN MIXTURES	24 LBS.	0.6 LBS.		J	F	м	<u> </u>	м	J	J	<u>,</u>	s	0	N	D			
LESPEDEZA, ANNUĄL			M-L			_												
(Lespedeza striata)			Р														200,000 SEED PER POUND. MAY	
ALONE	40 LBS.	0.9 LBS.	С		$\dashv$												VOLUNTEER FOR SEVERAL YEARS. USE INOCULANT EL.	
IN MIXTURES	10 LBS.	0.2 LBS.		J	F	м	A	м	J	J	A	s	0	N	D			
LOVEGRASS, WEEPING			M-L				+											
(Eragrostis curvula)	A LDC	0.1 1.00	Р				$\dashv$	⊢									1,500,000 SEED PER POUND. MAY LAST FOR SEVERAL YEARS. MIX	
ALONE IN MIXTURES	4 LBS. 2 LBS.	0.1 LBS.	С		-	$\dashv$	$\dashv$	$\dashv$									WITH SERICEA LESPEDEZA	
III MILATURES	Z LBS.	0.05 LBS.		J	F	м	A	м	J	J	A	s	0	N	D			
MILLET, BROWNTOP (Panicum fasciculatum)			M-L			-	-+	$\dashv$	-:-								137,000 SEED PER POUND.	
ALONE	40 LBS.	0.9 LBS.	P C														QUICK DENSE COVER. WILL PROVIDE TOO MUCH COMPETITION	
IN MIXTURES	10 LBS.	0.2 LBS.			F	M	^	М					^	N	_		IN MIXTURES IF SEEDED AT HIGH RATES.	
MILLET, PEARL			M-L		Г	M	^		٦		$\stackrel{\wedge}{\parallel}$	3		IN				
(Pennesetum glaucum)			P P					_		_ .							88,000 SEED PER POUND. QUICK, DENSE COVER. MAY	
ALONE	50 LBS.	1.1 LBS.	С			-	-+	$\dashv$	$\dashv$	$\dashv$							REACH 5 FEET IN HEIGHT. NOT RECOMMENDED FOR MIXTURES.	
				J	F	м	A	м	J	J	A	s	0	N	D		THEODIMINETIPES FOR MINITORES.	
OATS (Avena sativa)			M-L											<u> </u>			13,000 SEED PER POUND. USE ON PRODUCTIVE SOILS. NOT AS WINTERHARDY AS RYE OR BARLEY.	
ALONE	128 LBS.	2.9 LBS.	P .								İ	"+		<b></b> ··				
IN MIXTURES	32 LBS.	0.7 LBS.	С											<b></b>				
				J	F	М	<u> </u>	М	J	J	<u> </u>	S	0	N	D			
RYE (Secale cereale)			M-L P											•••••	<u> </u>			
ALONE	168 LBS.	3.9 LBS.	C														18,000 SEED PER POUND. QUICK COVER. DROUGHT TOLERANT	
IN MIXTURES	28 LBS.	0.6 LBS.															AND WINTERHARDY.	
RYEGRASS, ANNUAL			M-L						1	1.					ļ			
(Lolium temulentum)	40 150	0.0.1.00	Р							-	<u> </u>	$\dashv$			├		227,000 SEED PER POUND. DENSE COVER. VERY COMPETITIVE	
ALONE	40 LBS.	0.9 LBS.	С														AND IS <u>NOT</u> TO BE USED IN	
				J	F	м	A	м	J	J	A	s	0	N	D		MIXTURES.	
SUDANGRASS			M-L			-		$\dashv$	$\dashv$								55,000 SEED PER POUND. GOOD	
(Sorghum sudanese)			P			-		$\dashv$	$\dashv$								ON DROUGHTY SITES. NOT RECOMMENDED FOR MIXTURES.	
ALONE	60 LBS.	1.4 LBS.	С		<u> </u>	""    	寸			╗					_		RECOMMENDED FOR MIXIURES.	
TRITICALE				J	F	M	<u> </u>	M	J	J	<u>A</u>	3	U	N	ח			
(X-Triticosecale)			С									]			L.		USE ON LOWER PART OF SOUTHE COASTAL PLAIN AND IN ATLANTIC	
ALONE	144 LBS.	3.3 LBS.															COASTAL FLATWOODS ONLY.	
IN MIXTURES	24 LBS.	0.6 LBS.		J	F	м	A	м	J	J	A	s	0	N	D			
WHEAT			M-L												ļ			
(Triticum aestivum)  ALONE	180 150	4.1 LDC	Р												+		15,000 SEED PER POUND.	
ALUNE !	180 LBS.	4.1 LBS.	C				- 1		- 1		- 1				⊢	4 l	15,000 SEED PER POUND.   WINTERHARDY.	

- 1/ TEMPORARY COVER CROPS ARE VERY COMPETITIVE AND WILL CROWN OUT PERENNIALS IF SEEDED TOO HEAVILY.
- 2/ REDUCE SEEDING RATES BY 50% WHEN DRILLED.
- 3/ PLS IS AN ABBREVIATION FOR PURE LIVE SEED.
- 4/ M-L REPRESENTS TO MOUNTAIN; BLUE RIDGE; AND RIDGES AND VALLEYS MLRA'S P REPRESENTS THE SOUTHERN PIEDMONT MLRA
- C REPRESENTS THE SOUTHERN COASTAL PLAIN; SAND HILLS; BLACK LANDS; AND ATLANTIC COAST FLATWOODS MLRAS



# DISTURBED AREA STABILIZATION

(WITH TEMPORARY VEGETATION)

REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.

WAKEFIELD Beasley & ASSOCIATES

# ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office:

208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

FAYETTE

110 Volunteer Way Fayetteville, Georgia 30215

Print Record

08/29/2013: 80% CD Set for Review 09/23/13: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Revisions \ 12/02/13 ADDENDUMS AND CLARIFICATIONS

2013-09-23

1207007000


Sheet Title

ESPC DETAILS


Sheet No.

C801

PROJECT NO. 13-105 DRAWING PREPARED BY: CIVIL ENGINEERING • LAND PLANNING • CONSULTING 355 Peachtree Drive White, Georgia 30184 770.345.0589 office 770.720.2253 fax www.PartainEngineering.com





PROPER PLACEMENT OF STRAW BALE BARRIER IN DRAINAGE WAY



CROSS-SECTION OF A PROPERLY INSTALLED STRAW BALE








ANCHORING DETAIL


Anchor and embed into soil to prevent washout or water working under barrier
 Repair or replacement must be made promptly as needed




REFER TO THE "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" FOR FURTHER DETAILS AND SPECIFICATIONS NOT SHOWN HERE.



SILT FENCE TYPE C





MATTING AND BLANKETS





ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215

Print Record

08/29/2013: 80% CD Set for Review 09/23/13: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION


Revisions

\ 12/02/13 ADDENDUMS AND CLARIFICATIONS

2013-09-23

1207007000

ESPC DETAILS



Wakefield Beasley & associates

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

770 209 7050 FAX

Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE



FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215

©2013, Wakefield Beasley & Associates Architects, Inc. These d are protected by the copyright laws of the United States. The drawings or any part thereof may not be used for any purpos reproduced in any form or by any means without the written of Watefield Register.

Print Record

08/29/2013: 80% CD Set for Review
09/23/13: RELEASE FOR BID
12/02/13 FOR CONSTRUCTION

12/02/13 ADDENDUMS AND CLARIFICATIONS

Date 2013-09-23

Sheet Title

CONSTRUCTION


Sheet No.

355 Peachtree Drive White, Georgia 30184

770.345.0589 office 770.720.2253 fax www.PartainEngineering.com

C830

1207007000



WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215

Print Record

09/23/13: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION


12/02/13 ADDENDUMS AND CLARIFICATIONS

770.345.0589 office 770.720.2253 fax www.PartainEngineering.com

CONSTRUCTION **DETAILS** 

1207007000

C831





I. CONTRACTOR SHALL COMPLY WITH ALL APPLICABLE CODES AND ORDINANCES REGARDING LANDSCAPING.

2. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO INSTALL HEALTHY SOD AND/OR ESTABLISH A HEALTHY STAND OF GRASS ON ALL SEEDED AREAS. 3. ALL PLANTING BEDS AND MULCH: CONTRACTOR SHALL APPLY PRE-EMERGENT TO PREVENT WEED GROWTH.

4. CONTRACTOR SHALL BE RESPONSIBLE FOR THE WATERING AND THE MAINTENANCE OF ALL LANDSCAPED AREAS PER AGREEMENT WITH OWNER. 5. LANDSCAPE CONTRACTOR TO CLEAN ENTIRE SITE OF ALL LANDSCAPING DEBRIS WHEN INSTALLATION IS COMPLETED 6. LANDSCAPE CONTRACTOR RESPONSIBLE FOR LOCATING ALL UTILITIES

PRIOR TO BEGINNING INSTALLATION. 7. LANDSCAPE CONTRACTOR TO PROVIDE PLANTS TRUE TO SPECIES AND VARIETY, PER PLANT LIST. ACCEPTANCE OF PLANT MATERIAL SUBJECT TO 8. STAKING MATERIALS SHOULD BE REMOVED WITHIN ONE YEAR OF

9. BURLAP AND ALL OTHER MATERIALS MUST BE REMOVED FROM AT LEAST THE TOP 1 / 3 OF THE ROOTBALL AND THE TREE SHOULD BE PLANTED SO THAT THE TRUNK FLARE IS VISIBLE ABOVE THE GROUND. IO. PLANTED TREES SHOULD BE IMMEDIATELY MULCHED AFTER PLANTING. MULCH IS NOT ALLOWED CLOSER THAN 6" TO THE TRUNK FLARE.







ARCHITECTS INTERIORS

FAYETTE

COUNTY

110 Volunteer Way


Fayetteville, Georgia


30215


Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

#### QTY COMMON NAME BOTANICAL NAMESIZE TDU Lagerstroemia indica 10' ht. min. (3) 1"canes 1.5 llex opaca 'Greenleaf' 10' ht. min (2"cal.) Holly Trees total 24" @ ınstall Switchgrass Panicum virgatum 3 gal. 'Shenandoah 'Shenandoah' Rosa spp. 'Knockout' 'Knockout' Rose 24" @ ınstall 3 gal. 'Purple Pixie' Loropetalum chinense 24" @ ınstall 'Purple Pixie' Loropetalum 'Shamrock' Ilex glabra 24" @ ınstall 'Shamrock' Inkberry Dwf. Indian Raphiolepis indica 24" @ install Hawthorn 41 Dwf. Yaupon Holly Ilex vomitoria 'nana' Full in pot, healthy 20 Black Eyed Susan Rudbekia spp. Full in pot, healthy Relocate existing Japanese maple as shown. Contractor to verify method and fee for transplanting tree with owner for approval prior to construction TBD Tifway 419 Cynodon dactylon Contractor to quantify sod totals for Owner approval or equal prior to construction ALL TREES TO HAVE STRAIGHT SINGLE LEADER WITH GOOD FULL FORM - HEALTHY ALL SHRUBS TO BE FULL IN POTS, GOOD FORM, HEALTHY ALL SOD TO BE HEALTHY AND INSTALLED PER INDUSTRY STANDARD PRACTICE IRRIGATION INSTALLATION TO BE DESIGN BUILD BY LANDSCAPE CONTRACTOR








\*\*\*LANDSCAPE CONTRACTOR TO PROVIDE PRICE FOR RELOCATING EXISTING JAPANESE MAPLE WITH TREE SPADE PRICE TO INCLUDE:

AND WILL TAKE INTO ACCOUNT ALL TREE & SHRUB HEIGHTS AND LOCATIONS

- USING TREE SPADE OF APPROPRIATE SIZE FOR EXISTING ROOTBALL
- MOVING TREE DIRECTLY FROM EXISTING LOCATION TO NEW LOCATION (I.E. TREE WILL NOT BE HEELED IN ON SITE OR TEMPORARILY STORED, BUT WILL BE IMMEDIATELY TRANSFERRED FROM EXISTING LOCATION TO AN EXISTING HOLE IN THE NEW LOCATION
- WATERING AND MAINTENANCE AS NEEDED UNTIL PROJECT IS ACCEPTED BY COUNTY



# **UTILITY DISCLAIMER**

UTILITIES MAY EXIST WHICH ARE NOT SHOWN ON THESE PLANS. THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL UTILITY COMPANIES HAVING UTILITIES ADJACENT TO OR WITHIN THE WORK AREA. THE CONTRACTOR SHALL HAVE THE UTILITIES FIELD LOCATED AND COORDINATE WITH UTILITY COMPANIES TO HAVE THEM RELOCATED WHEN NECESSARY FOR



Call before you dig.

24 HOUR EMERGENCY CONTACT CHERYL ROGERS 770-320-605

Revisions

©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review


09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Date Job No. 2013-09-23 1207007000 Sheet Title

FOUNDATION LANDSCAPE PLAN - ALTERNATE #1

Sheet No.



WAKEFIELD BEASLEY & ASSOCIATES

FAYETTE COUNTY

110 Volunteer May Fayetteville, Georgia



 $\hat{\underline{\ \ \ }}$  12/02/13 ADDENDUMS AND CLARIFICATIONS

1207007000

**ARCHITECTURAL** 

A-000

- CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND CONDITIONS SHOWN ON THE DRAWINGS AND IMMEDIATELY NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO ORDERING OR FABRICATING MATERIALS OR OTHERWISE PROCEEDING WITH THE WORK.
- 3. PROVIDE LABOR, MATERIAL, EQUIPMENT AND SERVICES
  REQUIRED TO EXECUTE AND COMPLETE ALL ITEMS OF WORK
  AS SHOWN OR INDICATED ON THE DRAWINGS AND AS
  SPECIFIED, INCLUDING INCIDENTAL ITEMS TO EFFECT A
  FINISHED AND COMPLETE JOB, EVEN THOUGH SUCH ITEMS ARE
  NOT SHOWN OR PARTICULARLY MENTIONED.
- 4. MAINTAIN PREMISES AND PUBLIC PROPERTIES FREE FROM ACCUMULATIONS OR WASTE MATERIALS, DEBRIS AND RUBBISH CAUSED BY CONSTRUCTION OPERATIONS. PERFORM DAILY CLEANUP.
- 5. CONTRACTOR SHALL BE COMPLETELY RESPONSIBLE FOR BRACING. AND SHORING OF THE STRUCTURE DURING CONSTRUCTION TO ENSURE STABILITY.
- 6. THE CONTRACTOR SHALL RESTORE TO ITS ORIGINAL CONDITION AND QUALITY (AS APPROVED BY THE ARCHITECT, ENGINEER, UTILITY REPRESENTATIVE AND/OR APPLICABLE OWNER REPRESENTATIVE) ALL SITE APPURTENANCES DAMAGED AT NO ADDITIONAL COST TO THE OWNER.
- CONTRACTOR TO SAW CUT WALLS AND FLOORS AT TRANSITIONS OF SCHEDULED DEMOLITION TO PROVIDED A CLEAN EDGE FOR FUTURE WORK...
- NOTIFY ARCHITECT IMMEDIATELY UPON DISCOVERING ANY UNFORESEEN "UNKNOWNS", FOR FURTHER DIRECTION PRIOR TO PROCEEDING WITH FURTHER WORK.
- 9. AFTER COMPLETION OF WORK, DEMOLITION AND ALL NEW ADDITIONAL MATERIALS REMAINING DUE TO CONSTRUCTION (UNLESS NOTED OTHERWISE IN DIAGS OR SPECIFICATIONS) SHALL BECOME THE PROPERTY OF THE GENERAL CONTRACTOR AND SHALL BE DISPOSED OF/REMOVED FROM THE SITE IN ACCORDANCE WITH ALL APPLICABLE LAWS, ORDINANCES, RULES, AND REGULATIONS UNLESS NOTIFIED OTHERWISE (INCLUDING BUT NOT LIMITED TO SURPLUS STOCK MATERIALS FOR FUTURE REPLACEMENTS SUCH AS PAINT, TILES, ETC.) CONTRACTOR SHALL ALSO REMOVE ALL WASTE DEBRIS, RUBBISH, TOOLS, AND EQUIPMENT UPON COMPLETION OF WORK, THROUGHOUT CONSTRUCTION, SITE SHALL BE ORGANIZED AND CLEANED BY CONTRACTOR ON A DAILY
- 10. RELOCATE ANY AND ALL EXISTING UTILITIES IN AFFECTED DEMOLITION SCHEDULED TO BE REUSED TO AREAS SCHEDULED AS NEW OR REMAINING ADJACENT AREAS.
- II. CONTRACTOR SHALL PROTECT ALL PORTIONS SCHEDULED TO REMAIN / NOT SCHEDULED FOR DEMOLITION. CONTRACTOR SHALL REPAIR/REPLACE ANY AND ALL DAMAGED OR REMOVED ENTITIES NOT SCHEDULED FOR DEMOLITION TO IT'S ORIGINAL CONDITION AT NO COST TO THE OWNER.
- 12. CONTRACTOR TO PROVIDE TEMP WALLS AND/OR DUST BARRIERS TO ISOLATE WORK FROM OPERATIONAL AREAS OF THE BUILDING, COORDINATE WITH OWNER.
- 13. PROTECT ALL AREAS SCHEDULED TO REMAIN. CONTRACTOR
  SHALL RESTORE ANY AND ALL DAMAGED AREAS SCHEDULED
  TO REMAIN THRU DEMOLITION AND CONSTRUCTION PHASES TO
  ORIGINAL LIKE NEW CONDITION.
- 14. REFER TO ENGINEERS DEMOLITION SHEETS FOR BALANCE OF
- 15. REUSE/CLEAN ANY DEMOLISHED CMU AS NEEDED FOR WALL REPAIR & NEW CMU WALL INFILL AREAS.
- I6. GC TO PROVIDE SECURED CONSTRUCTION SITE DURING DEMOLITION AND CONSTRUCTION TO PREVENT ANY/ALL PUBLIC ACCESS. SITE WILL BE SECURED WITH PADLOCK AND KEY
- 17. THE EXISTING FACILITY IS "ESSENTIAL" TO GOVERNMENT SERVICES AND MUST REMAIN OPERATIONAL WITHOUT INTERRUPTION THROUGHOUT THE ENTIRETY OF THE CONSTRUCTION PROCESS.
- 18. THE GC MUST INSURE CONTINUED, SAFE ACCESS TO AND FROM THE EXISTING STRUCTURE.
- 19. ANY CONSTRUCTION ACTIVITIES INCLUDING BUT NOT LIMITED TO DISRUPTION OF UTILITIES, EXCESSIVE NOISE, EXCESSIVE DUST & DEBRIS, DELIVERIES OF MATERIALS, ETC., WHICH MAY INTERFERE WITH THE DAILY OPERATIONS OF THE EXISTING FACILITY, MUST BE COORDINATED WITH THE OWNER'S REPRESENTATIVE A MINIMUM OF 48 HOURS PRIOR TO THE START OF SAID "CONSTRUCTION ACTIVITIES".

DEMO PLAN NOTES:

- DEMO EXISTING VESTIBULE IN ITS ENTIRETY INCLUDING STOREFRONT WINDOWS, DOOR & FRAME, CMU COLUMN WRAP, STEEL COLUMN, CONCRETE SLAB, CONCRETE FOOTING, METAL ROOF, ROOF FLASHING, AND CEILING AS INDICATED. CLEAN & REPAIR ADJACENT CMU TO REMAIN AS NEEDED TO CREATE A UNIFORM APPEARANCE.
- 2 DEMO PORTION OF CONCRETE SIDEWALK AS INDICATED REFER TO CIVIL DRAWINGS.
- DEMO PORTION OF CONCRETE CURB & GUTTER AS INDICATED REFER TO CIVIL DRAWINGS.
- DEMO PORTION OF ASPHALT PAVEMENT AS INDICATED REFER TO CIVIL DRAWINGS.
- 5> SAW-CUT & DEMO PORTION OF CMU PILASTER AS INDICATED. CLEAN & REPAIR CMU AS NEEDED TO RECEIVE NEW EXPANSION JOINT SYSTEM.
- OPENING TO RECEIVE NEW CMU INFILL WITH METAL STUDS & GYP. BD. TO MATCH ADJACENT SURFACES.
- PREP. 4 REPAIR EXISTING WALL 4 ADJACENT FINISHES TO RECEIVE NEW WORK.
- DEMO NEW OPENING FOR NEW DOOR, REFER TO STRUCTURE FOR LINTEL SIZE, SEE CONSTRUCTION PLAN.

9 DEMO NEW OPENING FOR TRANSACTION DRAWER BELOW

- EXISTING WINDOW TO REMAIN. COORDINATE WITH NEW WORK.

  DEMO PORTION OF EXISTING CMU COLUMN WRAP. CLEAN,
- REPAIR, & SAVE CMU AS NEEDED FOR NEW CMU PILASTER.
  COORDINATE WITH NEW WORK.
- EXISTING STEEL COLUMN & CONCRETE FOOTING TO REMAIN.


  PREPARE TO RECEIVE NEW WORK.
- (12) EXISTING PAD MOUNTED GENERATOR & TRANSFORMER TO REMAIN.
- EXISTING CONCRETE SIDEWALK TO REMAIN COORDINATE WITH CIVIL 4 NEW WORK.
- (14) EXISTING AREA TO REMAIN UNDISTURBED

DEMOLISH
TO REMAIN

TO REMAIN

DEMOLISH DOOR AND FRAME

DOOR AND FRAME TO REMAIN







ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX
Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

01/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Revisions

1207007000

DEMOLITION

Sheet No.

SCALE: 1/8" = 1'-0"

2013-09-23

Sheet Title

A-100

# 2009 IECC

## Section 1: Project Information

# Project Type: **Addition**Project Title: Fayette County EOC Addition

Construction Site: 110 Volunteer Way Fayetteville, GA 30215

Owner/Agent: Thomas Bartlett Fayette County 140 Stonewall Avenue West Fayetteville, GA 30215 770-305-5165

Designer/Contractor:
Jennifer Franklin
Wakefield Beasley & Associates
5155 Peachtree Parkway
Building300, Suite 3220
Norcross, GA 30092
770-209-9393
jfranklin@wbassociates.com

### Section 2: General Information

Building Location (for weather data):
Climate Zone:
Building Space Conditioning Type(s):
Vertical Glazing / Wall Area Pct.:

Activity Type(s)
Police/Fire Station

Fayetteville, Georgia
3a
Nonresidential
6%

Floor Area
4166

#### Section 3: Requirements Checklist

#### Envelope PASSES: Design 1% better than coo

#### Climate-Specific Requirements:

Component Name/Description	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U-Factor(a)
Roof 1: Insulation Entirely Above Deck	4166		20.0	0.048	0.048
Exterior Wall 1: Concrete Block:8", Solid Grouted,Medium Density , Furring: Metal	3546	0.0	13.0	0.062	0.123
Window 1: Metal Frame Curtain Wall/Storefront:Double Pane with Low-E, Clear, SHGC 0.36, PF 0.33	157		-	1.300	0.600
Door 1: Glass (> 50% glazing):Metal Frame, Entrance Door, SHGC 0.36, PF 0.33	42			1.300	0.900
Floor 1: Slab-On-Grade:Unheated, Horizontal with vertical 2 ft.	3546		10.0		

#### (a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.

- Air Leakage, Component Certification, and Vapor Retarder Requirements:

  1. All joints and penetrations are caulked, gasketed or covered with a moisture vapor-permeable wrapping material installed in accordance
- with the manufacturer's installation instructions.
- 2. Windows, doors, and skylights certified as meeting leakage requirements.
   3. Component R-values & U-factors labeled as certified.
- 4. No roof insulation is installed on a suspended ceiling with removable ceiling panels.
   5. 'Other' components have supporting documentation for proposed U-Factors.
- 6. Insulation installed according to manufacturer's instructions, in substantial contact with the surface being insulated, and in a manner that achieves the rated R-value without compressing the insulation.

Project Title: Fayette County EOC Addition Report date: 09/20/13

Data filename: I:\Municipal\Municipal\Municipal Studio\03 Projects\2012\1207007000 - Fayette County EOC\1-PROJECT\_DATA\Project

Criteria\ComCheck Report for Envelope.cck Page 1 of 2

7. Stair, elevator shaft vents, and other outdoor air intake and exhaust openings in the building envelope are equipped with motorized

- dampers.

  B. Cargo doors and loading dock doors are weather sealed.
- 8. Cargo doors and loading dock doors are weather sealed.
   9. Recessed lighting fixtures installed in the building envelope are Type IC rated as meeting ASTM E283, are sealed with gasket or caulk.
   10.Building entrance doors have a vestibule equipped with self-closing devices.
  - =xceptions: □ Building entrances with revolving doors...
  - Building entrances with revolving doors.Doors not intended to be used as a building entrance.
  - ☐ Doors that open directly from a space less than 3000 sq. ft. in area.
- ☐ Doors used primarily to facilitate vehicular movement or materials handling and adjacent personnel doors.
- Doors opening directly from a sleeping/dwelling unit.

# Section 4: Compliance Statement


Project Title: Fayette County EOC Addition

Criteria\ComCheck Report for Envelope.cck

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed envelope system has been designed to meet the 2009 IECC requirements in COMcheck Version 3.9.2 and to comply with the mandatory requirements in the Requirements Checklist.

Name - Title Signature Date

Data filename: I:\Municipal\Municipal Studio\03 Projects\2012\1207007000 - Fayette County EOC\1-PROJECT\_DATA\Project





ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX
Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



are pro	tected by	the copy	k Associates ight laws of of may not	f the United	States. Th	nese
reprodu		ıy form or	by any me			

Print Record

07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Revisions

Date 2013-09-23

Sheet Title


1207007000

DIMENSION FLOOR PLAN

Sheet No.

SCALE: 1/8" = 1'-0"

A-101



SCALE: 1/8" = 1'-0"

INTERIOR & EXTERIOR WALL TYPES



ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX
Jacksonville Office

Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

Date 2013-09-23

Sheet Title


Job No. 12*0*7007000


REFERENCE FLOOR PLAN

Sheet No.

SCALE: 1/8" = 1'-0"


A-102





SOFFIT DETAIL

SCALE: 1" = 1'-0"



# SOFFIT DETAIL

SCALE: 1" = 1'-0"

ITEM	SYMBOL	R.C.P. LEGEND  DESCRIPTION
A		2X4 LIGHT FIXTURE
В	¤	DECORATIVE PENDANT (ENTRY VESTIBULE)
С	0	CAN LIGHT FIXTURE (WET LOCATION)
D		LINEAR PENDANT
F		UTILITY LINEAR PENDANT
G	>0	DIRECTIONAL LIGHTING (@ MARKER BOARD)
Н	Ю	EXTERIOR SCONCE
K		STRIP LIGHT

LOCATIONS ONLY FOR MEP ITEMS - REFER TO ENGINEERING DWGS. FOR MORE INFO. CEILING TYPE SCHEDULE


2'x2' ACOUSTICAL PANEL CEILING MARS CLIMAPLUS 2X2 REVEAL EDGE W/ 9/16 "DXF GRID SYSTEM OR APPROVED EQUAL.


EXPOSED TO UNDERSIDE OF DECK ABOVE 5/8" GYPSUM BOARD - APPLY TO FRAMING AT HEIGHT GYP. I SPECIFIED ON RCP.

GYP. 2 5/8" MOISTURE RESISTANT GYPSUM BOARD - APPLY TO FRAMING AT HEIGHT SPECIFIED ON RCP.


# R.C.P. GENERAL NOTES

- ALL CEILINGS 10'-0" ACT UNLESS NOTED OTHERWISE CENTER CEILING GRID EACH WAY IN ALL CORRIDORS AND IN EACH ROOM WITH LAY-IN CEILINGS UN.O. - RE: PLAN FOR ADDITIONAL
- CENTER ALL INTERIOR DOWN LIGHTS IN CEILING TILES AND IN ROOM WITHOUT TILES UN.O.- REFER TO PLAN FOR ADDITIONAL INFORMATION
- REFER TO ROOM FINISH SCHEDULE FOR ADDITIONAL
- INFORMATION/REQUIREMENTS
- . INSTALL ALL CEILING SYSTEMS PER MANUFACTURER'S RECOMMENDATIONS.
- PROVIDE SOUND ATTENUATION BATTS ON TOP OF ACT CEILINGS UNLESS











ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©20	13, Wake	efield Be	asley &	: Associ	ates Ar	chitects,	Inc.	These	drawin
		d by the							
		any par							
repro	oduced i	n any fo	orm or	by any	means	s without	t the	writter	n conse
of W	/akefield	Beasley.							

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION


Revisions

2013-09-23 1207007000

REFLECTED **CEILING PLAN** 

Sheet No.

A-103



WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23 1207007000

**ROOF PLAN** 


Sheet No.

A-104

PL-1	MANUFACTURER: PRODUCT/COLOR:		
PL-2	MANUFACTURER:	NEVAMAR GRAND ISLE MAPEL W837117	
	TILE		
T-I	FIELD TILE MANUFACTURER: PRODUCT/COLOR: SIZE/GROUT:	DALTILE HEATHLAND, EDGEWOOD HLØ4 12×12/TBD	
T-2	TILE BASE MANUFACTURER: PRODUCT/COLOR: SIZE/GROUT:	DALTILE HEATHLAND, EDGEWOOD HLØ4 6X12 COVE BASE,/TBD	
Ť-3	ACCENT TILE MANUFACTURER: PRODUCT/COLOR: SIZE/GROUT:	DALTILE HEATHLAND, EDGEWOOD HLØ4 2x2 MO6AIC/TBD	
	ACOUSTICAL CEILING	PANELS	
ACT-I	MANUFACTURER: PRODUCT/COLOR:  SIZE/GRID:		
	RESILIENT BASE		
VB-I	MANUFACTURER: PRODUCT/COLOR: SIZE:		
	TILE CARPETING		
CPT-I	MANUFACTURER: PRODUCT/COLOR:	JULIE INDUSTRIES STATIC SMART, PRESIDENTIAL SERIES, ROOSEVELT	
CPT-2		PATCRAFT *10117 DON'T RUN *00118 BLACK	
	PAINTS		
<del>P</del> 1-1		BENJAMIN MOORE SHAKER BEIGE HC-45 MATCH EXISTING	
<del>P</del> T-2	ACCENT PAINT MANUFACTURER: COLOR: FINISH:	BENJAMIN MOORE DEUSEN BLUE HC-156 MATCH EXISTING	
PT-3	ACCENT PAINT MANUFACTURER: COLOR/FINISH: FINISH:	SHERWIN WILLIAMS SW 2823 ROOKWOOD CLAY MATCH EXISTING	
<del>P</del> T-4	TRIM PAINT MANUFACTURER: COLOR/FINISH:	MATCH EXISTING MATCH EXISTING	
	SOLID SURFACE COUN	TERTOPS	
<del>5</del> 6-1	MANUFACTURER: PRODUCT/COLOR:	LG HAUSYS HI MACS, VOLCANICS, AMBERGLOW VEII	
	MARKER BOARDS		
MB-1	MANUFACTURER: PRODUCT/COLOR:  STYLE/SIZE:	CLARIDGE LC6 PORCELAIN ENAMEL 6TEEL MARKERBOARD, NO. 32 WHITE 6ERIEG 3, TYPE A, 4'HXII'W (TOP MOUNTED T'-0"AFF)	
	SEALED CONCRETE		
CONC-I	MANUFACTURER: PRODUCT/COLOR:	TBD HIGH PERFORMANCE, NON-YELLOWING, CLEAR ACRYLIC-BASED SEALER PER MANUFACTURERS INSTRUCTIONS	
	KEY L	EGEND	
<del></del>	XX	FINISH E FINISH	

FINI	SH PLAN GENERAL NOTES:
1.	ALL ROOMS TO RECEIVE, PT-1, VB-1, AND CPT-1 ON AS INDICATED IN SCHEDULE UNLESS NOTED OTHERWISE
2.	INSTALL PRODUCTS AND EQUIPMENT PER MANUFACTURES INSTALLATION REQUIREMENTS PROVIDE STANDARD MANUFACTURER WARRANTIES
3.	SEE ROOM FINISH SCHEDULE FOR WALL FINISHES BY ROOM

ROOM	ROOM NAME	FL:	20R	BASE		WALL	REMARKS		
NO.		FIELD	ACCENT		NORTH	EAST	SOUTH	WEST	
101	CORRIDOR	CPT-1		VB-I	PT-1	PT-1	<u>-</u>	PT-3	
102	EOC ROOM	CPT-1		VB-1	PT-1	P <sup>†</sup> -	<u>-</u>	PT-2	
103	ELEC. / COMM.	CONC-1		VB-1	PT-I	<u>;</u>	<u>;</u>	<u>;</u>	
104	OFFICE	CPT-1		VB-1	PT-I	P†-	PT-3	<del> </del>	
105	BREAK ROOM	T-1		T-2	PT-1	P†-1	<del>-</del>	<del>-</del> -	
106	RESTROOM	T-1		T-2	PT-1, T-1	P <sup>†</sup> -	<u>-</u>	PT-1, T-1	SEE ELEVATIONS
107	RESTROOM	T-1		T-2	PT-I	PT-I	PT-1, T-1	PT-1, T-1	SEE ELEVATIONS
108	CLOSET	CPT-1		VB-1	PT-I	PT-1	PT-1	PT-1	
109	CLOSET	CPT-1		<b>∀B-1</b>	PT-I	PT-1	PT-1	PT-1	
110	EOC ROOM	CPT-1		√B-1	PT-I	PT-I	PT-1	PT-2	
111	VESTIBULE	CONC-1							
112	EXIST. CONF. ROOM	EXISTING		EXISTING	EXISTING	EXISTING	EXISTING	MATCH	
113	CORRIDOR	EXISTING		EXISTING	EXISTING	MATCH	EXISTING	EXISTING	





Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX
Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



	are protecte drawings or	efield Beasley & / d by the copyrigh any part thereof in any form or b	nt laws of the may not be	e United Stat used for an	tes. These y purpose o
--	-----------------------------	---	------------------------------	------------------------------	---------------------------

Print Record

07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Revisions

Date 2013-09-23

Job No. 1207007000

Sheet Title
FINISH PLAN,
FINISH SCHEDULE
AND NOTES

Sheet No.

SCALE: 1/8" = 1'-0"

A-105

FOR CONSTRUCTION

1 FINISH PLAN

SCALE: 1/8' - 1'-0'

18'-0" EI FINISH FLOOR
ELEVATION
0'-0"

> **EAST ELEVATION** SCALE: 1/8" = 1'-0"

> > SOUTH ELEVATION


WEST ELEVATION

SCALE: 1/8" = 1'-0"

SCALE: 1/8" = 1'-0"

E2Ø **E**4 FINISH FLOOR ELEVATION Ø'-Ø"

> ES TOP OF CMU 18'-0" FINISH FLOOR ELEVATION Ø'-Ø" BASEMENT WALL CONDITION-REFER TO DETAIL 3/AIØI & CIVIL DRAWINGS



NORTH ELEVATION SCALE: 1/8" = 1'-0"

WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23 1207007000 Sheet Title

**EXTERIOR** 

**ELEVATIONS** 

Sheet No.

A-200

EXTERIOR FINISH LEGEND:

(EI) EXISTING SPLIT FACE CMU TO REMAIN.

(E2) NEW SPLIT FACE CMU - (CMU & MORTAR) TYPE, COLOR & TOOLING TO MATCH EXISTING - TYP.

(E3) EXISTING SPLIT FACE CMU ACCENT BAND TO REMAIN.

E4> NEW SPLIT FACE CMU ACCENT BAND TO ALIGN W/ EXISTING - (CMU & MORTAR) TYPE, COLOR & TOOLING TO MATCH "E3".

E5 EXISTING CAST STONE ACCENT PIECE TO REMAIN.

EG NEW CAST STONE ACCENT PIECE - SIZE, PROFILE, COLOR, & FINISH TO MATCH EXISTING - TYP.

ET NEW SPLIT FACE CMU PILASTER - (CMU & MORTAR) TYPE, COLOR & TOOLING TO MATCH EXISTING "EI" - UNLEESS NOTED OTHERWISE

(E8) CMU CONTROL JOINT - REFER TO STRUCTURAL.

(E9) ALUMINUM STOREFRONT SYSTEM - REFER TO DETAIL 2/A600 - FINISH TO BE CLEAR ANODIZED ALUMINUM.

PAINTED STEEL ENTRANCE CANOPY FRAME - REFER TO SHEETS A302 & A303 - COLOR TO BE SELECTED BY ARCHITECT.

(EII) NEW RADIUSED STANDING SEAM METAL ROOFING -PREFINISHED WITH KYNAR 500 - AEP SPAN COLOR TO BE SELECTED BY ARCHITECT.

(E12) EXISTING HM DOOR & FRAME TO REMAIN.

EI3 NEW HM DOOR & FRAME - REFER TO SHEETS AI02 & A600 - MATCH EXISTING DOOR & FRAME COLOR (SEALANT COLOR TO MATCH FRAME).

(ÉI4) EXISTING BLAST RESISTANT WINDOW W/ HM FRAME TO REMAIN.

(EIS) NEW CONCRETE STAIRS W/ PAINTED METAL HANDRAIL/ COLOR TO BE GUARDRAIL - REFER TO DETAIL 5/A300 -SELECTED BY ARCHITECT. REFER TO SPECIFICATIONS.

EIS PREFINISHED METAL CANOPY - REFER TO SECTION 4/A300 -COLOR TO MATCH EXISTING HM WINDOW FRAME.

(EIB) NEW METAL COPING TO MATCH EXISTING.

(EIT) EXISTING METAL COPING TO REMAIN.

(ÉIB) EXISTING MTL. COLLECTOR HEAD & RAIN LEADER TO REMAIN.

NEW MTL. COLLECTOR HEAD & RAIN LEADER TO MATCH EXISTING.

EXTERIOR GENERAL NOTES:

REFER TO SHEET A600 FOR WINDOW KEYS LOCATED ON THIS


ALL EXPOSED STEEL SHALL BE PRIMED & PAINTED - COLOR TO BE SELECTED BY ARCHITECT. REFER TO SPECIFICATIONS.

COORDINATE ALL DOOR & WINDOW OPENINGS IN NEW WALLS

4. COORDINATE ALL DOOR & WINDOW OPENINGS IN EXISTING

WITH STRUCTURAL BRACING REQUIREMENTS.

MASONRY WALLS WITH STRUCTURAL DRAWINGS.



Wakefield Beasley Si Associates

ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX

770 209 7050 FAX

Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record
07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

ØØ MONTH 2000


Date 2013-09-23

Job No. 12@7@@7@@0

Sheet Title
INTERIOR
ELEVATIONS AND
MILLWORK DETAILS

Sheet No.

A-201





Atlanta Office: 5/55 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TFLEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia



Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID


12/02/13 FOR CONSTRUCTION

Revisions

1207007000

**BUILDING SECTIONS** AND VERTICAL CIRCULATION

A-300





Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.
Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions


2013-09-23

WALL

1207007000

SECTIONS

Sheet No. A-301





FAYETTE COUNTY

110 Volunteer Way Fayetteville, Georgia 30215




©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

07/26/2013: 80% CD Set for Review

1207007000

SECTIONS

A-302





Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

# FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



of Wakefield	Beasley.	, ,		
are protecte drawings or reproduced	efield Beasley & / ed by the copyrigh any part thereof in any form or b	nt laws of the may not be	e United States. used for any pi	These urpose or

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions


2013-09-23

ARCHITECTURAL STEEL **DETAILS AND NOTES** 

1207007000

Sheet No.


A-303



WAKEFIELD BEASLEY & ASSOCIATES

110 Volunteer May Fayetteville, Georgia





INSULATED GLAZING UNIT BY
STOREFRONT MANUFACTURER
- MEET OR EXCEED CURRENT
IECC REQUIREMENTS


ALUM. STOREFRONT ASSEMBLY
W/ THERMAL BREAK BY
STOREFRONT MANUFACTURER


ALUM. STOREFRONT
FRAME BEYOND

ALUM. & GLASS
DOOR

# HEAD DETAIL SCALE: 11/2' = 1'-0'


# HEAD DETAIL SCALE: 1 1/2' = 1'-0'

















# 16 SILL DETAIL SCALE: 11/2' - 1'-0'








	DOOR SCHEDULE:											
NO. DOOR				FRAME		DETAIL			REMARKS			
	SIZE	TYPE	MATERIAL	FINISH	TYPE	MATERIAL	FINISH	HEAD	JAMB	SILL	HDWR.	
101A	3'-@"x 1'-@"	ДД	MTL	PT-4	А	₩	PT-4	9/4600	8/4600	7/4600	5	
1Ø2A	3'-@"x T'-@"	AA	MTL	PT-4	В	HM	PT-4	6/4600	5/4600		4	I HOUR RATED
102B	3'-0"x 1'-0"	ДД	MTL	PT-4	В	HM	PT-4	6/4600	5/4600		4	I HOUR RATED
1Ø3A	3'-0"x 1'-0"	AA	MTL	PT-4	В	HM	PT-4	6/4600	5/4600	4/4600	6	I HOUR RATED
1Ø4A	3'-0"x T'-0"	ДД	MTL	PT-4	В	HM	PT-4	6/4600	5/4600		5	I HOUR RATED
1Ø5A	3'-0"x 1'-0"	AA	MTL	PT-4	В	HМ	PT-4	6/4600	5/4600	4/4600	5	I HOUR RATED
106A	3'-@"x 1'-@"	ДД	MTL	PT-4	В	HM	PT-4	6/4600	5/4600	4/4600	7	I HOUR RATED
IØ7A	3'-0"x T'-0"	AA	MTL	PT-4	В	HM	PT-4	6/4600	5/4600	4/4600	7	
1Ø8A	(2) 3'-Ø"x T'-Ø"	BB	MTL	PT-4	С	HM	PT-4	6/4600	5/4600		8	
1Ø9A	(2) 3'-Ø"x T'-Ø"	BB	MTL	PT-4	С	HM	PT-4	6/4600	5/4600		8	
IIØA	3'-0"x T'-0"	ДД	MTL	PT-4	В	HM	PT-4	6/4600	5/4600		3.1	I HOUR RATED
IIIA	(2) 3'-@"x T'-@"	9F A	GLASS	ALUM	SF	ALUM	CLEAR	15/A600	14/4600	13/A <b>600</b>	AL-I	
IIIB	3'-@"x T'-@"	ДД	MTL	PT-4	А	HM	PT-4	9/4600	8/4600	1/A600	2	
112A	3'-@"x T'-@"	ДД	MTL	PT-4	А	нм	PT-4	12/4600	11/4600	10/4600	3	
113.4	3'-0"x T'-0"	ДД	MTL	PT-4	В	HM	PT-4	6/4600	5/4600		5	











ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX
Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer May Fayetteville, Georgia 30215



©2013, Wakefield E are protected by t drawings or any p reproduced in any of Wakefield Beast
--

Print Record

07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Revisions

ate Job No.

2013-09-23 1207007000 Sheet Title

DOOR SCHEDULE AND DETAILS

Sheet No.

A-600

# General Notes

### 1. GENERAL

- 1.1 THE STRUCTURAL DRAWINGS AND SPECIFICATIONS ARE A PORTION OF THE CONSTRUCTION DOCUMENTS. THE CONTRACTOR AND SUBCONTRACTORS SHALL REFERENCE AND COORDINATE WITH ALL OTHER DISCIPLINES' DRAWINGS. ANY DISCREPANCIES OR OMISSIONS SHALL BE REPORTED TO THE STRUCTURAL ENGINEER AND ARCHITECT.
- 1.2 DESIGN CRITERIA:
  - A. CODES AND SPECIFICATIONS:
    - . GENERAL BUILDING CODE: INTERNATIONAL BUILDING CODE, 2006 EDITION WITH 2007, 2009, 2010 GEORGIA AMENDMENTS.
    - 2. CONCRETE:

BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, AMERICAN CONCRETE INSTITUTE, ACI 318-05.

- 3. STRUCTURAL STEEL:
  SPECIFICATION FOR STRUCTURAL STEEL BUILDINGS,
  AMERICAN INSTITUTE OF STEEL CONSTRUCTION, AISC 360-05.
- STEEL JOISTS:
  STANDARD SPECIFICATIONS, LOAD TABLES AND WEIGHT TABLES
  FOR STEEL JOISTS AND JOIST GIRDERS, STEEL JOIST
  INSTITUTE, SJI.
- 5. STEEL DECK:
  STEEL DECK INSTITUTE DESIGN MANUAL FOR COMPOSITE DECKS,
  FORM DECKS, ROOF DECKS AND CELLULAR METAL FLOOR DECK WITH
  ELECTRICAL DISTRIBUTION.
- 6. COLD-FORMED METAL FRAMING:
  NORTH AMERICAN SPECIFICATION FOR DESIGN OF COLD-FORMED
  STEEL STRUCTURAL MEMBERS, AMERICAN IRON AND STEEL INSTITUT
- 7. MASONRY:
  BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES, ACI
  530-05. SPECIFICATION FOR MASONRY STRUCTURES, ACI 530.1-05
- B. DESIGN LOADS (PSF):

1.	DEAD LOADS:	
	ROOF	2

ANY CHANGES IN CONSTRUCTION MATERIALS FROM THOSE SHOWN ON THE ARCHITECTURAL OR STRUCTURAL DRAWINGS SHALL BE REPORTED BY THE CONTRACTOR TO THE STRUCTURAL ENGINEER FOR VERIFICATION OF LOAD-CARRYING CAPACITY OF THE STRUCTURE.

LIVE LOAD REDUCTIONS HAVE BEEN APPLIED IN ACCORDANCE WITH THE BUILDING CODE, UNLESS NOTED.

- SNOW LOAD:

  GROUND SNOW LOAD (Pg)-----5.0

  FLAT-ROOF SNOW LOAD (Pf)----6.0

  SNOW EXPOSURE FACTOR (Ce)----1.0

  SNOW LOAD IMPORTANCE FACTOR (Is)-----1.2

  THERMAL FACTOR (Ct)-----1.0
- WALL COMPONENT AND CLADDING WIND PRESSURE-SEE DRAWINGS
- 5. SEISMIC LOADS:
  SEISMIC IMPORTANCE FACTOR (Ie)-----1.5

MADDED	CDECTRAL DECRONCE ACCELERATIONS.	
	SPECTRAL RESPONSE ACCELERATIONS:	0 007
	S	
SITE CL	_ASSC	(ASSUMED)
SITE CO	DEFFICIENTS:	
Fo	]	1.60
F۱	/	2.40
DESIGN	SPECTRAL RESPONSE ACCELERATION PARAME	TERS:
Sc	ds	0.217
Sc	d1	0.130
SEISMIC	C DESIGN CATEGORY	C

SEISMIC RESPONSE COEFFICIENT (Cs)0.163
RESPONSE MODIFICATION FACTOR(R)2.0
OVER-STRENGTH FACTOR $(\Omega_0)$ 2.50
DEFLECTION AMPLIFICATION FACTOR (Cd)1.75

ANALYSIS PROCEDURE: FOULVALENT LATERAL FORCE METHOD

ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE METHOD

REFER TO MECHANICAL, ELECTRICAL, AND PLUMBING DRAWINGS FOR SEISMIC SUPPORT AND ATTACHMENT REQUIREMENTS FOR UTILITIES.

- 1.3 EXISTING CONDITIONS:
  - A. CONTRACTOR SHALL VERIFY ALL EXISTING DIMENSIONS, ELEVATIONS AND SITE CONDITIONS PRIOR TO FABRICATION/CONSTRUCTION. NOTIFY STRUCTURAL ENGINEER AND ARCHITECT OF ANY DISCREPANCIES PRIOR TO FABRICATION/CONSTRUCTION.
  - THE CONTRACTOR SHALL OBTAIN A COPY OF THE EXISTING BUILDING DRAWINGS TITLED "FAYETTE COUNTY COMMUNICATIONS BUILDING", PREPARED BY SLATER PAULL & ASSOCIATES, INC., DATED 09-08-95, AND "FAYETTE COUNTY 911 CENTER", PREPARED BY ROSENBAUM ENGINEERING, INC., DATED AUG, 1 2008 THAT WERE USED IN THE PREPARATION OF THESE DOCUMENTS. NOTIFY STRUCTURAL ENGINEER AND ARCHITECT OF ANY DISCREPANCIES OF THE EXISTING CONDITIONS AND DIMENSIONS PRIOR TO FABRICATION/CONSTRUCTION.
- 1.4 INSPECTIONS/OBSERVATIONS:
  - A. SPECIAL INSPECTIONS ARE REQUIRED FOR THIS PROJECT IN ACCORDANCE WITH INTERNATIONAL BUILDING CODE. REFER TO PROJECT SPECIFICATIONS AND DRAWINGS.
  - STRUCTURAL OBSERVATION BY STRUCTURAL ENGINEER'S OFFICE.
    - 1. STRUCTURAL OBSERVATION IS VISUAL OBSERVATION OF THE IN-PLACE STRUCTURE FOR GENERAL CONFORMANCE TO THE APPROVED CONSTRUCTION DOCUMENTS AT THE TIME OF THE OBSERVATION.
    - 2. CONTRACTOR SHALL NOTIFY STRUCTURAL ENGINEER AND ARCHITECT, PER THE SCHEDULE STATED BELOW, WHEN SUCH ITEMS HAVE PROGRESSED TO THE POINT WHERE THEY WILL BE IN PLACE AND READY FOR REVIEW. FAILURE TO NOTIFY MAY REQUIRE REMOVAL OF COMPLETED CONSTRUCTION.

NOTIFY PRIOR TO THE	REQUIRED DAYS
FOLLOWING SCHEDULED TASKS	NOTIFICATION
FIRST FOUNDATION POUR	2 DAYS
GROUTING MASONRY WALL CONSTRUCTION-	
COVERING METAL ROOF DECK	2 DAYS

- C. OBSERVATION BY THE STRUCTURAL ENGINEER'S OFFICE DOES NOT REPLACE INSPECTIONS AND TESTING BY THE TESTING AGENCY OR SPECIAL INSPECTOR
- 1.5 SUBMITTALS:
  - A. REVIEW OF SHOP DRAWINGS AND OTHER SUBMITTALS BY THE STRUCTURAL ENGINEER DOES NOT RELIEVE THE CONTRACTOR OF THE RESPONSIBILITY TO REVIEW AND CHECK SHOP DRAWINGS BEFORE SUBMITTING TO THE STRUCTURAL ENGINEER. THE CONTRACTOR REMAINS SOLELY RESPONSIBLE FOR ERRORS AND OMISSIONS ASSOCIATED WITH THE PREPARATION OF SHOP DRAWINGS AS THEY PERTAIN TO MEMBER SIZES, DETAILS, AND DIMENSIONS SPECIFIED IN THE CONTRACT DOCUMENTS. ALL SHOP DRAWINGS MUST BE REVIEWED AND "APPROVED" BY THE CONTRACTOR PRIOR TO SUBMITTAL.
  - B. SUBMIT ALL SHOP DRAWINGS ON THREE PRINTS ONLY. ONE PRINT WILL BE RETURNED TO THE CONTRACTOR. ALL PRINTS REQUIRED BY THE CONTRACTOR ARE THE RESPONSIBILITY OF THE CONTRACTOR AND SHALL BE MADE AFTER APPROVED SHOP DRAWINGS ARE RETURNED. IF ADDITIONAL PRINTS ARE SUBMITTED, THEY WILL BE RETURNED UNMARKED.
  - C. SHOP DRAWINGS: THE CONTRACTOR SHALL SUBMIT FOR STRUCTURAL ENGINEER REVIEW SHOP DRAWINGS FOR THE FOLLOWING ITEMS. ITEMS MARKED (\*) SHALL HAVE SHOP DRAWINGS SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE IN WHICH THE PROJECT IS LOCATED. ITEMS MARKED (#) SHALL BE SUBMITTED FOR STRUCTURAL ENGINEER'S RECORDONLY
    - CONCRETE MIX DESIGNS
      CONCRETE REINFORCING
      STRUCTURAL STEEL (\*)
      STEEL JOIST
      STEEL DECK
      COLD-FORMED METAL FRAMING (\*)
      MASONRY MORTAR MIX DESIGNS
      MASONRY GROUT MIX DESIGNS

MASONRY REINFORCING

- D. DESIGN CALCULATIONS: THE CONTRACTOR SHALL SUBMIT FOR STRUCTURAL ENGINEER'S RECORD, DESIGN CALCULATIONS SEALED BY A PROFESSIONAL ENGINEER REGISTERED IN THE STATE IN WHICH THE PROJECT IS LOCATED FOR THE FOLLOWING ITEMS.
  - 1. STRUCTURAL STEEL CONNECTIONS
  - STEEL STAIRS
  - STEEL JOIST (SEE STEEL JOIST SECTION OF GENERAL NOTES)
  - COLD-FORMED METAL FRAMING
- 1.6 ALL DETAILS SHOWN ARE TYPICAL. SIMILAR DETAILS APPLY TO SIMILAR CONDITIONS, UNLESS NOTED.
- 1.7 THE CONTRACTOR IS RESPONSIBLE FOR MEANS, METHODS, TECHNIQUES, SEQUENCES, AND PROCEDURES OF CONSTRUCTION.
- 1.8 CONSTRUCTION MATERIALS SHALL BE SPREAD OUT IF PLACED ON FRAMED FLOORS/ROOFS. IT IS THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT LOADS DO NOT EXCEED THE DESIGN LIVE LOAD.

### 2. FOUNDATION

GEOTECHNICAL REPORT: FOUNDATION DESIGN IS BASED ON THE GEOTECHNICAL REPORT BY PIEDMONT GEOTECHNICAL CONSUTLANTS, INC., TITLED REPORT OF SUBSURFACE EXPLORATION AND GEOTECHNICAL ENGINEERING EVALUATION PROPOSED ADDITION TO EMERGENCY OPERATIONS CENTER 110 VOLUNTEER WAY FAYETTEVILLE, GEORGIA PGC PROJECT NO. 113165, DATED JULY 17, 2013. THE CONTRACTOR SHALL OBTAIN A COPY OF THE GEOTECHNICAL REPORT FROM THE OWNER AND FOLLOW ALL REQUIREMENTS AND RECOMMENDATIONS.

2.2 MAXIMUM ALLOWABLE BEARING PRESSURES (PSF):

CONTINUOUS WALL FOOTINGS-----2000

- ALL FOUNDATION BEARING SURFACES SHALL BE REVIEWED BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING CONCRETE TO ENSURE THEIR COMPLIANCE WITH PRESSURES NOTED. ALL FOOTING ELEVATIONS ARE ESTIMATED AND MAY BE ADJUSTED IN THE FIELD BY THE GEOTECHNICAL FNGINFFR.
- 2.4 COMPACTED FILL SHALL MEET THE REQUIREMENTS NOTED IN THE GEOTECHNICAL REPORT.
- 2.5 BACKFILL FOR FOUNDATION AND RETAINING WALLS SHALL BE A FREE DRAINING GRANULAR MATERIAL, SUCH AS SIZE #57 STONE. BACKFILL SHALL BE COMPACTED SUFFICIENTLY TO PREVENT SUBSIDENCE OF SURFACE ADJACENT TO WALL. THE GRANULAR MATERIAL SHALL BE PLACED IN A 45 DEGREE WEDGE EXTENDING FROM THE BASE OF THE FOOTING.
- 2.6 FOUNDATION AND RETAINING WALLS SHALL NOT BE BACKFILLED UNTIL CONCRETE HAS ATTAINED THE REQUIRED 28 DAY COMPRESSIVE STRENGTH.
- 2.7 PROVIDE 6" COMPACTED GRANULAR FILL BENEATH ALL EARTH SUPPORTED SLABS.
  PROVIDE 6 MIL VAPOR RETARDER BETWEEN BOTTOM OF SLAB AND TOP OF GRANULAR FILL.
- 3. CONCRETE
- 3.1 CONCRETING OPERATIONS SHALL COMPLY WITH ACI STANDARDS.
- 3.2 MINIMUM CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS (PSI), TYPE OF CONCRETE, MAXIMUM W/C (WATER/CEMENTITIOUS MATERIALS RATIO), AIR CONTENT, SLUMP AND CONCRETE USE:

STRENGTH	TYPE	W/C	AIR	SLUMP	USE
4500	NORMAL WT.	0.45	1–3%	3" TO 5"	SLAB ON GRADE
3000	NORMAL WT.	0.57		3" TO 5"	FOOTINGS

- 3.3 REINFORCING BARS: ASTM A615 GRADE 60.
- 3.4 WELDED WIRE REINFORCEMENT (WWR): ASTM A185. MINIMUM LAP AND EMBEDMENT TO BE THE GREATER OF ONE CROSS WIRE SPACING PLUS 2" OR 6".
- REINFORCING STEEL SHOWN IN SECTIONS AND DETAILS ARE A SCHEMATIC INDICATION THAT REINFORCING EXISTS. SEE SCHEDULES, SECTION NOTES AND GENERAL NOTES FOR ACTUAL REINFORCING REQUIRED.
- 3.6 REINFORCING BAR PLACING ACCESSORIES IN ACCORDANCE WITH ACI MANUAL OF STANDARD PRACTICE. WHERE CONCRETE IS EXPOSED IN FINISHED BUILDING, PROVIDE ACCESSORIES WITH RUSTPROOF LEGS. WHERE CONCRETE IS SAND-BLASTED OR BUSH-HAMMERED, PROVIDE ACCESSORIES OF STAINLESS STEEL.
- 3.7 DETAIL REINFORCEMENT IN ACCORDANCE WITH ACI 315. REINFORCEMENT SHALL NOT BE WELDED UNLESS NOTED OR APPROVED BY THE STRUCTURAL ENGINEER.
- 3.8 ALL SPLICES SHALL BE CLASS "B" TENSION LAP SPLICE, UNLESS NOTED.
- 3.9 ALL REINFORCING MARKED "CONTINUOUS" SHALL BE SPLICED WITH CLASS "B" TENSION LAP SPLICE, UNLESS NOTED.
- 3.10 CONCRETE COVERAGE OF REINFORCEMENT, UNLESS NOTED:

FOOTINGS2"	TOD	0 7"	DOTTOM	0	CIDEC
FUUTTNGS2	TUP	αз	BOLLOM	ĊΧ	21DF2
GRADE BEAMS2"	TOP	8 3"	BOTTOM	8	SIDES
FOUNDATION RETAINING WALLS			2" BO	ГΗ	FACES
WWR IN SLABS ON GRADE				2	" TOP
SLABS ON WELL GRADED SUBGRADE OR VAPOR BAR	RRIFF	RS:			

- 3.11 PEDESTAL, COLUMN AND WALL VERTICAL REINFORCING: DOWEL TO FOUNDATION WITH HOOKED BARS OF SAME SIZE AND SPACING AS VERTICAL REINFORCING.
- FOR CONCRETE WALLS WITH A SINGLE LAYER OF REINFORCING, REINFORCING TO BE CENTERED IN WALL UNLESS NOTED.
- 3.13 EARTH SUPPORTED SLABS: 4" THICK, REINFORCED WITH 6X6 W2.9/W2.9 WWR AT MID-DEPTH OF SLAB, UNLESS NOTED.
- 4. STRUCTURAL STEEL
- 4.1 FABRICATE AND ERECT ALL STRUCTURAL STEEL IN ACCORDANCE WITH AISC "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES".





ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Re	Print Record					
Ø7/26/2Ø13:	80% CD Set for Review					
Ø9/23/2Ø13:	RELEASE FOR BID					

12/02/13 FOR CONSTRUCTION

	 _
	_
	-

Date Job No.

20|3-09-23 | 1207007000 | Sheet Title

Sheet Title

GENERAL NOTES

Sheet No.

S-100

# General Notes

- 4.1 FABRICATE AND ERECT ALL STRUCTURAL STEEL IN ACCORDANCE WITH AISC "CODE OF STANDARD PRACTICE FOR STEEL BUILDINGS AND BRIDGES".
- 4.2 THE STEEL FRAME IS "NON-SELF-SUPPORTING". ADEQUATE TEMPORARY SUPPORT MUST BE PROVIDED BY THE CONTRACTOR UNTIL REQUIRED CONNECTIONS OR ELEMENTS ARE IN PLACE.
  - A. ALL LATERAL LOAD RESISTANCE AND STABILITY OF THE BUILDING IN THE COMPLETED STRUCTURE IS PROVIDED AS FOLLOWS:
    - 1. ROOF DIAPHRAGM: STEEL ROOF DECKING
    - 2. LATERAL LOAD RESISTING SYSTEM: REINFORCED MASONRY SHEAR WALLS,
- 4.3 STRUCTURAL STEEL: ASTM A992, GRADE 50 FOR WIDE FLANGE BEAMS AND COLUMNS; ASTM A36 FOR S, M AND HP SHAPES AND CHANNELS; ASTM A36 FOR STIFFENER PLATES, BASE PLATES, COLUMN CAP PLATES, BEAM CONNECTION PLATES AND STEEL ANGLES.
- 4.4 HOLLOW STRUCTURAL SECTIONS: ASTM A500, GRADE B.
- 4.5 WELDED CONNECTIONS: E70XX ELECTRODES, MINIMUM SIZE FILLET WELD 3/16".
- 4.6 HEADED ANCHOR RODS: ASTM F1554 GRADE 36 WELDABLE ANCHOR AND HEAVY HEX NUT, UNLESS INDICATED.
- 4.7 BOLTED CONNECTIONS: BEARING TYPE A325-N IN ACCORDANCE WITH AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS".
  BOLTS THROUGH 4" WIDE BEAM FLANGES SHALL BE 5/8" DIAMETER. OTHER BOLTS SHALL BE 3/4" DIAMETER. USE SNUG TIGHT BEARING CONNECTIONS FOR ALL BOLTED CONNECTIONS.
- 4.8 BOLTS SHOWN IN SECTIONS AND DETAILS ARE A SCHEMATIC INDICATION THAT BOLTS MAY BE USED. ACTUAL NUMBER, UNLESS SPECIFIED, TO BE IN ACCORDANCE WITH AISC.
- 4.9 ALL STRUCTURAL STEEL CONNECTIONS NOT SPECIFICALLY DETAILED ON THE STRUCTURAL DRAWINGS SHALL BE DESIGNED BY THE CONTRACTOR TO RESIST FORCES INDICATED. THE CONTRACTOR'S CONNECTION DESIGN SHALL BE UNDER THE DIRECT SUPERVISION OF A PROFESSIONAL ENGINEER REGISTERED IN THE STATE WHERE THE PROJECT IS LOCATED. LBYD CAN CONTRACT WITH THE CONTRACTOR TO PROVIDE CONNECTION DESIGN SERVICES IF REQUESTED.
- DESIGN CALCULATIONS FOR THE CONNECTIONS SHALL BE PROVIDED BY THE CONTRACTOR AND DESIGNED BY A PROFESSIONAL ENGINEER. CALCULATIONS SHALL BEAR THE SEAL OF A PROFESSIONAL ENGINEER REGISTERED IN THE STATE WHERE THE PROJECT IS LOCATED AND SUBMITTED FOR THE FILES OF THE ARCHITECT AND STRUCTURAL ENGINEER. THE CONNECTION DESIGNER'S ENGINEERING SEAL ON THE DESIGN CALCULATIONS SHALL REPRESENT THAT THE CONNECTIONS INDICATED ON THE SHOP DRAWINGS HAVE BEEN REVIEWED AND ARE IN ACCORDANCE WITH THE SUBMITTED DESIGN CALCULATIONS. SHOP DRAWINGS CONTAINING CONNECTIONS FOR WHICH CALCULATIONS HAVE NOT BEEN RECEIVED OR REQUIRED CONNECTION INFORMATION IS NOT PROVIDED WILL BE RETURNED UNCHECKED AS AN INCOMPLETE SUBMITTAL.
- 4.11 REQUIRED CONNECTION INFORMATION SHALL BE SHOWN AT EACH DETAILED CONNECTION ON THE SUBMITTAL DRAWINGS AS FOLLOWS:
  - A. DESIGN REACTION.
  - B. CALCULATION PAGE NUMBER.
  - C. CONNECTION CAPACITY.
- 4.12 ALL NON-COMPOSITE BEAM CONNECTIONS SHALL BE "SIMPLE SHEAR CONNECTIONS", UNLESS NOTED. WHERE BEAM REACTIONS AND/OR DESIGN FORCES ARE NOT SHOWN ON THE STRUCTURAL DRAWINGS, THE CONNECTIONS SHALL BE DESIGNED TO SUPPORT A REACTION EQUAL TO ONE-HALF THE TOTAL UNIFORM LOAD CAPACITY FROM THE MAXIMUM TOTAL UNIFORM LOAD TABLE MULTIPLIED BY A FACTOR OF 1.2 FOR GIVEN SHAPE, SPAN, AND GRADE OF STEEL.
- 4.13 WHERE BEAM REACTIONS ARE SHOWN ON THE DRAWINGS, THE CONNECTIONS SHALL DEVELOP THE REACTIONS SHOWN. WHERE CONNECTIONS ARE SUBJECT TO ECCENTRICITY, SUCH ECCENTRICITY SHALL BE TAKEN INTO ACCOUNT WHEN DESIGNING AND DETAILING THE CONNECTION.
- 4.14 WHERE STEEL BEAMS ARE CONTINUOUS OVER COLUMNS, PROVIDE WEB STIFFENER PLATES EACH SIDE OF BEAM WEB, OF THICKNESS EQUAL TO BEAM FLANGE THICKNESS, LOCATED IN ALIGNMENT WITH COLUMN WEB, FLANGES OR CENTER LINE OF TUBES AND PIPE COLUMNS.

# 5. STEEL JOISTS

- 5.1 DESIGN, FABRICATE, AND ERECT STEEL JOISTS IN ACCORDANCE WITH THE SJI.
- 5.2 PROVIDE A MINIMUM END BEARING ON STEEL SUPPORTS AS REQUIRED BY SJI. STAGGER THE ENDS OF JOIST IF NECESSARY. CONTRACTOR COORDINATE METAL DECK SPLICE LOCATION TO CENTER OVER JOIST.
- 5.3 PROVIDE HORIZONTAL AND DIAGONAL BRIDGING IN ACCORDANCE WITH SJI TO PROVIDE ADEQUATE JOIST CHORD BRACING.
- 5.4 AT JOISTS PARALLEL TO MASONRY WALL, WELD EACH BRIDGING ROW TOP AND BOTTOM TO AN ANGLE 3X3X3/16X0'-6". ANCHOR ANGLE WITH TWO 3/8" DIAMETER SLEEVE ANCHORS WITH A TWO-INCH EMBEDMENT INTO WALL.
- 5.5 AT JOISTS PARALLEL TO BEAMS, ANCHOR BRIDGING ROWS BY WELDING TO BEAMS.

- DESIGN ROOF JOISTS TO RESIST THE FOLLOWING NET WIND UPLIFT PRESSURES FROM THE COMPONENT AND CLADDING WIND LOAD TABLE SHOWN ON THE DRAWINGS.
- 5.7 DESIGN CALCULATIONS SHALL BE SUBMITTED FOR THE FILES OF THE STRUCTURAL ENGINEER AND ARCHITECT FOR JOISTS WITH CANTILEVERS OR CONCENTRATED LOADS AND FOR JOIST SIZES FOR WHICH STANDARD SJI LOAD TABLES ARE NOT APPLICABLE. CALCULATIONS SHALL BEAR THE SEAL OF A PROFESSIONAL ENGINEER REGISTERED IN THE STATE WHERE THE PROJECT IS LOCATED. SHOP DRAWINGS CONTAINING JOISTS FOR WHICH CALCULATIONS HAVE NOT BEEN RECEIVED WILL BE CONSIDERED AN INCOMPLETE SUBMITTAL.
- 5.8 PROVIDE JOIST REINFORCEMENT AT ANY CONCENTRATED LOADS NOT LOCATED AT A JOIST PANEL POINT.
- 9 CAMBER AND DEFLECTION SHOULD BE CONSIDERED WHEN DETAILING / CONSTRUCTING FRAMING ADJACENT TO OR ATTACHING TO JOISTS.

### 6. STEEL DECK

- 6.1 DECK PROPERTIES AND ATTACHMENTS SHALL BE IN ACCORDANCE WITH THE STEEL DECK INSTITUTE.
- 6.2 DECK SHALL BE CONTINUOUS OVER THREE OR MORE SPANS.
- 6.3 DO NOT SHORE DECK.
- 6.4 ROOF DECK: WIDE RIB TYPE "WR", STEEL ROOF DECK, 20 GAGE, 1-1/2" DEEP, GALVANIZED. SHEET STEEL FOR DECK SHALL HAVE A MINIMUM YIELD STRENGTH OF
- 6.5 COLD-FORMED METAL FRAMING, SUSPENDED CEILINGS, LIGHT FIXTURES AND DUCTS OR OTHER UTILITIES SHALL NOT BE SUPPORTED BY THE METAL ROOF DECK.

#### 7. MASONRY

- 7.1 MASONRY CONSTRUCTION SHALL CONFORM TO ACI 530 SPECIFICATION.
- 7.2 SPECIFIED COMPRESSIVE STRENGTH OF MASONRY (F'm): 1500 PSI AT 28 DAYS.
- 7.3 SPECIFIED COMPRESSIVE STRENGTH OF GROUT (F'g): 2500 PSI AT 28 DAYS.
- 7.4 MORTAR: TYPE S OR M.
- 7.5 ALL MASONRY SHALL BE RUNNING BOND, UNLESS NOTED.
- 7.6 ALL BLOCK CELLS AND CAVITIES BELOW GRADE SHALL BE FILLED WITH CONCRETE OR GROUT.
- 7.7 MINIMUM REINFORCING LAP SPLICE OF 48 BAR DIAMETERS.
- 7.8 SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS AND DETAILS OF MASONRY CONTROL JOINTS.
- 7.9 WHEN REINFORCING IS SPECIFIED, PROVIDE AT EACH SIDE OF CONTROL JOINTS, OPENINGS AND WALL ENDS. REINFORCING TO BE CENTERED IN WALL UNLESS NOTED.
- 7.10 ADEQUATE TEMPORARY BRACING OF CMU WALLS MUST BE PROVIDED BY THE CONTRACTOR UNTIL REQUIRED CONNECTIONS OR ELEMENTS ARE IN PLACE.

# 8. POST INSTALLED ANCHORS

- 8.1 POST INSTALLED ANCHORS SHALL COMPLY WITH ACI-318 APPENDIX D.
- 8.2 ACCEPTABLE MANUFACTURERS SHALL INCLUDE BUT ARE NOT LIMITED TO HILTI, INC. AND SIMPSON STRONG-TIE COMPANY, INC.
- 8.3 CARE SHALL BE TAKEN IN PLACING POST INSTALLED ANCHORS TO AVOID CONFLICTS WITH EXISTING REBAR.
- 8.4 HOLES SHALL BE DRILLED AND CLEANED IN ACCORDANCE WITH THE MANUFACTURER'S WRITTEN INSTRUCTIONS. SUBSTITUTION REQUESTS, FOR PRODUCTS OTHER THAN THOSE SHOWN SHALL BE SUBMITTED BY THE CONTRACTOR ALONG WITH PREPARED DOCUMENTATION DEMONSTRATING EQUAL SUBSTITUTION THAT THE PRODUCT IS CAPABLE OF ACHIEVING EQUIVALENT PERFORMANCE VALUES (MINIMUM) OF THE SPECIFIED PRODUCT USING THE APPROPRIATE DESIGN PROCEDURE AND/OR STANDARD(S) AS REQUIRED BY THE BUILDING CODE.
- 8.5 THE CONTRACTOR SHALL FOLLOW ALL MANUFACTURER'S INSTALLATION GUIDELINES, SPECIFICATIONS, AND RECOMMENDATIONS.
- A REPRESENTATIVE OF THE POST-INSTALLED ANCHOR MANUFACTURER SHALL BE PRESENT FOR THE FIRST INSTALLATION OF EACH TYPE OF ANCHOR USED TO DEMONSTRATE AND INSTRUCT TO THE CONTRACTOR'S INSTALLATION CREW AND PERSONNEL THE PROPER METHOD OF INSTALLATION. SHOULD THE CONTRACTOR CHANGE INSTALLATION CREW OR INDIVIDUALS INSTALLING THE ANCHOR, THE MANUFACTURER'S REPRESENTATIVE SHALL BE NOTIFIED BY THE CONTRACTOR TO RETURN AND PROVIDE INSTRUCTION TO THE NEW INSTALLER(S).
- 8.7 CONCRETE ANCHORS:
  - 1. MECHANICAL ANCHORS FOR USE IN CRACKED AND UNCRACKED CONCRETE SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI-355.2 AND ICC-ES AC193.

2. ADHESIVE ANCHORS FOR USE IN CRACKED AND UNCRACKED CONCRETE SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ACI355.4 AND ICC-ES AC308.

## 8.8 MASONRY ANCHORS:

- 1. ANCHORAGE TO SOLID-GROUTED CONCRETE MASONRY
  - A. MECHANICAL AND CONCRETE SCREW ANCHORS FOR USE IN SOLID-GROUTED CONCRETE MASONRY SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICC-ES AC01 OR ICC-ES AC106, RESPECTIVELY.
  - B. ADHESIVE ANCHORS FOR USE IN SOLID-GROUTED CONCRETE MASONRY SHALL HAVE BEEN TESTED AND QUALIFIED FOR USE IN ACCORDANCE WITH ICC-ES AC58 OR AC60.
- 2. ANCHORAGE TO HOLLOW CONCRETE MASONRY/UNREINFORCED CLAY BRICK MASONRY:
  - A. SCREW ANCHORS FOR USE IN HOLLOW CONCRETE MASONRY SHALL HAVE BEEN TESTED AND QUALIFIED IN ACCORDANCE WITH ICC-ES AC106.
  - B. ADHESIVE ANCHORS WITH SCREEN TUBES SHALL BE TESTED AND QUALIFIED IN ACCORDANCE WITH ICC-ES AC58 OR AC60, AS APPROPRIATE. THE APPROPRIATE SCREEN TUBE SHALL BE USED AS RECOMMENDED BY THE ADHESIVE MANUFACTURER.
- 9. FOUNDATION QUALITY CONTROL DURING CONSTRUCTION
- 9.1 BEARING ELEVATIONS: THE TOP ELEVATION OF ALL FOOTINGS IS SHOWN ON THE DRAWINGS FOR BID PURPOSES. THE FINAL BEARING ELEVATIONS MAY VARY AS REQUIRED TO PROVIDE PROPER BEARING CAPACITY IN AN APPROVED BEARING STRATUM AS DETERMINED BY THE GEOTECHNICAL ENGINEER
- 9.2 FIELD INSPECTION OF BEARING STRATUM: THE BEARING STRATUM OF EACH SPREAD FOOTING SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO POURING OF CONCRETE.
- 9.3 FOOTING EXCAVATION:
  - A. FOOTINGS SHALL BE NEATLY EXCAVATED WHERE POSSIBLE WITH SIDES AND TOP EDGES FREE OF LOOSE OR WET MATERIALS. WHERE NEAT EXCAVATION IS NOT POSSIBLE, FOOTING EXCAVATION SHALL BE OPEN CUT WITH EDGES FORMED AND BRACED. ALL FOOTINGS WITH FORMED EDGES SHALL BE BACKFILLED FROM BOTTOM TO TOP OF FOOTING WITH LEAN CONCRETE. THE BOTTOM EXCAVATION SHALL BE CLEAN AND DRY WITH ALL LOOSE MATERIAL REMOVED FOR AN ESSENTIALLY FLAT BEARING SURFACE. EXCAVATIONS SHALL NOT BE LEFT OVERNIGHT UNLESS A 2" UNREINFORCED CONCRETE SEAL (MUD) SLAB IS PLACED AT THE BOTTOM OF THE FOOTING EXCAVATION. WHERE SOFT OR UNSUITABLE BEARING SURFACES ARE ENCOUNTERED, THE AREA SHALL BE UNDERCUT AS REQUIRED AND REPLACED WITH LEAN CONCRETE OR COMPACTED DENSE GRADED CRUSHED STONE AS DIRECTED BY THE GEOTECHNICAL ENGINEER.
  - B. ALL BACKFILL SHALL BE ENGINEERED FILL AS DEFINED IN THE GEOTECHNICAL REPORT. EXCAVATED MATERIAL MAY BE USED AS BACKFILL MATERIAL WITH WRITTEN APPROVAL FROM THE GEOTECHNICAL ENGINEER STATING THAT SUCH MATERIAL IS SUITABLE AS BACKFILL AND INSTRUCTIONS ARE GIVEN FOR PROPER MOISTURE CONTENT AND COMPACTION. THE TESTING AGENCY APPROVAL AND INSTRUCTIONS FOR COMPACTION SHALL BE SUBMITTED TO THE GEOTECHNICAL ENGINEER FOR REVIEW.
- 10. CONCRETE QUALITY CONTROL TESTING DURING CONSTRUCTION
- 10.1 ALL CONCRETE SHALL USE AIR-ENTRAINING ADMIXTURE AT THE MANUFACTURER'S PRESCRIBED RATE TO RESULT IN CONCRETE AT POINT OF PLACEMENT HAVING TOTAL AIR CONTENT AS NOTED ABOVE.
- 10.2 CONCRETE AGGREGATES SHALL CONFORM TO THE FOLLOWING SPECIFICATIONS:
  - A. SPECIFICATION FOR CONCRETE AGGREGATES, ASTM C33.
  - B. NORMAL WEIGHT CONCRETE AGGREGATES MAY BE EITHER GRAVEL OR LIMESTONE UNLESS SPECIFIED.
- 10.3 WATER: WATER FOR CONCRETE SHALL BE CLEAN, FRESH AND DRINKABLE.
- 10.4 CEMENT:
  - A. CEMENT SHALL CONFORM TO THE SPECIFICATION FOR PORTLAND CEMENT, ASTM C150, TYPE I (NORMAL).
  - B. BRAND OF CEMENT: UNLESS ACCEPTED BY THE STRUCTURAL ENGINEER, USE ONE BRAND OF CEMENT THROUGHOUT THE PROJECT.
- 10.5 CONCRETE MIX DESIGNS:
  - A. AN INDEPENDENT TESTING AGENCY SHALL PREPARE DESIGN MIXES FOR EACH TYPE AND STRENGTH OF CONCRETE BY EITHER LABORATORY TRIAL MIXTURES OR FIELD EXPERIENCE METHODS AS SPECIFIED IN ACI 318.
  - B. STRUCTURAL ENGINEER ACCEPTANCE: CONCRETE MIX DESIGNS MUST BE SUBMITTED A MINIMUM OF 15 DAYS PRIOR TO THE START OF THE WORK FOR STRUCTURAL ENGINEER'S ACCEPTANCE PRIOR TO PLACEMENT OF CONCRETE IN THE PLANT OR FIELD. ANY ADJUSTMENT IN APPROVED MIX DESIGNS INCLUDING CHANGES IN ADMIXTURES MUST BE SUBMITTED IN WRITING TO THE STRUCTURAL ENGINEER FOR ACCEPTANCE PRIOR TO USE IN THE FIELD.



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

01/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

\_\_\_\_\_\_ Revisions

 Date
 Job No.

 2013-09-23
 1207007000

Sheet Title

GENERAL NOTES

Sheet No.

S-101

- ADMIXTURES: USE ONLY ADMIXTURES APPROVED BY THE STRUCTURAL ENGINEER
- THE CONTRACTOR WILL EMPLOY A TESTING AGENCY TO PERFORM OTHER TESTS AND TO SUBMIT TEST REPORTS. SAMPLING AND TESTING FOR QUALITY CONTROL DURING PLACEMENT OF CONCRETE, AS FOLLOWS


AND CONTAINING NO CHLORIDE IONS.


- SAMPLING FRESH CONCRETE: ASTM C172, EXCEPT MODIFIED FOR SLUMP TO COMPLY WITH ASTM C94.
  - 1. SLUMP: ASTM C143, ONE TEST FOR EACH SET OF COMPRESSIVE STRENGTH TEST SPECIMENS.
  - 2. AIR CONTENT: ASTM C173, VOLUMETRIC METHOD FOR LIGHTWEIGHT OR NORMAL WEIGHT CONCRETE; ASTM C231 PRESSURE FOR NORMAL WEIGHT CONCRETE; ONE FOR EACH SET OF COMPRESSIVE STRENGTH TEST SPECIMENS.
  - 3. CONCRETE TEMPERATURE: TEST HOURLY WHEN AIR TEMPERATURE IS 40 DEGREES F (4 DEGREES C) AND BELOW, AND WHEN 80 DEGREES F (27 DEGREES C) AND ABOVE; AND EACH TIME A SET OF COMPRESSION TEST SPECIMENS ARE MADE.
  - 4. COMPRESSIVE TEST SPECIMEN: ASTM C31, ONE SET OF FOUR STANDARD CYLINDERS FOR EACH COMPRESSIVE STRENGTH TEST. UNLESS DIRECTED. MOLD AND STORE CYLINDERS FOR LABORATORY CURED TEST SPECIMENS EXCEPT WHEN FIELD-CURE TEST SPECIMENS ARE REQUIRED.
  - COMPRESSIVE STRENGTH TESTS: ASTM C39, ONE SET FOR EACH 50 CU. YDS. OR FRACTION THEREOF, OF EACH CONCRETE CLASS PLACED IN ANY ONE DAY OR FOR EACH 5,000 SQ. FT. OF SURFACE AREA PLACED; ONE SPECIMEN TESTED AT 7 DAYS, TWO SPECIMENS TESTED AT 28 DAYS, AND ONE SPECIMEN RETAINED IN RESERVE FOR LATER TESTING IF REQUIRED.
  - A. WHEN FREQUENCY OF TESTING WILL PROVIDE LESS THAN 5 STRENGTH TESTS FOR A GIVEN CLASS OF CONCRETE, CONDUCT TESTING FROM AT LEAST 5 RANDOMLY SELECTED BATCHES OR FROM EACH BATCH IF FEWER THAN 5 ARE USED
  - B. WHEN STRENGTH OF FIELD-CURED CYLINDERS IS LESS THAN 85 PERCENT OF COMPANION LABORATORY-CURED CYLINDERS EVALUATE CURRENT OPERATIONS AND PROVIDE CORRECTIVE PROCEDURES FOR PROTECTING AND CURING THE IN-PLACE CONCRETE.
  - C. STRENGTH LEVEL OF CONCRETE WILL BE CONSIDERED SATISFACTORY IF AVERAGES OF SETS OF THREE CONSECUTIVE STRENGTH TEST RESULTS EQUAL OR EXCEED SPECIFIED COMPRESSIVE STRENGTH, AND NO INDIVIDUAL STRENGTH TEST RESULTS FALLS BELOW SPECIFIED COMPRESSIVE STRENGTH BY MORE THAN 500 PSI.
- 10.8 TEST RESULTS WILL BE REPORTED IN WRITING TO OWNER, STRUCTURAL ENGINEER, ARCHITECT AND CONTRACTOR. REPORTS OF COMPRESSIVE STRENGTH TESTS SHALL CONTAIN THE PROJECT IDENTIFICATION NAME AND NUMBER, DATE OF CONCRETE PLACEMENT, NAME OF CONCRETE TESTING AGENCY, CONCRETE TYPE AND CLASS, LOCATION OF CONCRETE BATCH IN STRUCTURE, DESIGN COMPRESSIVE STRENGTH AT 28 DAYS, CONCRETE MIX PROPORTIONS AND MATERIAL; COMPRESSIVE BREAKING STRENGTH AND TYPE OF BREAK FOR BOTH 7-DAY TESTS AND 28-DAY TESTS.
- 10.9 NONDESTRUCTIVE TESTING: IMPACT HAMMER, SONOSCOPE, OR OTHER NONDESTRUCTIVE DEVICE MAY BE PERMITTED BUT SHALL NOT BE USED AS THE SOLE BASIS FOR ACCEPTANCE OF REJECTION.
- 10.10 ADDITIONAL TESTS: THE TESTING AGENCY WILL MAKE ADDITIONAL TESTS OF IN-PLACE CONCRETE WHEN TEST RESULTS INDICATE SPECIFIED CONCRETE STRENGTHS AND OTHER CHARACTERISTICS HAVE NOT BEEN ATTAINED IN THE STRUCTURE, AS DIRECTED BY THE STRUCTURAL ENGINEER. CONTRACTOR SHALL PAY FOR SUCH TESTS CONDUCTED, AND ANY OTHER ADDITIONAL TESTING AS MAY BE REQUIRED, WHEN UNACCEPTABLE CONCRETE IS VERIFIED.
- 11. STRUCTURAL STEEL QUALITY CONTROL TESTING DURING CONSTRUCTION
- 11.1 FIELD INSPECTIONS AND TESTS: CHECK STEEL AS RECEIVED IN THE FIELD FOR POSSIBLE SHIPPING DAMAGE, WORKMANSHIP, PIECE MARKING AND VERIFICATION OF REQUIRED CAMBER.
- 11.2 SHOP AND FIELD BOLTED CONNECTIONS: INSPECT AND TEST DURING FABRICATION AND ERECTION OF STRUCTURAL STEEL, AS FOLLOWS:
  - INSPECT OR TEST IN ACCORDANCE WITH AISC SPECIFICATIONS.
  - FOR NON-SLIP CRITICAL BOLTED CONNECTIONS (BEARING-TYPE), ALL CONNECTIONS SHALL BE VISUALLY OBSERVED TO ASSURE THAT ALL BOLTS, NUTS AND WASHERS ARE IN PLACE AND THAT ALL PLIES OF CONNECTION MATERIAL HAVE BEEN DRAWN TOGETHER. ALL BOLTS SHALL BE VERIFIED TO BE SNUG TIGHT ONLY.
- 11.3 SHOP AND FIELD WELDING INSPECTION AND TESTING DURING FABRICATION AND ERECTION OF STRUCTURAL STEEL. AS FOLLOWS:
  - CERTIFY WELDERS AND CONDUCT INSPECTIONS AND TESTS AS REQUIRED. RECORD TYPES AND LOCATIONS OF DEFECTS FOUND IN WORK. RECORD WORK REQUIRED AND PERFORMED TO CORRECT DEFICIENCIES.

# **General Notes**

- PERFORM VISUAL INSPECTION OF ALL WELDS, INCLUDING BUT NOT LIMITED TO FIT-UP, INTERMEDIATE PASSES AND FINAL WELD
- INSPECTION PROCEDURES:
  - MAGNETIC PARTICLE INSPECTION: ASTM E 709, PERFORMED ON ROOT PASS AND ON FINISHED WELD. CRACKS OR ZONES OF INCOMPLETE FUSION OR PENETRATION NOT ACCEPTABLE INSPECT 10% OF THE WELD FOR EACH MEMBER CONNECTED IF ANY PORTION OF A WELD DOES NOT CONFORM, 100% OF THE WELD FOR THAT MEMBER SHOULD BE TESTED
  - ULTRASONIC INSPECTION: ASTM E164, PERFORM ON ALL FULL AND PARTIAL PENETRATION WELDS

# **Abbreviations**





**LBYD** 

PROJECT NO.

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

# **FAYETTE** COUNTY **EOC**

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23


Sheet Title GENERAL NOTES **AND ABBREVIATIONS** 

Job No.


1207007000

Sheet No.


S-102



### Typical Slab on Grade Detail




### Sawed Joint




### **Keyed Joint**

NOTES:
1. CONTROL JOINT FILLER SEMI-RIGID EPOXY.
2. SAWCUT TO TAKE PLACE WITHIN 4-12 HOURS OF FINISHING CONCRETE: 4 HOURS IN HOT WEATHER, 12 HOURS IN COLD WEATHER.


# Slab Control Joint Details JOINT TYPE IS OPTIONAL




Depressed Slab on Grade Detail



TYPICAL SLAB CONTROL JOINT




# PREFORMED ISOLATION JOINT FILLER AROUND COLUMN FOOting Step Detail



Column Base and Footing Detail

#### Tension Lap Splice Lengths $f_{C} = 3000$ $f_{C} = 4500$ OTHER BARS TOP BARS TOP BARS OTHER BARS SIZE 15" 24" 19" 22" 29" 25" 29" 19" 28" 33" 43" 29" 48" 42" 54" 55" 72" 62" 93" 48" 54" 70" 79" 61" 118 91" 102"

TOP BARS ARE HORIZONTAL REINFORCEMENT WITH MORE THAN 12" OF CONCRETE CAST BELOW THE REINFORCEMENT.



2#4 CONT

COLUMN -


**Exterior** 

**Isolation Joint Detail** 

WWR - SEE GEN NOTES -

Slab Edge Detail

Thickened Slab on Grade Detail



Stair on Grade Detail

Footing Schedule					
FOO	OTING DESIGNATION	F3	F4		
	SIZE	2'-8"x3'-6"	4'-0"x4'-0"		
	DEPTH	1'-0"	1'-0"		
FOOTING	BOTTOM REINF EW	5#4	6#4		
"	NOTES				


	Column Schedule						
COI	LUMN DESIGNATION	C1	C2				
	SIZE	HSS6x6x1/4	HSS4x4x1/4				
Ş	BASE PLATE	3/4x14x1'-2"	3/4x7x0'-10"				
COLUMN	ANCHOR RODS	(4) 3/4"ø	(4) 3/4 <b>"</b> ø				
	NOTES		2				

#### NOTES:

1. SEE ANCHOR ROD DETAILS FOR ROD LENGTHS,

EMBEDMENT, AND PLATE WASHER SIZE.

2. DRILL AND EPOXY ANCHOR RODS INTO EXISTING FOOTING AND FOOTING EXTENSION AS REQUIRED




### Anchor Rod Detail

	Ar	chor	Roc	d Sc	hedu	ıle	
	MATERIAL GRADE		MIN. PROJECTION		HOLE SIZE IN PLATE	PLATE WASHER	WELD SIZE
3/4"	A1554 GR. 36	0'-8"	0'-5"	1-1/2"	1-5/16"	PL 1/4x2" SQ.	1/4"

#### <u>NOTES</u>

- 1. PROVIDE LEVELING PLATES AND NUTS AS REQUIRED. STEEL SHIMS MAY BE USED AS CONTRACTOR'S OPTION.
- 2. PLATE WASHERS SHALL BE ASTM A36 MATERIAL. PROVIDE STANDARD HOLES IN PLATE WASHERS (1/16" LARGER THAN DIAMETER OF ROD).
- 3. LOCATION AND ELEVATION OF ANCHOR RODS SHALL BE VERIFIED BY SURVEYOR PRIOR TO ERECTION. WHERE ANCHOR RODS ARE OUT OF TOLERANCE, CONTRACTOR SHALL COORDINATE REPAIR WITH DESIGN PROFESSIONAL.



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

 Date
 Job No.


 2013-09-23
 1207007000

Sheet Title

TYPICAL DETAILS

Sheet No.

S-103



DOWELS TO BE TIED IN PLACE

BEFORE CONCRETE PLACED.

Isometric View Of Typical Masonry Wall

1. STONE VENEER NOT SHOWN FOR CLARITY.

JOINT SPACING NOT TO EXCEED 25'-0".

2. ALL BOND BEAMS MADE WITH FORM BLOCKS ONLY. 3. FOR STRUCTURAL BOND BEAMS, SEE SECTIONS.


4. SEE ARCHITECTURAL DRAWINGS FOR VERTICAL MASONRY

CONTROL JOINT LOCATIONS. VERTICAL MASONRY CONTROL

## HORIZONTAL STEEL -STOP AT CONTROL VERTICAL STEEL JOINT LOCATIONS


### Wall Control Joint Detail

PROVIDE CONTROL JOINT AT 25'-0" MAXIMUM SPACING. SEE ARCH. DWGS FOR LOCATIONS. (ALTERNATE WITH EXPANSION JOINTS)




### Wall Expansion Joint Detail

PROVIDE EXPANSION JOINT AT 50'-0" MAXIMUM SPACING. SEE ARCH. DWGS FOR LOCATIONS.




Plan Showing Joint Reinforcement At Wall Corner



Masonry Lintel Schedule							
MAXIMUM	BRICK	CMU LINTEL DIM AND REINF					
OPENING WIDTH	LINTEL ANGLE	DEPTH	8" WALL				
2'-0"	L3 1/2x3 1/2x3/8	8	2#5 BOT				
4'-0"	L3 1/2x3 1/2x3/8	16	2#5 BOT				
6'-0"	L3 1/2x3 1/2x3/8	24	2#7 BOT & 2#5 TOP				
10'-0"	L5x3 1/2x3/8 LLV	24	2#7 BOT & 2#5 TOP				


1. PROVIDE 8" MINIMUM BEARING FOR ALL LINTELS. FOR LINTELS GREATER THAN 6'-0" FILL CELLS SOLID AT EACH SIDE OF OPENING.

Masonry Lintel Detail and Schedule




ALL LAP SPLICES CLASS "B" TENSION.

### Wall Corner Reinforcing Detail




### Depressed Slab Detail



### <u>Plan</u> Masonry Control Joint


### NO SCALE

1. SEE ARCHITECTURAL DRAWINGS FOR VERTICAL MASONRY CONTROL JOINT LOCATIONS. VERTICAL MASONRY CONTROL JOINT SPACING NOT TO EXCEED 25'-0".




Detail "A"

**Masonry Control Joint** NO SCALE



Detail "B" **Masonry Control Joint** NO SCALE



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

## **FAYETTE** COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

Job No.


Sheet Title TYPICAL DETAILS

1207007000

Sheet No.

2013-09-23

S-104




CURB PERPENDICULAR

MAXIMUM SPACING

PERPENDICULAR TO DECK FLUTES

TO FLUTES



Roof Wind Components

- ZONE 1


- ZONE 2


- ZONE 3

and Cladding Diagram

#### MAXIMUM POSITIVE PRESSURE (PSF) MAXIMUM NEGATIVE PRESSURE (PSF) EFFECTIVE WIND AREA (SQ.FT) ZONE +10.0-20.450 +10.0-19.2100 +10.0 -18.7500 +10.0 -18.710 +10.0-34.3-25.850 +10.0 100 +10.0 -22.1500 +10.0-22.110 +10.0 -51.650 +10.0 -31.0-22.1100 +10.0-22.1500 +10.0 10 +18.7-20.250 +16.8 -18.3100 +15.9 -17.5500 +14.0-15.610 +18.7-24.950 -21.1+16.8 100 +15.9 -19.3500 +14.0-15.610 ±31.1 50 ±27.5 ±19.0 100 500 $\pm 19.0$ 10 ±48.4 50 ±39.6 100 $\pm 19.0$







## Components and Cladding Pressures

500

1. SEE COMPONENT AND CLADDING DIAGRAMS FOR WALL AND ROOF ZONES

 $\pm 19.0$ 

2. 4P AND 5P ARE PARAPET WIND PRESSURES

## Mechanical Unit Curb on Existing Roof Support Detail

EXISTING DECK SUPPORT MEMBER BEYOND

Section A

1. CONTRACTOR VERIFY WITH CURB SUPPLIER THAT CURB CAN SPAN 3'-0" AND

STEEL ROOF DECK

SUPPORT UNIT ADEQUATELY.

2. MAXIMUM CURB LOAD 180 LBS/FT

CURB PARALLEL

TO FLUTES -

MC6x12 FOR CURB

SUPPORT PARALLEI

TO DECK FLUTES —

WELD CHANNEL


FLANGE TO DECK SUPPORT MEMBER

- 3. SEE "ROOF OPENING FRAME DETAIL" FOR DUCT OPENING FRAMING.
  4. SEE "JOIST REINFORCEMENT DETAILS" FOR CONCENTRATED LOAD ON JOIST.

5. PROVIDE HOLD DOWN ANCHORAGE WHERE REQUIRED BY BUILDING OFFICIAL.

# Wall Wind Components and Cladding Diagram


- ZONE 4 - ZONE 5 - ZONE 4P - ZONE 5P




25 PSF 6 PSF 25 PSF

Joist Bearing at Top of Column

Snow Load Plan



Joist Reinforcement Detail




Roof Deck Attachment Pattern Layout

Section A

Roof Opening Frame Detail

AT ALL OPENINGS IN ROOF LARGER THAN 8"



WAKEFIELD BEASLEY SI ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX


LBYD, Inc.
Civil and Structural Engineers
900 Circle 75 Parkway, Suite 1300
Atlanta, Georgia, 30339
Main (770) 857–1230
Fax (770) 857–1239

PROJECT NO. 201-13-014.001
These drawings and design intent are the sole property of LBYD, Inc. which may not be reproduced without written permission

Jacksonville Office:

**FAYETTE** COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



Print Record 07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23 1207007000 Sheet Title

TYPICAL DETAILS

Sheet No.

S-105

SCHEDULE OF SPECIAL INSPECTION SERVICES  Fayette County EOC							
MATERIAL (ACTIVITY	0557405	N/N		BLE TO THIS			
MATERIAL / ACTIVITY 1704.2 Inspection of Fabricators	SERVICE	Y/N	EXTENT	AGENT*	DATE COMPLETE		
Verify fabrication/quality control procedures.	In-plant review	Y (3)	Periodic	1			
1704.3 Steel Construction	·						
Material verification of high-strength polts, nuts, and washers.	Review material markings and certificates of compliance	Υ	Periodic	1			
nspection of high-strength bolting:  a. Snug-tight joints b. Pre-tensioned or slip-critical	Field inspection	Υ	Periodic	1			
) Turn-of-nut with matching markings		N	Periodic	_			
) Direct tension indicator		N	Periodic	-			
) Twist-off bolt		N	Periodic	-			
) Turn-of-nut without matching narkings		N	Continuous	-			
) Calibrated wrench		N	Continuous	-			
laterial verification of structural steel:							
. Identification markings	Field inspection	Y	Periodic	1			
. Certified mill tests	Review submittals	У	Each submittal	2			
. Certilled mill tests		Y .	Each submillar	2			
/eld filler materials.	Review certificate of compliance and field verification	Υ	Periodic	1			
tructural steel welding:	Shop and field inspection						
. Complete and partial		Y	Continuous	1			
enetration groove welds  Multi-pass fillet welds							
Multi-pass fillet welds  Single-pass fillet welds > 5/16"		Y N	Continuous	1 -			
. Single-pass fillet welds < 5/16"		Y	Periodic	1			
Floor and roof deck welds		Y	Periodic	1			
einforcing steel welding	Shop and field	•	2500	· ·			
Verification of weldability of eel other than ASTM A 706	inspection	Y	Periodic	1			
. Reinforcing steel-resisting exural and axial forces in attermediate and special moment cames, and boundary elements of		N	Continuous	-			
pecial concrete shear walls, and hear reinforcement		NI .	Continuous				
Shear reinforcement     Other reinforcing steel		N N	Continuous  Periodic	-			
spection of steel frame joint details or compliance with approved construction documents.	Field inspection		. 0.100.10				
. Details such as bracing & stiffening		N	Periodic	-			
Member locations		Υ	Periodic	1			
Application of joint details at each onnection		Υ	Periodic	1			
704.4 Concrete Construction			-		-		
nspection of reinforcing steel	Field inspection	Υ	Periodic	1			
spection of prestressing steel	In-plant or field	N	Periodic	-			
estallation.  Inspection of prestressed concrete:	review In-plant or field						
. Application of prestressing force	review	N	Continuous				
Grouting of bonded prestressing endons in the seismic-force-resisting		N	Continuous	-			
nspection of anchor bolts to be nstalled in concrete prior to and luring placement of concrete where illowable loads have been increased er IBC section 1911.5 or where trength design is used	Field inspection	Y	Continuous	1			
nspection of anchors and reinforcing steel installed in hardened concrete: rerify anchor type, anchor dimensions, hole eleaning procedures, anchor spacing, adge distances, concrete minimum hickness, anchor embedment and ightening torque	Field inspection	Υ	Periodic, or as required by ICC-ES Report	1			
erify use of approved design mix	Field review	Υ	Periodic	1			
resh concrete sampling	Field testing	Υ	Continuous	1			
spection of concrete and shotcrete acement for proper application chniques	Field inspection	Υ	Continuous	1			
oncrete and shotcrete curing perations	Field inspection	Υ	Periodic	1			
rection of precast concrete members	Field inspection	N	Periodic	-			
oncrete strength testing and erification of compliance with	Field testing and review of	Y	Periodic	1			
erification of in-situ concrete rength, prior to stressing of tendons post tensioned concrete and prior removal of shores and forms from eams and structural slabs	Review field testing and laboratory reports	N	Periodic	-			
nspection of formwork for shape,	Field inspection	Y	Periodic	1			
704.5 Masonry Construction				<u> </u>	<del> </del>		
erify proportions of site prepared	Field and submittal review	Υ	Periodic	1			
	Field inspection	Υ	Periodic	1			
or bonded tendons.							
or bonded tendons.  erify construction of mortar joints  erify location of reinforcement and connectors, and placement of	Field inspection	Υ	Periodic	1			
erify construction of mortar joints erify location of reinforcement and connectors, and placement of restressing tendons and anchorages	Field inspection	Y	Periodic Periodic	-			
nortar, grout and prestressing grout or bonded tendons.  Verify construction of mortar joints  Verify location of reinforcement and connectors, and placement of restressing tendons and anchorages  Verify prestressing technique  Verify size and location of structural pasonry elements.	Field inspection Field and						
erify construction of mortar joints erify location of reinforcement and connectors, and placement of restressing tendons and anchorages erify prestressing technique	Field inspection	N	Periodic	-			

Verify size, grade, and type of reinforcement	Field inspection	Y	Periodic	1	
Verify welding of reinforcing bars  Verify protection of masonry during	Field inspection	Y	Continuous	1	
hot/cold weather	Field inspection	Y	Periodic Level 1 -	1	
Verify grout space is clean prior to grouting	Field inspection	N Y	Periodic  Level 2 - Continuous	1	
Verify grout placement complies with code and construction document provisions	Field inspection	Y	Continuous	1	
Testing of grout specimens, mortar specimens, and/or prisms required by construction documents	Field testing	Y	Periodic	1	
Observe preparation of prisms required by construction documents  Verify compliance with required	Field inspection	Y	Continuous	1	
testing and inspection provisions of construction documents and the approved submittals	Field testing and inspection	Y	Periodic	1	
Verify grade and size of prestressing tendons and anchorages	Field inspection	N	Periodic	-	
Verify proper grouting of prestressing tendons	Field inspection	N	Continuous	-	
Verify application and measurement of prestressing force	Field inspection	N N	Level 1 - Periodic Level 2 - Continuous	-	
1704.6 Wood Construction	<u> </u>	T	1	<u> </u>	1
Inspection of the fabrication process of wood structural elements and assemblies in accordance with Section 1704.2	In-plant review	N	Periodic	-	
For high-load diaphragms, verification of grade and thickness of structural panel sheathing	Field inspection	N	Periodic	-	
For high-load diaphragms, verify nominal size of framing members at adjoining panel edges, nail or staple diameter and length, number of fastener lines, and that spacing between fasteners in each line and at edge margins agrees with approved bldg plans	Field inspection	N	Periodic	-	
1704.7 Soils  Verify materials below shallow foundations are adequate to achieve	Field inspection	Y	Periodic	1	
the design bearing capacity  Verify excavations are extended to proper depth and have reached	Field inspection	Y	Periodic	1	
proper material  Perform classification and testing of	Field inspection	Y	Periodic	1	
controlled fill materials  Verify use of proper materials, densities, and lift thicknesses during placement and compaction of	Field inspection	Y	Continuous	1	
controlled fill  Prior to placement of controlled fill, observe subgrade and verify that site	Field inspection	Y	Periodic	1	
has been prepared properly  1704.8 Pile Foundations					
Verify pile materials, sizes and lengths comply with requirements	Field inspection and submittal review.	N	Continuous	-	
Verify capacities of test piles and results of additional load tests, as required	Field inspection and submittal review.	N	Continuous	-	
Observe pile driving operations and maintain complete and accurate records for each pile	Field inspection and submittal review. Submittal to the bldg official of the results of pile load tests.	N	Continuous	-	
Verify placement locations and plumbness, confirm type and size of hammer, record number of blows per foot of penetration, verify required penetrations to achieve design capacity, record tip and butt elevations, and document any pile damage	Field inspection and submittal review	N	Continuous	-	
For steel piles, perform additional inspections per Section 1704.3	See Section 1704.3	N	See Section 1704.3	-	
For concrete piles and concrete-filled piles, perform additional inspections per Section 1704.4	See Section 1704.4	N	See Section 1704.4	-	
For specialty piles, perform additional inspections as determined by the registered design professional in	Field inspection	N	Periodic	-	
responsible charge For augered uncased piles and caisson piles, perform inspections per	See Section 1704.9	N N	See Section 1704.9	-	
Section 1704.9  1704.9 Pier Foundations	1704.9		1704.9		
Observe drilling operations and verify that complete and accurate records are maintained for each pier.	Field inspection and submittal review.	N	Continuous	-	
Verify placement locations and plumbness, confirm pier diameters, bell diameters (if applicable), lengths, embedment into bedrock (if applicable), and adequate end bearing strata capacity.	Field inspection and submittal review.	N	Continuous	-	
For concrete piers, perform additional inspections per Section 1704.4.	See Section	N	See Section 1704.4	-	
For masonry piers, perform additional inspections per Section 1704.5.	See Section 1704.5	N	See Section 1704.5	-	
1704.10 Sprayed Fire-resistant M	/laterials				
Verify surface condition preparation of structural members.	Field inspection	N	Periodic	-	
Verify application of sprayed fire-resistant materials.	Field inspection	N	Periodic	-	
Verify average thickness of sprayed fire-resistant materials applied to structural members.  Verify density of the sprayed	Field inspection	N	Periodic	-	
fire-resistant material complies with approved fire-resistant design.  Verify the cohesive/adhesive bond	and submittal review Field inspection	N	Periodic	-	
verify the conesive/agnesive bond strength of the cured sprayed fire-resistant material.  1704.11 Mastic and Intumescent	and submittal review	N Coatings	Per IBC section 1704.101.5	-	
Inspect mastic and intumescent fire-resistant coatings applied to structural elements and decks, in	Field inspection	N	Periodic	-	
accordance with AWCI 12-B.  1704.12 Exterior Insulation and	Finish Systems (	EIFS)			
Verify materials, details and installations are per construction documents.	Field inspection	N	Periodic	-	
1704.13 Special Cases Work unusual in nature, including but				_	
mot limited to alternative construction materials, unusual design applications, systems or materials with special manufacturer requirements.	Submittal review, shop inspection and/or field inspection.	N	-	-	
		•			•

1704.14 Smoke Control Systems Leakage testing and recording of device					
locations prior to concealment.	Field testing	Y	Periodic	1	
Prior to occupancy and after sufficient completion, pressure difference testing, flow measurements, and detection and control verification.	Field testing	Y	Periodic	1	
1707.2 Structural Steel Special Insp	pections for Seism	nic Resistanc	ee		1
Continuous inspection of structural welding in accordance with AISC 341, Seismic Provisions	Shop and field inspection	N N	Continuous	-	
1707.3 Structural Wood Special Ins Inspection of field gluing operations of	pections for Seisi	mic Resistan	ce		
elements of the seismic-force resisting system.  Inspection of nailing, bolting, anchoring	Field inspection	N	Continuous	-	
and other fastening of components within the seismic-force-resisting system.	Shop and field inspection	N	Periodic	-	
1707.4 Cold-formed Steel Framing Inspection during welding operations of		ns for Seismi	c Resistance		
elements of the seismic-force-resisting system.	Shop and field inspection	N	Periodic	-	
Inspections for screw attachment, bolting, anchoring and other fastening of components within the seismic-force-resisting system.	Shop and field inspection	N	Periodic	-	
1707.5 Pier Foundations Special In	spections for Seis	mic Resistar	nce		
Inspection during placement of reinforcing.	Field inspection	N	Periodic	-	
Inspection during placement of concrete.	Field inspection	N	Continuous	-	
1707.6 Storage Racks and Access Inspection during the anchorage of	Floors Special Ins	pections for	Seismic Resista	ance	1
access floors and storage racks 8 feet or greater in height.  1707.7 Architectural Components \$	Field inspection	N s for Seismic	Periodic	-	
Inspection during the erection and fastening of exterior cladding and interior and exterior veneer.	Field inspection	N N	Periodic	-	
Inspection during the erection and fastening of interior and exterior non load bearing walls.	Field inspection	N	Periodic	-	
1707.8 Mechanical and Electrical C	omponents Speci	<u></u> al Inspection	s for Seismic R	esistance	
Inspection during the anchorage of electrical equipment for emergency or standby power systems.	Field inspection	N	Periodic	-	
Inspection during the anchorage of other electrical equipment.	Field inspection	N	Periodic	-	
Inspection during installation of piping systems intended to carry flammable, combustible, or highly toxic contents and their associated mechanical units.	Field inspection	N	Periodic	-	
Inspection during the installation of HVAC ductwork that will contain hazardous materials	Field inspection	N	Periodic	-	
Inspection during the installation of	Field inspection	N	Periodic	-	
vibration isolation systems.  1707.9 Designated Seismic System	Verification				
Inspect and verify that that the component label, anchorage or mounting conforms to the certificate of compliance in accordance with 1708.5.	Field inspection	N	Periodic	-	
1707.10 Seismic Isolation System Inspection during the fabrication and installation of isolator units and energy	Shop and field		Devientie		
dissipation devices used as part of the seismic isolation system.  1708.1 Masonry Testing and Verific	inspection	N Resistance	Periodic	-	
Certificates of compliance used in	Review submittals	Y	Each submittal	1	
masonry construction  Verification of f'm and f'AAC prior to	Review submittals	Y	Each Submittal	1	
construction Verification of f'm and f'AAC every 5000	Review submittals				
SF during construction  Verification of proportions of materials in	and field testing	Y	Periodic	1	
mortar and grout as delivered to the site	Field review	Y	Periodic	1	
1708.3 Reinforcing and Prestressin Review certified mill test reports for each	g Steel Testing fo	r Seismic Re	esistance		
shipment of reinforcing steel used to resist flexural, shear and axial forces in concrete intermediate frames, special moment frames and special concrete or masonry shear walls.	Review testing reports	N	Each submittal	-	
Verify reinforcing steel weldability of ASTM A615 reinforcing used to resist seismic flexural and axial forces in special moment frames and shear walls	Review testing reports	N	Each submittal	-	
1708.4 Structural Steel Testing for Test In accordance with the quality assurance requirements of AISC 341, Seismic Provisions	Seismic Resistand Shop and field testing	ce N	Per AISC 341	-	
Ultrasonically test for discontinuities behind and adjacent to welds with base metal thicker than 1.5 inches where	Shop and field	N	Each	-	
subject to through-thickness weld shrinkage strains.	testing		occurrence		
1708.5 Seismic Qualification of Med		trical Equipm	ent		
Review certificate of compliance for designated seismic system components	Certificate of compliance review	N	Each submittal	-	
1708.6 Seismicly Isolated Structure	:: :s T				
Test seismic isolation system in accordance with ASCE 7 Section 17.8	Prototype testing	N	Per ASCE 7	-	
* INSPECTION AGENTS (Include Na	me, Firm, Address	and Telephor	ne Number)		
Special Inspector (Firm to be determined	,	ingham, AL 352	33 205-251-4500)		
3					
3 4 5					
3 4 5 6					
2. Structural Engineer-of-Record (LBYD, Inc.)  4  5  6  7  Notes:	hall be	0.Deci - 7	oined a final	al les	d not built a Co.
3 4 5 6 7	ed or tested. Any confl	lict of interest mu	ust be disclosed pri	or to commenci	-

Are Requirements for Wind Resistance included in the Statement of Special Inspections? □Yes ■No





ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



are	3, Wakefield protected by	the copyri	ght laws of	the United	States. Th	nese
draw repr	ings or any oduced in an akefield Beas	part therec y form or	of may not	be used fo	r any purp	ose o

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23

1207007000

Sheet Title
SCHEDULE OF SPECIAL
INSPECTIONS

Sheet No.

S-106





Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

### FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

 Date
 Job No.

 2@13-@9-23
 12@7@@7@@0


Theet Title
FOUNDATION

PLAN

Sheet No.

S-200

FOR CONSTRUCTION






### Foundation Plan

#### 1/8"=1'-0"

NOTES.

- FINISH FLOOR REFERENCE ELEVATION (TOP OF SLAB) 0'-0", UNLESS NOTED.
   TOP OF FOOTING ELEVATIONS -1'-4" BELOW FINISH FLOOR, UNLESS NOTED.
   FOR SLAB ON GRADE CONSTRUCTION, SEE GENERAL NOTES AND TYPICAL DETAILS.
- 4. PROVIDE 2#5x5'-0" LONG AT MID-DEPTH OF SLAB AT ALL REENTRANT CORNERS AND DISCONTINUOUS CONTROL JOINTS.
- 5. S DENOTES 1'-4" FOOTING STEP SEE TYPICAL DETAILS





### Parking Lot Ramp Retaining Wall Plan

B"=1'-0"


NOTES:

1. SEE ARCHITECTURAL DRAWINGS FOR LOCATION OF PARKING LOT RAMP.

2. SEE CIVIL DRAWINGS FOR FINISH GRADE ELEVATIONS.

3. LOCATIONS OF FOOTING STEPS SHOWN IN PLAN ARE APPROXIMATE, STEP FOOTING AS REQUIRED.





Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23

Job No. 1207007000


Sheet Title ROOF FRAMING

**PLAN** 

Sheet No.

S-201

FOR CONSTRUCTION






### Roof Framing Plan

1/8"=1'-0"

- 1. TOP OF STEEL (JOIST BEARING) ELEVATION AT COLUMN LINE 1 14'-7" AND 15'-8" AT COLUMN LINE 4, UNLESS NOTÉD. TOP OF STEEL IS UNIFORMLY SLOPING BETWEEN NOTED
- 2. ROOF SYSTEM: 1 1/2" WIDE RIB, STEEL ROOF DECK ON STEEL JOISTS AT UNIFORM SPACING NOTED ON PLAN.
- 3. VERTICAL BEAM SHEAR REACTIONS ARE INDICATED BENEATH BEAM SIZES AS R=#k, WHERE # IS THE MAGNITUDE OF THE FACTORED LOAD IN KIPS.
- 4. EQUIPMENT LOCATIONS AND WEIGHTS SHOWN ARE APPROXIMATE. THE GENERAL CONTRACTOR SHALL COORDINATE AND VERIFY SIZE, WEIGHT, AND LOCATION OF ALL MECHANICAL UNITS WITH JOIST MANUFACTURER. DO NOT SCALE FROM THESE DRAWINGS. REFERENCE MECHANICAL UNIT CURB ON EXISTING ROOF SUPPORT DETAIL ON S-105 FOR SUPPORT FRAMING REQUIRED.
- 5. SEE TYPICAL DETAILS FOR JOIST REINFORCEMENT PIPE HANGER DETAIL. SEE MECHANICAL,
- PLUMBING, AND FIRE PROTECTION DRAWINGS. 6. SEE TYPICAL DETAILS FOR FRAMING AT ROOF OPENINGS. COORDINATE LOCATION OF
- OPENING AND WEIGHT OF EQUIPMENT WITH MECHANICAL DRAWINGS.
- 7. TOP OF CMU WALLS 18'-0" UNLESS NOTED
- 8. BEAMS PARALLEL TO JOIST ARE 2 1/2" HIGHER THAN SUPPORTING BEAMS
- 9. # DENOTES CENTERLINE OF BEAM SPLICE SEE TYPICAL DETAILS



WAKEFIELD BEASLEY & ASSOCIATES

ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

> **FAYETTE** COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

Job No. 1207007000

SECTION AND **DETAILS** 

S-300





Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions


2013-09-23

1207007000


Sheet Title
SECTION AND
DETAILS

Sheet No.

S-301







3 Section 3/4"=1'-0"

	MECHANICAL	ADDK	
	ABBREVIATION/DEFINITION		ABBREVIATION/DEFINITION
A/C	ABOVE CEILING	IN. WC	INCHES WATER COLUMN
AFF	ABOVE FINISHED FLOOR	LAT	LEAVING AIR TEMPERATURE (*F)
AHU	AIR HANDLING UNIT	MBH	1000 BRITISH THERMAL UNITS PER HOUR
CFM	CUBIC FEET PER MINUTE	MD	MANUAL DAMPER
CU	CONDENSING UNIT	MOD	MOTOR OPERATED DAMPER
CHR	CHILLED WATER RETURN	MS	MINI-SPLIT SYSTEM HVAC UNIT
CHS	CHILLED WATER SUPPLY	OA	OUTSIDE AIR
C.T.E.	CONNECT TO EXISTING	PD	PRESSURE DROP
CWP	CONDENSER WATER PUMP	PRV	PRESSURE REDUCING VALVE
D	CONDENSATE DRAIN	RA	RETURN AIR
DB	DRY BULB TEMPERATURE (*F)	RTU	ROOF MOUNTED HVAC UNIT
EAT	ENTERING AIR TEMPERATURE (°F)	SB	SECURITY BARS
EF	EXHAUST FAN	SMD	SMOKE DAMPER
ESP	EXTERNAL STATIC PRESSURE	SPS	DUCT MOUNTED STATIC PRESSURE SENSOR
FD	FIRE DAMPER	SPD	SPLITTER DAMPER
HP	HEAT PUMP	VFD	VARIABLE FREQUENCY DRIVE
HWC	HOT WATER COIL	WB	WET BULB TEMPERATURE (°F)
HWP	HOT WATER PUMP	WL	WALL LOUVER
HWR	HOT WATER RETURN	W.O.	WALL OPENING
HWS	HOT WATER SUPPLY		

NOTE: THESE ARE STANDARD ABBREVIATIONS, ALL ABBREVIATIONS SHOWN ABOVE MAY NOT APPEAR ON DRAWINGS.

### MECHANICAL LEGEND

ING ING ING IMENT DESIGNATION ISTRIBUTION TAG PE B. SIZE C. CFM SIZE - RECTANGULAR (INCHES) SIZE - ROUND (INCHES)		THERMOSTAT OR TEMERATURE SENSOR  HUMIDISTAT OR HUMIDITY SENSOR  WALL MOUNTED SWITCH  FLEXIBLE DUCTWORK  MANUAL DAMPER  FIRE DAMPER  DUCT WITH LINER  DUCT TRANSITION  SQUARE TO ROUND DUCT TRANSITION
MENT DESIGNATION  ISTRIBUTION TAG  PE B. SIZE C. CFM  SIZE - RECTANGULAR (INCHES)		WALL MOUNTED SWITCH FLEXIBLE DUCTWORK MANUAL DAMPER FIRE DAMPER DUCT WITH LINER DUCT TRANSITION
MENT DESIGNATION  ISTRIBUTION TAG  PE B. SIZE C. CFM  SIZE - RECTANGULAR (INCHES)		FLEXIBLE DUCTWORK  MANUAL DAMPER  FIRE DAMPER  DUCT WITH LINER  DUCT TRANSITION
ISTRIBUTION TAG PE B. SIZE C. CFM SIZE - RECTANGULAR (INCHES)		MANUAL DAMPER FIRE DAMPER DUCT WITH LINER DUCT TRANSITION
ISTRIBUTION TAG PE B. SIZE C. CFM SIZE – RECTANGULAR (INCHES)		FIRE DAMPER DUCT WITH LINER DUCT TRANSITION
PE B. SIZE C. CFM SIZE – RECTANGULAR (INCHES)		DUCT WITH LINER DUCT TRANSITION
PE B. SIZE C. CFM SIZE – RECTANGULAR (INCHES)		DUCT TRANSITION
SIZE - RECTANGULAR (INCHES)		
, ,		SQUARE TO ROUND DUCT TRANSITION
SIZE - ROUND (INCHES)		
	SPS	DUCT MOUNTED STATIC PRESSURE SENSOR
SER	<b>≡</b> SD>	DUCT MOUNTED SMOKE DETECTOR
		WALL OPENING
RN AIR DISTRIBUTION DEVICE	•••••	SECURITY BARS
		WALL LOUVER
JST AIR DISTRIBUTION DEVICE	<u>S</u> ——	SMOKE DAMPER
WORK (POSITIVE PRESSURE)	M	MOTOR OPERATED DAMPER
		SPLITTER DAMPER
NORK (NEGATIVE PRESSURE)		SUPPLY AIR ARROW
	- <del></del>	RETURN AIR ARROW
ECT TO EXISTING		
WORK - EXISTING TO REMAIN	<i>\$[[]]</i> ;	REMOVE EXISTING DUCTWORK
	VORK (POSITIVE PRESSURE)  VORK (NEGATIVE PRESSURE)  ECT TO EXISTING	VORK (POSITIVE PRESSURE)  WORK (NEGATIVE PRESSURE)  ECT TO EXISTING

### GENERAL NOTES:

- 1. REFER TO ALL DRAWINGS AND SPECIFICATIONS. CONTRACTOR SHALL BE RESPONSIBLE FOR APPLICABLE PROVISIONS THEREIN.
- 2. COORDINATE WORK WITH ALL OTHER TRADES PRIOR TO INSTALLATION.
- 3. INSTALL SPACE THERMOSTATS 48" ABOVE FINISHED FLOOR.
- 4. DRAWINGS ARE GENERALLY DIAGRAMMATIC AND DO NOT NECESSARILY SHOW EVERY FITTING AND DETAIL. INSTALL DUCTS, EQUIPMENT AND CONTROLS IN A NEAT WORKMANLIKE MANNER, AND IN ACCORDANCE WITH GOOD PRACTICE FOR A COMPLETE WORKABLE INSTALLATION. AVOID CONFLICT WITH OTHER WORK; MAKE ADEQUATE PROVISIONS FOR PREVENTING NOISE AND VIBRATION. ARRANGE EQUIPMENT INTO THE AVAILABLE SPACE IN A MANNER TO MAKE WORKING PARTS ACCESSIBLE FOR MAINTENANCE AND SERVICE.
- 5. DUCT SIZES SHOWN ARE INSIDE CLEAR DIMENSIONS.
- 6. COORDINATE VOLTAGE AND PHASE OF EACH PIECE OF EQUIPMENT WITH ELECTRICAL CONTRACTOR BEFORE ORDERING.
- 7. FOR ROUND DUCT TAKE-OFF FROM RECTANGULAR SHEET METAL DUCTS, USE JER-AIR MODEL S-2, FITTING WITH DAMPER. FOR ROUND DUCT TAKE-OFF FROM ROUND DUCTS, USE JER-AIR MODEL RBD-38, FITTING WITH DAMPER
- 8. FLEXIBLE DUCT RUNOUTS TO CEILING DIFFUSERS SHALL BE INSTALLED FREE OF KINKS AND SAGS. BRANCH DUCTWORK SHALL BE SIZED TO MATCH THE INLET OF THE DIFFUSERS SERVED. MAXIMUM LENGTH 7 FEET.
- 9. COMPLETION AND TESTS SHALL INCLUDE CLEANING AND LUBRICATION OF EQUIPMENT, AND ADJUSTMENTS FOR PROPER OPERATION. ADJUST DAMPERS, REGISTERS AND DIFFUSERS FOR PROPER AIR DISTRIBUTION. CHECK SYSTEM UNDER ACTUAL OPERATING CONDITIONS AND MAKE ADJUSTMENTS FOR A UNIFORM TEMPERATURE THROUGH THE CONDITIONED SPACE.
- 10. LOCATIONS SHOWN FOR EQUIPMENT ARE APPROXIMATE LOCATIONS. CONTRACTOR SHALL COORDINATE WITH THE FIELD CONDITIONS FOR THE EXACT LOCATION AND CONFIGURATION. AND MODIFY DUCT SYSTEM ACCORDINGLY.
- 11. CONTRACTOR SHALL FIELD VERIFY AVAILABLE SPACE FOR DUCTWORK BEFORE FABRICATING. CONTRACTOR SHALL MODIFY DUCTWORK TO FIT AVAILABLE FIELD CONDITIONS. CUTTING OR OTHERWISE ALTERING ANY STRUCTURAL MEMBERS SHALL NOT BE PERMITTED WITHOUT WRITTEN PERMISSION FROM THE ARCHITECT.
- 12. SHEET METAL DUCTWORK SHOWN AS BEING INTERNALLY LINED SHALL BE LINED WITH 1" THICK, 1-1/2 LB/CU.FT. DENSITY DUCT LINER, MANVILLE LINACOUSTIC OR EQUAL.
- 13. INTERRUPTION OF SERVICE: THE DRAWINGS ARE BELIEVED TO BE A FAIRLY ACCURATE REPRESENTATION OF THE EXISTING WORK. HOWEVER, THE CONTRACTOR SHALL BE RESPONSIBLE FOR MAKING ON SITE INVESTIGATIONS TO DETERMINE THE ACCURACY OF THE EXISTING CONDITION DRAWINGS. NO ATTEMPT HAS BEEN MADE TO SHOW ON THE DRAWINGS MECHANICAL WORK WHICH IS NOT CONSIDERED TO BE RELEVANT TO THIS PROJECT. IN PERFORMANCE OF THE WORK, IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY EXISTING CONDITIONS AND THE EFFECT THAT THE WORK SHOWN ON THE DRAWINGS WILL HAVE ON THE EXISTING SERVICES. SHOULD THE ACTUAL CONDITIONS BE DIFFERENT FROM THOSE SHOWN ON THE DRAWINGS, THE CONTRACTOR SHALL NOTIFY THE OWNER FOR FURTHER INSTRUCTIONS PRIOR TO THE DISRUPTION OF THE EXISTING SERVICES.
- 14. EQUIPMENT SHALL BE INSTALLED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.
- 15. ROOFTOP MOUNTED EQUIPMENT SHALL BE INSTALLED ON 12" HIGH INSULATED ROOF CURB. TOP OF CURB SHALL BE LEVEL.
- 16. PORTIONS OF DUCTWORK VISIBLE THROUGH SUPPLY AND RETURN AIR OPENINGS SHALL BE PAINTED FLAT BLACK.
- 17. TRAP AND ROUTE CONDENSATE FROM MS-1 TO HUB DRAIN.

DUCTLESS SPLIT SYSTEM							
MARK	AIR UNIT	COOLING CYCLE			REMARKS		
	CFM	TOTAL	AMBIENT	SEER			
		(BTU/HR)	TEMP (°F)				
MS-1/CU-1	330	12,000	95	10.2	1		

<u>REMARKS</u>

1. BASIS OF DESIGN: SANYO KS1251 (INDOOR UNIT) AND CL1251 (OUTDOOR UNIT)

	AIR DISTRIBUTION DEVICE						
MARK	BASIS OF	DESCRIPTION	NOTES				
	DESIGN						
	(MAKE & MODEL)						
D	TITUS	DIFFUSER, CONE FACE	1				
	TMS	24x24 FACE, LAY IN					
С	TITUS	DIFFUSER, CONE FACE	1				
	TMS	12x12 FACE, SURFAC MOUNTED					
E	TITUS	EGGCRATE EXHAUST	1				
	50F	REGISTER					
R	TITUS	EGGCRATE RETURN					
	50F	GRILLE					

#### NOTES:

PROVIDE WITH OPPOSED BLADE BALANCING DAMPER.

FANS													
MARK	TYPE CFM ESP MOTOR H.P. DRIVE				MAX	BASIS OF DESIGN	REMARKS						
			(IN WC)	OR		NOISE							
				[WATTS]		(SONES)							
EF-1	ROOF CENTRIFUGAL	225	0.375	1/4	DIRECT	5	LOREN COOK ACED 90C15DL	1, 2, 3					

### REMARKS:

- 1. INTERLOCK WITH RTU-3.
- 2. PROVIDE MATCHING ROOF CURB.
- WITH INTEGRAL DISCONNECT.
- 4. PROVIDE WITH SPEED CONTROLLER. MOUNT ON DUCT ABOVE AN ACCESSIBLE CEILING.

	PACKAGED ROOFTOP UNITS															
MARK	TYPE		FAN COOLING										HEATIN	IG		REMARKS
		CFM	O.A.	ESP	MAX	TOTAL	SENS	EAT	EAT	AMB. AIR	MIN.	INPUT	OUTPUT	MIN.	NO.	
			CFM	(IN W.C.)	MOTOR	CAPACITY	CAPACITY	DB	WB	TEMP DB	ARI	(BTU/HR)	(BTU/HR)	AFUE	STAGES	
					HP	(BTU/HR)	(BTU/HR)	(°F)	(°F)	(°F)	SEER					
RTU-1	ELEC/GAS	1600	110	0.7	1.5	45	39	78	64	95	13	75	60	80%	1	
RTU-2	ELEC/GAS	1200	170	0.7	1.5	36	28	80	66	95	13	75	60	80%	1	
RTU-3	ELEC/GAS	1020	170	0.7	0.75	32	23	80	67	95	13	70	56	80%	1	
RTU-4	ELEC/GAS	1920	265	0.7	1.5	59	45	80	67	95	13	75	60	80%	2	



#### ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



404/355-9334 main 404/835-1118 fax



110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

 Date
 Job No.

 2013-09-23
 1207007000

 Sheet Title

MECHANICAL — GENERAL NOTES & SCHEDULES

Sheet No.

M001

Designer/Contractor: 110 Volunteer Way Fayetteville, GA 30215

COMcheck Software Version 3.9.1

**Mechanical Compliance Certificate** 

Fred Gordon Covalent Consulting 1708 Peachtree Street, NW Atlanta, GA 30309

### **Section 2: General Information**

Building Location (for weather data): Climate Zone:

#### **Section 3: Mechanical Systems List**

Quantity System Type & Description

1 HVAC System RTU-1 (Single Zone):

Heating: 1 each - Central Furnace, Gas, Capacity = 75 kBtu/h, Efficiency = 80.00% Et Cooling: 1 each - Rooftop Package Unit, Capacity = 45 kBtu/h, Efficiency = 13.00 SEER, Air-Cooled Condenser 1 HVAC System RTU-2 (Single Zone):

Heating: 1 each - Central Furnace, Gas, Capacity = 75 kBtu/h, Efficiency = 80.00% Et Cooling: 1 each - Rooftop Package Unit, Capacity = 36 kBtu/h, Efficiency = 13.00 SEER, Air-Cooled Condenser 1 HVAC System RTU-3 (Single Zone):

Heating: 1 each - Central Furnace, Gas, Capacity = 70 kBtu/h, Efficiency = 80.00% Et Cooling: 1 each - Rooftop Package Unit, Capacity = 32 kBtu/h, Efficiency = 13.00 SEER, Air-Cooled Condenser 1 HVAC System RTU-4 (Single Zone):

Heating: 1 each - Central Furnace, Gas, Capacity = 75 kBtu/h, Efficiency = 80.00% Et Cooling: 1 each - Rooftop Package Unit, Capacity = 59 kBtu/h, Efficiency = 13.00 SEER, Air-Cooled Condenser, No Economizer, Economizer exception: Filtration Requirements

1 Water Heater 1: Electric Storage Water Heater, Capacity: 30 gallons, Efficiency: 0.93 EF

#### Section 4: Requirements Checklist

Requirements Specific To: HVAC System RTU-1:

☐ 1. Equipment minimum efficiency: Central Furnace (Gas): 80.00 % Et (or 78% AFUE) 2. Equipment minimum efficiency: Rooftop Package Unit: 13.00 SEER

Requirements Specific To: HVAC System RTU-2:

☐ 1. Equipment minimum efficiency: Central Furnace (Gas): 80.00 % Et (or 78% AFUE)

2. Equipment minimum efficiency: Rooftop Package Unit: 13.00 SEER

Requirements Specific To: HVAC System RTU-3:

☐ 1. Equipment minimum efficiency: Central Furnace (Gas): 80.00 % Et (or 78% AFUE) 2. Equipment minimum efficiency: Rooftop Package Unit: 13.00 SEER

Requirements Specific To: HVAC System RTU-4:

1. Equipment minimum efficiency: Central Furnace (Gas): 80.00 % Et (or 78% AFUE)

Project Title: Fayette County EOC

Report date: 09/19/13 Data filename: \\FSERV\files\Projects\13-046 Fayette Co EOC\Comcheck.cck Page 1 of 6

☐ 2. Equipment minimum efficiency: Rooftop Package Unit: 13.00 SEER

 $\hfill \square$  3. Integrated economizer is required for this location and system. Exception(s):

☐ Air/evap condenser and extensive outside-air filtration

Requirements Specific To: Water Heater 1: 1. Water heating equipment meets minimum efficiency requirements: Electric Water Heater efficiency: 0.89 EF (211 SL, Btu/h (if > 12

☐ 2. First 8 ft of outlet piping is insulated

☐ 3. Hot water storage temperature controls that allow setpoint of 90°F for non-dwelling units and 110°F for dwelling units. ■ 4. Heat traps provided on inlet and outlet of storage tanks

Generic Requirements: Must be met by all systems to which the requirement is applicable:

1. Plant equipment and system capacity no greater than needed to meet loads

Standby equipment automatically off when primary system is operating

Multiple units controlled to sequence operation as a function of load

2. Minimum one temperature control device per system ☐ 3. Minimum one humidity control device per installed humidification/dehumidification system

☐ 4. Load calculations per ASHRAE/ACCA Standard 183. 5. Automatic Controls: Setback to 55°F (heat) and 85°F (cool); 7-day clock, 2-hour occupant override, 10-hour backup

Continuously operating zones

2 kW demand or less, submit calculations ☐ 6. Outside-air source for ventilation; system capable of reducing OSA to required minimum

7. R-5 supply and return air duct insulation in unconditioned spaces R-8 supply and return air duct insulation outside the building

R-8 insulation between ducts and the building exterior when ducts are part of a building assembly

Ducts located within equipment

Ducts with interior and exterior temperature difference not exceeding 15°F.

a. Mechanical fasteners and sealants used to connect ducts and air distribution equipment Ducts sealed - longitudinal seams on rigid ducts; transverse seams on all ducts; UL 181A or 181B tapes and mastics

Continuously welded and locking-type longitudinal joints and seams on ducts operating at static pressures less than 2 inches w.g. pressure classification

 $\blacksquare$  10.Hot water pipe insulation: 1.5 in. for pipes <=1.5 in. and 2 in. for pipes >1.5 in. Chilled water/refrigerant/brine pipe insulation: 1.5 in. for pipes <=1.5 in. and 1.5 in. for pipes >1.5 in.

Steam pipe insulation: 1.5 in. for pipes <=1.5 in. and 3 in. for pipes >1.5 in.

Piping within HVAC equipment.

Fluid temperatures between 55 and 105°F.

Fluid not heated or cooled with renewable energy.

Piping within room fan-coil (with AHRI440 rating) and unit ventilators (with AHRI840 rating).

Runouts <4 ft in length.</p>

☐ 11.Operation and maintenance manual provided to building owner

☐ 12.Thermostatic controls have 5°F deadband

☐ Thermostats requiring manual changeover between heating and cooling

Special occupancy or special applications where wide temperature ranges are not acceptable and are approved by the authority

☐ 13. Balancing devices provided in accordance with IMC (2006) 603.17

14. Demand control ventilation (DCV) present for high design occupancy areas (>40 person/1000 ft2 in spaces >500 ft2) and served by systems with any one of 1) an air-side economizer, 2) automatic modulating control of the outdoor air damper, or 3) a design outdoor airflow greater than 3000 cfm.

Systems with heat recovery.

Multiple-zone systems without DDC of individual zones communicating with a central control panel.

Systems with a design outdoor airflow less than 1200 cfm.

Project Title: Fayette County EOC Data filename: \\FSERV\files\Projects\13-046 Fayette Co EOC\Comcheck.cck

Report date: 09/19/13 Page 2 of 6

Spaces where the supply airflow rate minus any makeup or outgoing transfer air requirement is less than 1200 cfm.

☐ 15.Motorized, automatic shutoff dampers required on exhaust and outdoor air supply openings Exception(s):

Gravity dampers acceptable in buildings <3 stories</p>

Gravity dampers acceptable in systems with outside or exhaust air flow rates less than 300 cfm where dampers are interlocked

☐ 16.Automatic controls for freeze protection systems present

17. Exhaust air heat recovery included for systems 5,000 cfm or greater with more than 70% outside air fraction or specifically exempted

Hazardous exhaust systems, commercial kitchen and clothes dryer exhaust systems that the International Mechanical Code prohibits the use of energy recovery systems.

Systems serving spaces that are heated and not cooled to less than 60°F.

☐ Where more than 60 percent of the outdoor heating energy is provided from site-recovered or site solar energy.

Heating systems in climates with less than 3600 HDD.

☐ Cooling systems in climates with a 1 percent cooling design wet-bulb temperature less than 64°F.

Systems requiring dehumidification that employ energy recovery in series with the cooling coil.

Laboratory fume hood exhaust systems that have either a variable air volume system capable of reducing exhaust and makeup air volume to 50 percent or less of design values or, a separate make up air supply meeting the following makeup air requirements: a) at least 75 percent of exhaust flow rate, b) heated to no more than 2°F below room setpoint temperature, c) cooled to no lower than 3°F above room setpoint temperature, d) no humidification added, e) no simultaneous heating and cooling.

#### **Section 5: Compliance Statement**

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 2009 IECC requirements in COMcheck Version 3.9.1 and to comply with the mandatory requirements in the Requirements Checklist.

#### **Section 6: Post Construction Compliance Statement**

HVAC record drawings of the actual installation, system capacities, calibration information, and performance data for each equipment

HVAC O&M documents for all mechanical equipment and system provided to the owner by the mechanical contractor.

Written HVAC balancing and operations report provided to the owner.

Principal Mechanical Designer-Name Signature

The above post construction requirements have been completed.

Project Title: Fayette County EOC Data filename: \\FSERV\files\Projects\13-046 Fayette Co EOC\Comcheck.cck

Report date: 09/19/13 Page 3 of 6



#### ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



404/355-9334 main

FAYETTE

110 Volunteer Way Fayetteville, Georgia



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.


07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23 1207007000 MECHANICAL - COMCHECK

REPORT

2 DETAIL - ROOF TOP UNIT Scale: NONE



1 MECHANICAL - FLOOR PLAN
Scale: 1/8" = 1'-0"



ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

Covalent
Consulting,LLC

1708 Peachtree St.
Suite 210
Atlanta, GA 30309
404/355-9334 main
404/835-1118 fax

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright lows of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consen

Print Record

07/26/2013: 80% CD Set for Review
09/23/2013: RELEASE FOR BID
12/02/13 FOR CONSTRUCTION

Revisions

*Date* 2013-09-23

*Job No.* 1207007000

Sheet Title

MECHANICAL —
FLOOR PLAN

Sheet No.

M101

	FIRE PROTECTION ABBREVIATIONS										
	ABBREVIATION/DEFINITION	ABBREVIATION/DEFINITION									
A/C	ABOVE CEILING	EL	ELEVATION								
AFF	ABOVE FINISHED FLOOR	F	FIRE LINE								
AFG	ABOVE FINISHED GRADE	FLR	FLOOR								
B/F	BELOW FLOOR	FF	FINISHED FLOOR								
B/G	BELOW GRADE	ΙE	INVERT ELEVATION								
BLDG	BUILDING	GEN	GENERAL								
CI	CAST IRON	LOC	LOCATION								
CL	CENTER LINE	NIC	NOT IN CONTRACT								
CONT	CONTINUATION	PLBG	PLUMBING								
CONTR	CONTRACTOR	SP	SPRINKLER								
D	DRAIN	SP/FDV	STAND PIPE/ FIRE DEPT. VALVE								
DN	DOWN	TSW	TAMPER SWITCH								
DTL	DETAIL	W/	WITH								
DWGS	DRAWINGS										

NOTE: THESE ARE STANDARD ABBREVIATIONS, ALL ABBREVIATIONS SHOWN ABOVE MAY NOT APPEAR ON DRAWINGS.

#### FIRE PROTECTION LEGEND

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
<del></del>	RISER DOWN (ELBOW)		VALVE IN CAST IRON BOX W/ CONC. PAD
<b>——</b>	RISER UP (ELBOW)	P	FLOW SWITCH
0	RISE OR DROP		CONCENTRIC REDUCER
<del></del>	BRANCH - BOTTOM CONNECTION		ECCENTRIC REDUCER
ф	BRANCH - TOP CONNECTION		STRAINER
	BRANCH - SIDE CONNECTION	—— ——	UNION
₩	VALVE IN RISE		CAP ON END OF PIPE
M	ANGLE VALVE	<del>,</del> <del>,</del> <del>,</del> <del>,</del> <del>,</del>	PLUGGED TEE
$\triangleright$	SIDEWALL SPRINKLER		PRESSURE GAUGE WITH GAUGE COCK
<del></del>	CHECK VALVE	×	PIPE ANCHOR
$\longrightarrow \!$	SHUT-OFF VALVE	•	CONNECT TO EXISTING
<b>──</b>	GLOBE VALVE		FLOW INDICATOR FOR PORTABLE METER
<b>\</b>	PRESSURE REDUCING VALVE		FLOW - IN DIRECTION OF ARROW
₽	SOLENOID OPERATED VALVE	<b>-</b> ₩	BACKFLOW PREVENTER W/ STRAINER
0	UPRIGHT SPRINKLER	어."	SIAMESE FIRE CONNECTION
0	PENDENT SPRINKLER	O-IXHI	STANDPIPE W/FIRE DEPT. VALVE
•	CONCEALED SPRINKLER	M	METER

#### FIRE PROTECTION SYSTEM DESCRIPTION:

SCOPE: EXPAND THE EXISTING FIRE PROTECTION SYSTEM FOR THE NEW CONSTRUCTION SHOWN. REWORK PORTIONS OF EXISTING SYSTEM AS NEEDED TO ALLOW INSTALLATION OF NEW AREAS. CONTRACTOR SHALL VERIFY EXISTING SYSTEM ORIENTATION, EQUIPMENT & DEVICES NOT SHOWN ON FLOOR PLAN. COORDINATE LOCATIONS WITH ARCHITECT.

PROVIDE ALL LABOR AND MATERIAL, NECESSARY EQUIPMENT AND SERVICES TO MODIFY & EXPAND THE EXISTING AUTOMATIC WET-PIPE SPRINKLER SYSTEM TO PROVIDE COMPLETE COVERAGE OF WORK AREA MATCHING THE NEW SPACE

#### SYSTEM DESCRIPTION:

PROVIDE NEW QUICK RESPONSE SPRINKLER HEADS LOCATED AS INDICATED, MODIFY EXISTING SYSTEM AS NECESSARY. COORDINATE EXISTING SYSTEM TO REMAIN IN SERVICE WITH BUILDING MANAGEMENT.

#### **QUALITY ASSURANCE:**

DESIGN AND INSTALLATION TO CONFORM TO THE RULES & REGULATIONS OF THE SAFETY FIRE COMMISSIONER AND NFPA 13, 2002 EDITION. EQUIPMENT AND COMPONENTS TO BE UL LISTED AND FM APPROVED.

#### **REGULATORY REQUIREMENTS:**

PROVIDE HYDRAULIC CALCULATIONS, PRODUCT DATA, AND WORKING DRAWINGS: BEAR STAMP OF APPROVAL OF AUTHORITY HAVING JURISDICTION, FIRE MARSHAL, AND OWNER'S FIRE INSURANCE UNDERWRITER.

INDICATE HYDRAULIC CALCULATIONS, DETAILED PIPE LAYOUT, HANGER AND SUPPORTS, COMPONENTS AND ACCESSORIES.

SUBMIT SHOP DRAWINGS, PRODUCT DATA, AND HYDRAULIC CALCULATIONS TO AUTHORITY HAVING JURISDICTION, FIRE MARSHAL, AND OWNER'S INSURANCE UNDERWRITER FOR APPROVAL PRIOR TO SUBMISSION TO ARCHITECT.

PIPING 2-1/2" & SMALLER: STANDARD WEIGHT SCHEDULE 40 BLACK STEEL PIPE WITH THREADED FITTINGS. PIPING 3" & LARGER: SCHEDULE 10 BLACK STEEL WITH ROLLED GROOVE FITTINGS.

FITTINGS: CAST IRON FITTINGS, ANSI/ASME B16, FLANGES AND FITTINGS OR B16.4, SCREWED FITTINGS OR MECHANICAL COUPLINGS

SPRINKLER HEADS: AREAS WITH LAY-IN CEILINGS: SEMI-RECESSED PENDANT TYPE SPRINKLER HEADS: AREAS WITH HARD CEILINGS: FULLY-RECESSED, CONCEALED PENDANT TYPE SPRINKLER HEADS: UNFINISHED (NO CEILING) AREAS: BRASS UPRIGHT TYPE


EXECUTION:
COORDINATE WORK OF THIS SECTION WITH THE WORK OF ALL OTHER TRADES.

#### FIRE PROTECTION NOTES:

- 1. EXPAND THE EXISTING AUTOMATIC SPRINKLER SYSTEM IN ACCORDANCE WITH THE REQUIREMENTS OF THE SAFETY FIRE COMMISSIONER & NFPA 13 2002 EDITION FOR LIGHT HAZARD OCCUPANCY.
- 2. SYSTEM SHALL BE CAPABLE OF DELIVERING 0.10 GPM/SQFT. OVER THE MOST REMOTE 1500 SQ. FT.
- 3. PROVIDE A SPRINKLER HEAD FOR EVERY 225 SQ. FT OF FLOOR AREA WITH ADEQUATE FLOW TO MEET CRITERIA LISTED ABOVE.
- 4. INCLUDE ALL PIPE AND FITTINGS BACK TO THE CONNECTION OF THE CITY MAIN WHILE FLOWING THE ENTIRE CALCULATED FLOW PLUS 100 GPM FOR INSIDE & OUTSIDE HOUSE STREAMS WHEN PERFORMING PIPE SIZING CALCULATIONS.
- 5. ALL HEADS ARE TO BE QUICK RESPONSE TYPE.
- 6. PROVIDE PENDANT TYPE HEADS IN AREAS WITH CEILINGS. MOUNT SEMI-RECESSED HEADS IN THE CENTER OF THE CEILING TILES IN LAY-IN CEILINGS. PROVIDE FULLY RECESSED, CONCEALED HEADS IN HARD CEILINGS. SEE ARCHITECTURAL REFLECTED CEILING PLANS FOR CEILING DETAILS.

7. PROVIDE UPRIGHT TYPE HEADS IN AREAS WITH NO CEILINGS.

- 8. INSTALL PIPING SUCH THAT ENTIRE SYSTEM CAN BE DRAINED. SEE ARCHITECTURAL DRAWINGS FOR SLOPED CEILING AND STRUCTURE DETAILS.
- 9. SUPPORT PIPING FROM BUILDING STRUCTURAL ELEMENTS ONLY.
- 10. COORDINATE LOCATIONS OF PIPING WITH THE WORK OF OTHER TRADES AND WITH SPECIALTY ITEMS SHOWN ON THE ARCHITECTURAL DRAWINGS.
- 11. PERFORM HYDRANT FLOW TEST AS BASIS FOR SYSTEM DESIGN. PRELIMINARY TEST DATA RESULTS: HYDRANT AT VOLUNTEER WAY & McDONOUGH ROAD - STATIC PRESSURE OF 105 PSI AND RESIDUAL PRESSURE OF 55 PSI WHILE FLOWING 1240 GPM.



1 DETAIL - NEW SERVICE CONNECTION Scale: NONE



#### ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office:



1708 Peachtree St. Suite 210 Atlanta, GA 30309 404/355-9334 main 404/835-1118 fax



110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawing are protected by the copyright lows of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.
Dwint Doggod

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

2013-09-23 1207007000 Sheet Title

FIRE PROTECTION -GENERAL NOTES & DETAILS

Wakefield Beasley St associates

#### ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE



1708 Peachtree St. Suite 210 Atlanta, GA 30309 404/355-9334 main 404/835-1118 fax

### FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



# ©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review
09/23/2013: RELEASE FOR BID
12/02/13 FOR CONSTRUCTION

Revisions

Date

*Job No.* 3 1207007000

2013-09-23 12 Sheet Title

FIRE PROTECTION – FLOOR PLAN

Sheet No.

FP101

	ABBREVIATION/DEFINITION		ABBREVIATION/DEFINITION				
A/C	ABOVE CEILING	FF	FINISHED FLOOR				
AD	AREA DRAIN	G	LOW PRESSURE GAS				
AFF	ABOVE FINISHED FLOOR	GEN	GENERAL				
AFG	ABOVE FINISHED GRADE	нВ	HOSE BIBB				
AV	ACID VENT	HD	HUB DRAIN (OPEN PIPE HUB)				
AW	ACID WASTE	HCWH	HOT & COLD WATER HYDRANT				
B/F	BELOW FLOOR	HWR	HOT WATER RETURN				
B/G	BELOW GRADE	HW	HOT WATER				
BLDG	BUILDING	IW	INDIRECT WASTE				
СВ	CATCH BASIN	ΙE	INVERT ELEVATION				
CI	CAST IRON	LP	LIQUIFIED PETROLEUM GAS (PROPANE)				
CL	CENTER LINE	MPG	MEDIUM PRESSURE GAS				
СО	CLEANOUT	NIC	NOT IN CONTRACT				
CONT	CONTINUATION	OXY	MEDICAL OXYGEN				
CONTR	CONTRACTOR	PLBG	PLUMBING				
CW	COLD WATER	PRV	PRESSURE REDUCING VALVE				
D	DRAIN	PVC	POLYVINYL CHLORIDE				
DN	DOWN	RD	ROOF DRAIN				
DT	EMERGENCY ROOF DRAIN TERMINATION (COW'S TONGUE)	SAN	SANITARY				
DWGS	DRAWINGS	SD	STORM DRAIN				
DWR	CHILLED DRINKING WATER RETURN	SP	SPRINKLER				
DWS	CHILLED DRINKING WATER SUPPLY	STR	STRAINER				
ERD	EMERGENCY ROOF DRAIN (SECONDARY)	SV	SANITARY VENT				
EWC	ELEC. WATER COOLER	SW	SAFE WASTE				
FAV	FRESH AIR VENT	TP	TRAP PRIMER				
FC0	FLOOR CLEANOUT	VAC	MEDICAL VACUUM				
FLR	FLOOR	VTR	VENT THROUGH ROOF				
FD	FLOOR DRAIN	W	WASTE				
FFE	FINISHED FLOOR ELEVATION	W/	WITH				
GCO	GRADE CLEANOUT	WCO	WALL CLEANOUT				
SP/FDV	STAND PIPE / FIRE DEPT. VALVE	NFWH	NON-FREEZE WALL HYDRANT				

#### PLUMBING LEGEND

DESCRIPTION

SYMBOL

SYMBOL


DESCRIPTION

SIMBUL	DESCRIPTION	SIMBUL	DESCRIPTION
— —SS— —	SANITARY SEWER	<del></del>	TRAP
— —GW— —	GREASE WASTE	•	FLOOR CLEANOUT
SD	STORM DRAIN		VALVE IN CAST IRON BOX W/ CONC. PAD
	SANITARY VENT	•	FLOOR CLEANOUT
	BELOW GRADE PIPING	<b>D</b> C	FLOOR SINK W/ HALF GRATE
	ABOVE GRADE PIPING	<b>E</b> C	FLOOR DRAIN W/ FULL GRATE
	DOMESTIC COLD WATER SUPPLY	<b>©</b> c	FLOOR DRAIN
	DOMESTIC HOT WATER SUPPLY (110°F)	œ <u> </u>	HUB DRAIN OR OPEN SITE DRAIN
	DOMESTIC HOT WATER RETURN (110°F)	0+	HOSE BIBB
<del></del>	DOMESTIC HOT WATER SUPPLY (140°F)	<b>⊶</b> }∎	WALL HYDRANT (NFWH & HCWH)
<del></del>	DOMESTIC HOT WATER RETURN (140°F)	<u></u>	FLOW SWITCH
	DOMESTIC HOT WATER SUPPLY (180°F)	——  →	CONCENTRIC REDUCER
<del></del> G <del></del>	DOMESTIC HOT WATER RETURN (180°F)		ECCENTRIC REDUCER
	NATURAL OR LP GAS		STRAINER
	MEDICAL VACUUM	——  ———	UNION
<b>—</b>	MEDICAL OXYGEN	<del></del>	CAP ON END OF PIPE
Θ	RISER DOWN (ELBOW)	<del></del>	BREAK
O	RISER UP (ELBOW)	, <del>T</del> ,	PLUGGED TEE
0	RISE OR DROP		THERMOMETER
<del></del>	BRANCH - BOTTOM CONNECTION	<u> </u>	PRESSURE GAUGE WITH GAUGE COCK
ф	BRANCH - TOP CONNECTION		FLEXIBLE CONNECTION
	BRANCH - SIDE CONNECTION	×	PIPE ANCHOR
+€0	VALVE IN RISE	•	CONNECT TO EXISTING
<b>≱</b>	ANGLE VALVE		FLOW INDICATOR FOR PORTABLE METER
<b>→</b>	BALANCING VALVE		FLOW - IN DIRECTION OF ARROW
<u> </u>	STOP VALVE	<b>를</b>	THERMOSTATIC MIXING VALVE
	CHECK VALVE	+	BACKFLOW PREVENTER W/ STRAINER
<b>──</b> ₩──	SHUT-OFF VALVE	———	GAS SHUT-OFF VALVE
<b>──</b>	GLOBE VALVE	<del></del>	GAS REGULATOR
\\$	MOTOR OPERATED VALVE		FLUSH GRADE CLEANOUT W/CONC. PAD
	PRESSURE REDUCING VALVE	<b>©</b>	ROOF DRAIN
\	SOLENOID OPERATED VALVE	~【	SIAMESE FIRE CONNECTION
0	UPRIGHT SPRINKLER	O-D>CHI	STANDPIPE W/FIRE DEPT. VALVE
0	PENDENT SPRINKLER	M	METER
•	CONCEALED SPRINKLER	R <b>K</b>	TEMPERATURE & PRESSURE RELIEF VALVE
EQ #	EQUIPMENT DESIGNATION	RISER #	PLUMBING RISER DESIGNATION
	EXISTING PIPING TO REMAIN	+1+1+++,	REMOVE EXISTING PIPING

#### NOTE: THIS IS A STANDARD LEGEND. ALL ITEMS SHOWN MAY NOT APPEAR ON DRAWINGS.

### PLUMBING GENERAL NOTES:

- 1. COORDINATE WORK WITH ARCHITECTURAL, STRUCTURAL, MECHANICAL, AND ELECTRICAL TRADES. PIPE ROUTING SHOWN IS DIAGRAMMATIC, PROVIDE OFFSETS, ETC., TO AVOID INTERFERENCES WITH EQUIPMENT, PIPING, DUCTWORK, LIGHTS, CONDUIT, ETC..
- 2. COORDINATE FLOOR PENETRATIONS WITH STRUCTURAL DRAWINGS. SET SLEEVES IN FLOORS AND WALLS AND ATTACHMENTS FOR HANGERS AS CONSTRUCTION PROGRESSES. PENETRATIONS MUST BE SEALED AND HELD AS TIGHT TO COLUMNS OR WALLS AS POSSIBLE.
- 3. RUN VENT PIPING CONCEALED ABOVE CEILINGS OR IN WALL SPACES UNLESS NOTED OTHERWISE ON DRAWINGS.
- 4. PIPING SHALL BE SLOPED AS PER SPECIFICATIONS UNLESS NOTED OTHERWISE ON DRAWINGS.
- 5. CONTRACTOR SHALL EXTEND WATER, AND SANITARY SEWER PIPING TO EXISTING UTILITIES INSIDE BUILDING. REFER TO EXISTING CONDITIONS FOR CONTINUATION & LOCATION OF UTILITIES.
- 6. COORDINATE UNDERGROUND PIPING WITH GRADE BEAMS AND WALL FOOTINGS.
- 7. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF PLUMBING FIXTURES. EXACT LOCATION OF FIXTURES MUST BE VERIFIED IN THE FIELD PRIOR TO INSTALLATION. FINAL LOCATION SHALL BE AS DIRECTED BY ARCHITECT.
- 8. DO NOT RUN PLUMBING PIPING THROUGH ELECTRICAL ROOMS OR DIRECTLY ABOVE ELECTRICAL PANELS.
- 9. PLUMBING VENTS EXTENDING THROUGH ROOF SHALL TERMINATE AT 1'-0" ABOVE ROOF AND AT A MINIMUM DISTANCE OF 12'-0" HORIZONTALLY FROM ANY AIR INTAKE OR OPERABLE WINDOW.
- 10. WORK SHALL COMPLY WITH THE GEORGIA STATE ACCESSIBILITY REQUIREMENTS.



	PLUMBING FIXTURE CONNECTION SCHEDULE												
ITEM	FIXTURE	CW	HW	WATER	WASTE	MOUNTING	ВА	SIS OF DESIGN					
				USAGE		HEIGHT	TRIM / FAUCET	FIXTURE					
P-1	WATER CLOSET - FM, TANK, H/C	1/2"	-	1.28 GPF	3"	RIM AT 16.5"	_	AMERICAN STANDARD: 2467.100					
P-2	LAVATORIES - WH, H/C	1/2"	1/2"	0.5 GPM	1-1/4"	RIM AT 34"	DELTA: 500	AMERICAN STANDARD: 0356.015					
P-3	SINK - DOUBLE COMP., H/C	1/2"	1/2"	0.5 GPM	1-1/2"	SEE ARCH.	DELTA: 27T2123	JUST: DL-ADA-2233					
P-4	SHOWER-H/C	1/2"	1/2"		2"	RIM AT 8"	DELTA: 11T5123	AQUA BATH: 3634					
P-5	ICE MAKER UTILITY BOX	1/2"	-	N/A	-	SEE ARCH.		GUY GRAY: BIM875					

1. WATER CLOSETS: CONTROLS FOR FLUSH VALVES (TANK OR FV) SHALL BE MOUNTED ON THE WIDE SIDE OF TOILET AREAS NO MORE THAN 44 INCHES ABOVE THE FLOOR.


**BASIS OF** 

DESIGN


ACCESSORIES:

RHEEM

EGSP30







#### ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE





110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley. Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION Revisions

2013-09-23

1207007000


PLUMBING - GENERAL

NOTES & SCHEDULES

P001

COORDINATE VALVE HEIGHT WITH GRAB BAR HEIGHT.

<sup>2.</sup> PROVIDE HOT WATER SUPPLY AND WASTE PIPING TO THE DISHWASHER FROM P-3.



3 PLUMBING - WASTE RISER DIAGRAM Scale: NOT TO SCALE



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

Consulting,LLC

1708 Peachtree St.
Suite 210
Atlanta, GA 30309
404/355-9334 main
404/835-1118 fax

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wokefield Beasley & Associates Architects, Inc. These drawing are protected by the copyright lows of the United States. These drawings or any part thereof may not be used for any purpose or reportured in one formers by one many sithout the written constraints.

Print Record

07/26/2013: 80% CD Set for Review
09/23/2013: RELEASE FOR BID
12/02/13 FOR CONSTRUCTION

Revisions

12/02/13 SANITARY EXIT REVISION

*Date* 2013-09-23

1207007000

Sheet Title
PLUMBING —

FLOOR PLANS DEMO & WASTE

eet No.

P101

1 PLUMBING - WATER & GAS PLAN
Scale: 1/8" = 1'-0"



ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

Covalent
Consulting, LLC

1708 Peachtree St.
Suite 210
Atlanta, GA 30309
404/355-9334 main
404/835-1118 fax

FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beosley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beosley.

of Wokefield Beosley.

Print Record

07/26/2013: 80% CD Set for Review
09/23/2013: RELEASE FOR BID
12/02/13 FOR CONSTRUCTION

Revisions

*Date* 2013-09-23

*Job No.* 1207007000

*Sheet Title* PLUMBING –

WATER & GAS PLAN

Sheet No.


P102

HOMERUN TO PANEL INDICATED. ARROWS INDICATE NUMBER OF CIRCUITS. TICK MARKS INDICATE NUMBER OF L1C-2,4,6 #12 AWG CONDUCTORS. NO TICK MARKS INDICATES 2#12,#12(G)-1/2°C. GROUND CONDUCTORS NOT SHOWN, BUT ARE REQUIRED IN ALL BRANCH CIRCUITS. TEXT INDICATES PANEL ID AND NUMBER OF CIRCUIT IN PANEL.

1" EC RUN CONCEALED BELOW FLOOR, IN WALL OR ABOVE CEILING TO TELECOM BACKBOARD IN ROOM 103.

————— CONDUIT RUN EXPOSED ON WALL OR CEILING

CONDUIT RUN CONCEALED IN WALL OR ABOVE CEILING



CONDUIT RUN UNDERGROUND OR CONCEALED BELOW FLOOR DUPLEX RECEPTACLE, SPECIFICATION GRADE, 20A, 120V, 18" AFF. "2" INDICATES CIRCUIT NUMBER. IVORY. "C" INDICATES MOUNT ABOVE COUNTER, "GF" IS GFCI.

FLUSH MOUNTED, QUADRUPLEX RECEPTACLE, 120V, 20A, NEMA 5-20R.

JUNCTION BOX

SUB-SYSTEM GROUND BUS. REFER TO DETAILS 4/E-701 AND 5/E-701.

> FLUSH MOUNTED 6-GANG BOX FLOOR MOUNTED (WIREMOLD EVOLUTION SERIES OR APPROVED EQUAL) WITH FOUR DUPLEX RECEPTACLES AND TWO DATA OUTLETS. FURNISH WITH HARDWARE COMPATIBLE WITH FLUSH MOUNTING IN RAISED FLOOR OR IN CONCRETE SLAB AS LOCATION REQUIRES. RECEPTACLES SHALL BE CONNECTED TO UPS CIRCUIT(S). PROVIDE 1" EC FOR DATA FROM 6-GANG BOX TO BACKBOARD IN ROOM 103.

COMBINATION MAGNETIC STARTER WITH DISCONNECT SWITCH. FUSED IF INDICATED. OVERLOADS SIZED PER MOTOR NAMEPLATE DATA. 30/3/3R PROVIDE WITH "HAND-OFF-AUTOMATIC" SELECTOR SWITCH MOUNTED ON DOOR. NEMA STARTER SIZE AS INDICATED (1).

NON-FUSED DISCONNECT SWITCH (RATING/POLES/ENCLOSURE AS INDICATED) 30/3/3R

000000000 TELECOMMUNICATIONS BACKBOARD

PB PULL BOX

CEILING MOUNTED OCCUPANCY SENSOR. LEVITON OSC20-MOW,

CEILING MTD, VACANCY TYPE.

LEVITON POWER PACK OSP20-DO FOR OCCUPANCY SENSORS.

6" X 8' FLUORESCENT FIXTURE

6" X 4' FLUORESCENT FIXTURE

2' X 4' FLUORESCENT FIXTURE

DOWN LIGHT

HID WALL PACK

• POLE MOUNTED LIGHT STANDARD WITH SINGLE HEAD

POLE MOUNTED LIGHT STANDARD WITH TWIN HEAD

EXIT SIGN.

SINGLE POLE LIGHT SWITCH, FLUSH MOUNTED 48" AFF, 120/277V, 20AMP; UNO. ON STRIKER SIDE OF DOOR OR WHERE OTHERWISE INDICATED ON PLANS. \* IF SUBSCRIPT APPLIES, SEE BELOW:

"3"- SAME AS ABOVE SINGLE POLE LIGHT SWITCH BUT THREE WAY. "M"- MANUAL MOTOR STARTER SWITCH. FLUSH MOUNTED OR SURFACE MOUNTED IN "FS" BOX DEPENDING UPON LOCATION (PROVIDE WITH OVERLOADS).

"D" - 120/277V, 20A, 0-10V SLIDE DIMMER (LEVITON IP710-DLZ OR APPROVED EQUAL)

"a" - LOWER CASE LETTER INDICATES SWITCHLEG ARRANGEMENT OR ZONE TO BE CONTROLLED BY LIGHTING CONTROL EQUIPMENT. "OC"- INDICATES OCCUPANCY SENSOR TYPE. LEVITON OSSMT-MD

CEILING MOUNTED FIRE ALARM SMOKE DETECTOR

FIRE ALARM SMOKE DETECTOR MOUNTED BELOW RAISED FLOOR

FIRE ALARM VISIBLE SIGNAL DEVICE (75cd, UNO). WALL MOUNTED — 80"AFF OR 6" BELOW CEILING, WHICHEVER IS LOWER.

FIRE ALARM MANUAL PULL STATION.

FIRE ALARM AUDIBLE SPEAKER AND VISIBLE SIGNAL DEVICE (75cd, UNO). WALL MOUNTED - 80"AFF OR 6" BELOW CEILING, WHICHEVER IS LOWER.

FIRE ALARM FLOW SWITCH

FIRE ALARM TAMPER SWITCH

	ı		LIGHTING FIX	(   U   <del> </del>	KE SCH	EDULE T	T	
	FIXTURE		LAMPS				MANUFACTURERS	
TYPE	DESCRIPTION	NO.	WATTS/LAMP/CRI/ COLOR TEMP.	VA	MTG.	VOLTAGE	& CATALOG NOS.	REMARKS
A2	2' X 4' ACRYLIC LENS FLUORESCENT TROFFER	2	F32W/T8/82/ 3500K	60	RECESSED	120	DAY BRITE 2 DP G 2 32 FS 12 120  METALUX 2GC-232A125-UNV-HB81-U	
A3	2' X 4' ACRYLIC LENS FLUORESCENT TROFFER	3	F32W/T8/82/ 3500K	89	RECESSED	120	DAY BRITE 2 DP G 3 32 FS 12 120  METALUX 2GC-232A125-UNV-EB81-U	
A3F	2' X 4' ACRYLIC LENS FLUORESCENT TROFFER	3	F32W/T8/82/ 3500K	89	RECESSED	120	DAY BRITE 2 DP F 3 32 FS 12 120  METALUX 2GC-232A125-UNV-EB81-U/DF- < 24-W	PROVIDE FLANGE KIT FOR MOUNTING IN GYPSUM BOARD CEILING
В	VAPORTIGHT PENDANT MOUNTED	1	42W/CFL/3500K	50	PENDANT	120	TEDDICO VPKG-F42 LUMARK PLVS-C-GG-42-120	MOUNT 11'-0" AFF
С	CFL RECESSED SHOWER LIGHT	1	32W/CFL/3500K	40	SURFACE	120	OMEGA OM61H32PLTSRD120/277  - R61H32PLTSRDSHWR PORTFOLIO CD6S142E-6CLS1421LI1	
D	LINEAR PENDANT	6	F32W/T8/82/ 3500K	178	CABLE	120	FINELITE S12-P-8-3T8-SC-EP- 120-AC-FE-C3-0.88 CORELITE IP-WP-3T8-1D-120-AC48-TS-8-E	MOUNT 10'-0" AFF PROVIDE 3 LAM DIMMABLE BALLAST COMPATIBLE WITH DIMMER SWITCH
F	STRIP FIXTURE WITH SYMETRICAL REFLECTOR	2	F32W/T8/82/ 3500K	60	PENDANT	120	DAY BRITE T232-120-TSR4  METALUX SSF-232-UNV-EB81-U-SSF-AYC- CHAIN/SET-SYM-4	MOUNT 10'-0" AFF
G	8" CFL WALL WASH DOWNLIGHT	1	32W/CFL/3500K	40	SURFACE	120	OMEGA S81H32PLTDX1U-T81HPLTWWCS HALO PD8H142-1DMARKXREM-82HWWC	) DIMMING TYPE
Н	METAL HALIDE WALL PACK	1	70W MH	90	SURFACE	120	DAY BRITE WLI 070 M 120 LUMARK LP70G-120/277-BZ	MOUNT 10'-0" AGL
K	METAL HALIDE WALL PACK	1	100W MH	130	SURFACE	120	DAY BRITE WLI 100 M 120 LUMARK LP10G-120/277-BZ	MOUNT 12'-2" AFF
М	FLUORESCENT STRIP FIXTURE	1	F32W/T8/82/ 3500K	30	SURFACE	120	DAY BRITE T132-120  METALUX SSF-132-UNV-EB81-U	
XA	WALL MOUNTED, SINGLE FACE, THERMOPLASTIC L.E.D. EXIT SIGN WITH WHITE FACE AND RED LETTERS	L.E.D.s W/FIXT	L.E.D.s	5	SURFACE	120	LITHONIA LQM S W 3 R 120/277 SURE-LITES APX6R	CONNECT TO UNSWITCHED CIRCUIT.
XB	CEILING MOUNTED, SINGLE FACE, THERMOPLASTIC L.E.D. EXIT SIGN WITH WHITE FACE AND RED LETTERS	L.E.D.s W/FIXT	L.E.D.s	5	SURFACE	120	LITHONIA LQM S W 3 R 120/277 SURE-LITES APX6R	CONNECT TO UNSWITCHED CIRCUIT.
XC	CEILING MOUNTED, DOUBLE FACE, THERMOPLASTIC L.E.D. EXIT SIGN WITH WHITE FACE AND RED LETTERS	L.E.D.s W/FIXT	L.E.D.s	5	SURFACE	120	LITHONIA LQM S W 3 R 120/277  SURE-LITES APX6R	PROVIDE DIRECTION CHEVRONS AS INDICATED ON SHEET E-401. CONNECT TO UNSWITCHED CIRCUIT.

LICHTIMO FIVTUDE COHEDINE

#### ELECTRICAL SYMBOL LEGEND

CARD READER / ACCESS CONTROL.

TELECOMMUNICATIONS OUTLET, MOUNT 18"AFF, UNO. SEE GENERAL NOTE G18.

AUDIO/VISUAL OUTLET, MOUNT 18"AFF, UNO. SEE GENERAL NOTE G18.

BLUNT TIP AIR TERMINAL(ALUMINUM): AIR TERMINAL AND ALL ASSOCIATED COMPONENTS IN THE LIGHTNING PROTECTION SYSTEM SHALL BE CLASS I MATERIALS.

GROUND ROD

GROUND ROD - EXISTING

ELECTRICAL CONNECTION CONDUCTOR TO CONDUCTOR OR CONDUCTOR TO METAL OBJECT.

ELECTRICAL CONNECTION OF MAIN ALUMINUM CONDUCTOR TO COPPER DOWN CONDUCTOR WITH BIMETAL BONDING CLAMP AND PENETRATION OR PATH TO THE NEXT LOWER LEVEL.

MAIN CONDUCTOR (ALUMINUM)



MAIN CONDUCTOR - EXISTING



SECONDARY CONDUCTOR (ALUMINUM)



NEW GROUND LOOP CONDUCTOR



EXISTING DEVICE AND EQUIPMENT TO REMOVED. REFER TO GENERAL DEMOLITION NOTES.

### GENERAL NOTES:

G1. ALL ELECTRICAL EQUIPMENT AND FEEDERS SHALL BE INSTALLED IN ACCORDANCE WITH APPLICABLE LOCAL AND STATE CODES WITH THE 2011 EDITION OF NFPA 70 NATIONAL ELECTRICAL CODE WITH GA AMENDMENTS AND THE 2009 EDITION OF THE INTERNATIONAL ENERGY CONSERVATION CODE WITH GEORGIA AMENDMENTS.

G2. PROVIDE ADDITIONAL SUPPORT FOR SWITCHES, STARTERS, FIXTURES, RACEWAYS AND OTHER ELECTRICAL EQUIPMENT WHERE EVER THE BUILDING STRUCTURE IS NOT SUITABLE FOR DIRECT MOUNTING.

G3. FIRE STOP, DRAFT STOP AND/OR PROTECT THE ANNULAR SPACE AROUND ALL PIPE, TUBE, CONDUIT, WIRE, CABLE, VENT AND DUCT PENETRATION THROUGH WALLS, PARTITIONS, FLOORS, CEILINGS AND ROOFS IN ACCORDANCE WITH THE REQUIREMENTS OF THE NATIONAL ELECTRICAL CODE AND UL LISTING REQUIREMENTS.

G4. VERIFY CEILING SUSPENSION SYSTEMS IN THE VARIOUS AREAS AND PROVIDE THE PROPER MOUNTING ACCESSORIES, TRIMS, ETC., TO SUIT THE PARTICULAR AREA.

G5. SYMBOLS IN THE LEGENDS ARE APPLICABLE GENERALLY, FOR EXACT REQUIREMENTS REFER TO THE SCHEDULES, LAYOUTS, DETAILS AND TO THE SPECIFICATIONS SINCE THE APPEARANCE OF A PARTICULAR SYMBOL IN THE LEGEND DOES NOT NECESSARILY IMPLY THAT THE ITEM IS INCLUDED IN THE CONTRACT.

G6. PROVIDE INDEPENDENT NEUTRALS FOR ALL RECEPTACLE CIRCUITS.

G7. PHASE IDENTIFICATION FOR INCOMING FEEDERS TO PANELBOARDS AND TRANSFORMERS SHALL BE ACCOMPLISHED BY COLOR CODE TAPING AS FOLLOWS: FEEDERS RATED (208V)...PHASE "A" = BLACK; PHASE "B" = RED; PHASE "C" = BLUE; NEUTRAL = WHITE

G8. ALL POWER CIRCUITS SHALL CONTAIN AN EQUIPMENT GROUNDING CONDUCTOR (GREEN COLOR INSULATION) ROUTED IN CONDUIT AND SIZED AS INDICATED ON DRAWINGS (MINIMUM SIZE - #12AWG).

G9. EXCEPT WHERE NOTED OTHERWISE, LIMIT LIGHTING AND RECEPTACLE BRANCH CIRCUIT HOMERUNS TO 7 CONDUCTORS. 3 PHASE WIRES, 3 NEUTRALS, AND 1 GROUND.

G10. DO NOT INSTALL MATERIALS OTHER THAN SPECIFIED EXCEPT FOR ALTERNATES ACCEPTED BY OWNER.

G11. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE AMERICANS WITH DISABILITIES ACT (ADA).

G12. ROUTE CONDUITS CONCEALED IN FINISHED SPACES.

G13. PROVIDE EXPANSION JOINT FITTINGS FOR ALL RACEWAYS CROSSING EXPANSION JOINTS.

G14. THE USE OF TYPE AC CABLES IS NOT PERMITTED. THE USE OF TYPE MC CABLES IS PERMISSIBLE WHERE CIRCUITS ARE EXTENDED INTO EXISTING WALLS IN A CONCEALED FASHION.

G15. PROVIDE LABELS ON ALL DEVICES IDENTIFYING RESPECTIVE BRANCH CIRCUIT NUMBER AND PANELBOARD, SIMILAR TO BROTHER P-TOUCH.

G16. IN ALL EMPTY CONDUITS, PROVIDE PULL STRING.

G17. CONNECT FIRE ALARM DEVICES TO EXISTING FIRE ALARM BASE BUILDING RISER AS DIRECTED BY MANUFACTURER (EST). CONTRACTOR TO PROVIDE CERTIFIED LETTER FROM MANUFACTURER THAT WORK HAS BEEN PERFORMED IN ACCORDANCE WITH NFPA 72, 101 AND BUILDING STANDARDS. SYNCHRONIZE ALL STROBES.

G18. FOR TELECOMMUNICATIONS OUTLETS, EXTEND 1" EMPTY CONDUIT TO ABOVE ACCESSIBLE CEILING. FOR A/V OUTLETS, EXTEND 3/4" EC TO ABOVE ACCESSIBLE CEILING. USE OF THE WALL CAVITY AS A PHYSICAL PATHWAY IS ACCEPTABLE IF FREE OF INSULATION AND/OR OBSTRUCTIONS. PROVIDE PULL STRING REGARDLESS.

ABBREVIATIONS:

AFF ABOVE FINISHED FLOOR AGL ABOVE GRADE LEVEL

KILOWATTS

A/V AUDIO/VISUAL CONDUIT

ΚW

EMPTY CONDUIT FURNISHED WITH EQUIPMENT PROJECTOR PULL BOX EXISTING TO REMAIN

SHUNT TRIP UNLESS NOTED OTHERWISE UNO WP WEATHERPROOF

WAKEFIELD BEASLEY & ASSOCIATES

#### ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office:



404/355-9334 main 404/835-1118 fax





110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These draw are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written co
of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

### Revisions


1 12/02/13 ADDENDUMS AND CLARIFICATIONS

Job No. 2013-09-23 1207007000

Sheet Title

ELECTRICAL LEGEND. GENERAL NOTES AND **ABBREVIATIONS** 

Sheet No.



KEY NOTES

(APPLY TO THIS SHEET ONLY)

- 1) EXISTING UNDERGROUND COMMUNICATIONS RACEWAYS TO BE DISRUPTED BY CONSTRUCTION.
- $\langle 2 \rangle$  EXISTING UNDERGROUND ELECTRICAL BRANCH CIRCUITS TO BE DISRUPTED BY CONSTRUCTION (SITE LIGHTING AND GATE MOTOR/CONTROLS).
- PROVIDE NEW COMMUNICATIONS UNDERGROUND RACEWAYS (3 @ 4" EC PLUS 3 @ 2-1/2" EC) AND ROUTE OUTSIDE OF NEW BUILDING FOOTPRINT. PROVIDE EMPTY RACEWAY WITH PULL STRING. COORDINATE WITH OWNER AND UTILITY COMPANY.
- REMOVE EXISTING SITE LIGHTING STANDARD. EXTEND BRANCH CIRCUITS TO BACKFEED EXISTING GATE MOTOR AND CONTROLS AND CONNECT FOR NORMAL OPERATION ON CIRCUIT ELB-7. PRESNTLY SUPPORTED BY UPS PANEL LB.
- (5) COORDINATE WITH EXISTING UNDERGROUND UTILITIES. VERIFY UNDERGROUND UTILITIES PRIOR TO ANY TRENCHING. REPAIR ALL DAMAGE AT NO COST TO OWNER.
- $\stackrel{\textstyle lack}{\scriptstyle eta}$  extend 1-1/2" empty conduit with pull string to grassed area for security cameras.



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE









110 Volunteer Way Fayetteville, Georgia 30215



## ©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions


2013-09-23

1207007000

Sheet Title ELECTRICAL -

SITE PLAN

E-101



# 1 FLOOR PLAN - ELECTICAL DEMOLITION + NEW GROUND LOOP © 2) (E-201) SCALE: 1/8"=1'-0"

#### GENERAL DEMOLITION NOTES:

- D1. PRIOR TO DEMOLITION, CONTRACTOR SHALL PROPERLY DISCONNECT ALL ELECTRICAL EQUIPMENT FROM ITS RESPECTIVE POWER SOURCE. AT NO TIME SHALL ELECTRICAL EQUIPMENT REMAIN ENERGIZED IN AN UNPROTECTED FASHION. COORDINATE ALL POWER INTERRUPTIONS WITH OWNER AND RECEIVE OWNER PERMISSION PRIOR TO ANY INTERRUPTION.
- D2. THIS IS A RENOVATION WITHIN AN EXISTING BUILDING. WHEN WORK IS FINISHED, THE ELECTRICAL INSTALLATION SHALL BE COMPLETELY INTEGRATED WITH EXISTING ELECTRICAL SYSTEMS. EXISTING ELECTRICAL WORK REQUIRED TO REMAIN IN USE DURING AND AFTER THE COMPLETION OF THE WORK SHALL BE EXTENDED, REPLACED, RECONNECTED OR OTHERWISE TO FIT INTO THE BUILD—OUT AREA AND LEFT IN SAFE WORKING ORDER.
- D3. IF THE CONTINUITY OF FIRE ALARM, LIGHTING, POWER OR DATA/COMMUNICATION CIRCUITS OR EQUIPMENT OR AREAS OUTSIDE THE SCOPE OF THE DEMOLITION WORK IS INTERRUPTED BY THIS WORK, THE CONTRACTOR SHALL INSTALL REQUIRED WIRING TO INSURE THE CONTINUITY OF CIRCUITS TO EXISTING AREAS OUTSIDE THE DEMOLITION AREAS.
- D4. CONTRACTOR SHALL VERIFY ALL CONDITIONS IN THE FIELD PRIOR TO SUBMISSION OF BID.
- D5. EXISTING ELECTRICAL ITEMS THAT ARE BEING REMOVED AND NOT REUSED IN THIS NEW CONSTRUCTION SHALL BE RETURNED TO THE OWNER OR DISPOSED OF AS DIRECTED. REMOVAL AND DISPOSAL OF THE EXISTING ITEMS IS THE RESPONSIBILITY OF THE CONTRACTOR.

D6. CONTRACTOR IS RESPONSIBLE FOR CORING, CUTTING, PATCHING, REPAIRING, REMOVAL, REPLACEMENT, DISCONNECTING, RELOCATING, RECONNECTING OR REFINISHING OF EXISTING CONSTRUCTION, MATERIAL OR EQUIPMENT AS REQUIRED TO ACCOMMODATE INSTALLATION OF NEW WORK OR REMOVAL OF ANY EXISTING ITEMS. PATCHING, REPAIRING, REPLACEMENT AND REFINISHING SHALL MATCH EXISTING CONSTRUCTION.

D7. PROVIDE NEW TYPED UPDATED PANELBOARD SCHEDULE TO REPLACE EXISTING PANELBOARD SCHEDULE WHENEVER ANY CIRCUIT BECOMES SPARE AS A RESULT OF DEMOLITION OR ANY CHANGE OCCURS AS A RESULT OF ANY NEW CONSTRUCTION.

D8. REMOVE CONDUCTORS THAT ARE NO LONGER CONNECTED TO ACTIVE CIRCUITS IN THEIR ENTIRETY FROM POINT OF ORIGINATION TO POINT OF TERMINATION.

D9. RENOVATION WORK AS SHOWN ON DRAWINGS AND INCLUDED IN THESE NOTES INDICATE ITEMS IN A GENERAL MANNER. TYPICAL ITEMS INVOLVED IN THE RENOVATION ARE SHOWN BUT THE DRAWINGS ARE NOT INTENDED TO BE ALL INCLUSIVE. CONTRACTOR SHALL VERIFY ALL CONDITIONS IN THE FIELD PRIOR TO SUBMISSION OF BID.

KEY NOTES

(APPLY TO THIS SHEET ONLY)

- 1 REMOVE PORTION OF EXISTING GROUND LOOP TO ACCOMMODATE CONSTRUCTION OF BUILDING ADDITION.
- (2) MAKE EXOTHERMIC TYPE CONNECTION TO EXISTING GROUND LOOP.
- 3 PROVIDE #2/0 AWG STRANDED TINNED COPPER GROUND LOOP BURIED 18" BELOW GRADE. INSTALL GROUND LOOP A MINIMUM OF 2'-0" AWAY FROM FOUNDATION.
- PROVIDE #2 AWG, 3/4" CONDUIT FROM SSGB TO EXISTING GROUND BAR IN EXISTING MAIN ELECTRICAL ROOM AND FROM SSGB TO NEW EXTERIOR GROUND LOOP AND EXOTHERMICALLY WELD CONNECTIONS.

  GROUND RISER FROM SSGB SHALL EXIT BUILDING 6" ABOVE GRADE AND PVC SLEEVE SHALL EXTEND INTO THE GROUND. REFER TO DETAILS 4/E-701, 5/E-701 AND 7/E-701.
- FROVIDE SSGB MOUNTED UNDER RAISED FLOOR ON PEDESTAL AT 5" ABOVE SLAB. PROVIDE #2 AWG, STRANDED TINNED COPPER CONDUCTOR, 3/4" CONDUIT FROM SSGB EXISTING GROUND BAR IN EXISTING ELECTRICAL ROOM AND FROM SSGB TO NEW EXTERIOR GROUND LOOP AND EXOTHERMICALLY WELD CONNECTIONS. GROUND RISER FROM SSGB SHALL EXIT BUILDING 6" ABOVE GRADE AND PVC SLEEVE SHALL EXTEND INTO THE GROUND. REFER TO DETAILS 4/E-701, 5/E-701 AND 7/E-701.
- 6 PROVIDE #2 AWG STRANDED COPPER FOR INTERIOR GROUND RING MOUNTED TO WALL AT 5" ABOVE SLAB UNDER RAISED FLOOR ON 2" STAND OFFS ON 2'-0" CENTERS MAXIMUM. REFER TO DETAIL 2/E-701.
- PROVIDE #2 AWG STRANDED COPPER FOR INTERIOR GROUND RING MOUNTED AT 5" ABOVE SLAB UNDER RAISED FLOOR ON PEDESTALS. ROUTE BELOW CONSOLE EQUIPMENT AS SHOWN. REFER TO DETAIL 3/E-701.
- ullet bond door and door frame to interior ground ring using #2 awg green insulated stranded copper wire and two hole connector. Use parallel type crimp type connector at ground ring. Refer to detail 9/e-701.
- 9 GROUND RING SPLICE. REFER TO DETAIL 9/E-701.
- 800 BOND METAL TRAY UNDER RAISED FLOOR TO INTERIOR GROUND RING USING TWO HOLE CONNECTOR AND #2 AWG STRANDED COPPER WIRE. USE PARALLEL CRIMP CONNECTOR AT GROUND RING. BOND AT ENDS WHERE THEY MEET THE WALL. PROVIDE #6 SOLID COPPER WIRE ACROSS ALL SEPARATE SECTIONS OF CABLE TRAY.
- 11) BOND ALL SIGNIFICANT METAL OBJECTS TO WITHIN 6' TO INTERIOR GROUND RING.
- PROVIDE #2 AWG STRANDED, TINNED, COPPER GROUND RISER CONDUCTOR FROM INTERIOR GROUND RING TO BURIED GROUND RING. PROVIDE CRIMP TYPE CONNECTOR AT INTERIOR GROUND. PROVIDE 3/4" SLEEVE THROUGH WALL AT A 45" ANGLE. ROUTE CONDUCTOR DOWN TO BURIED GROUND RING AND EXOTHERMICALLY WELD CONNECTION. PVC SHALL EXIT BUILDING 6" ABOVE GRADE AND EXTEND INTO THE GROUND.
- PROVIDE #6 AWG STRANDED COPPER PIGTAIL 10'-0" LONG FOR CONNECTION TO CONSOLE BAY. FINAL CONNECTION TO BAYS BY CONSOLE SUPPLIER/VENDOR.
- BOND RAISED FLOOR PEDESTAL TO INTERIOR GROUND RING USING U-BOLT GROUND CLAMP. REFER TO DETAIL 3/E-701.
- (15) NOT USED.
- (16) BOND METAL WALL STUDS TO INTERIOR GROUND RING EVERY 25'-0" MINIMUM.
- (17) EXTEND #6 AWG INSULATED COPPER GROUNDING CONDUCTOR IN CONDUIT (ROUTE CONCEALED) AND CONNECT TO METALLIC PORTION OF SUSPENDED CEILING GRID.
- (18) EXTEND #6 AWG INSULATED COPPER GROUNDING CONDUCTOR IN CONDUIT (ROUTE CONCEALED) AND CONNECT TO HVAC DUCTWORK ABOVE SUSPENDED CEILING.
- (19) EXTEND #6 AWG INSULATED COPPER GROUNDING CONDUCTOR AND CONNECT TO METALLIC HOUSING OF FLOOR BOX CONTAINING POWER RECEPTACLES AND COMMUNICATIONS CABLING FOR OPERATOR POSITIONS. TYP. OF 8. REFER TO SHEET E-301 FOR FLOOR BOX LOCATIONS.
- GENERAL: UTILIZE PVC CONDUIT FOR ROUTING OF GROUNDING CONDUCTORS IN AREAS NOT USED FOR ENVIRONMENTAL AIR. WHEN METALLIC CONDUIT IS USED, PROVIDE BOND BUSHINGS.
- GENERAL: FOR GROUNDING OF EQUIPMENT MOUNTED WITHIN OPERATOR FURNITURE, UTILIZE A #6 AWG INSULATED COPPER GROUNDING CONDUCTOR AND ATTACH TO MOUNTING RAIL OR BRACKET.



ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX

Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE







110 Volunteer Way Fayetteville, Georgia 30215



## ©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID

12/02/13 FOR CONSTRUCTION

Revisions

*Job No.*−09−23 1207007000

2013-09-23


Sheet Title

FLOOR PLAN — ELECTRICAL

DEMOLITION & NEW GROUND LOOP

Sheet No.

E-201



1 FLOOR PLAN - POWER AND SIGNAL E-301 SCALE: 1/8"=1'-0"

KEY NOTES

(APPLY TO THIS SHEET ONLY)

- 1 PROVIDE CONDUIT AND CONDUCTORS AS NECESSARY FOR CONTROL OF MOTORIZED PROJECTION SCREEN.
- (2) CONNECT 120V POWER FOR MOTORIZED PROJECTION SCREEN. HOMERUN TO PANEL ELA CIRCUIT 3.
- 3 SWITCHES FOR MOTORIZED PROJECTION SCREEN ARE FURNISHED BY A/V VENDOR INSTALLED BY CONTRACTOR.
- PROVIDE CONDUIT AND CONDUCTORS AS REQUIRED TO CONNECT POWER TO MS-1 FROM CU-1 ON ROOF. POWER DISTRIBUTION ORIGINATES AT CU-1 AND EXTENDS TO THE INDOOR UNIT MS-1. INTERCONNECTING WIRING IS REQUIRED. REFER TO ROOF PLAN ON SHEET E-302.
- 5 COMBINATION MAGNETIC STARTER/DISCONNECT FOR EF-1 ON ROOF. REFER TO SHEET E-302.
- 6 PROPERLY SEAL CONDUITS EXITING COMM ROOM TO PREVENT GAS ESCAPE DURING FIRE PROTECTION SYSTEM DISCHARGE.
- (7) LINE WALLS WITH 4' X 8' X 3/4" PLYWOOD FOR MOUNTING OF COMMUNICATIONS EQUIPMENT.
- PROVIDE 18" WIDE LADDER TYPE CABLE TRAY AND MOUNT TO SLAB BELOW RAISED FLOOR. COORDINATE ROUTING WITH FLOOR PEDESTALS.



ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX

Jacksonville Office:
208 Ponte Vedra Park Drive
Ponte Vedra Beach, Florida 32082
904 245 6565 TELEPHONE







FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions


*Date* 2013-09-23

*Job No.* 1207007000

FLOOR PLAN — POWER AND SIGNAL

Sheet No.

E-301



1 ROOF PLAN - POWER +LIGHTNING PROTECTION SYSTEM

E-302 SCALE: 1/8"=1'-0"

KEY NOTES

(APPLY TO THIS SHEET ONLY)

- BOND METAL PARTS OF HVAC EQUIPMENT AND OTHER OBJECTS TO LIGHTNING PROTECTION SYSTEM IN ACCORDANCE WITH NFPA 780 AND UL96A.
- BOND NEW LIGHTNING PROTECTION SYSTEM TO EXISTING LIGHTNING PROTECTION SYSTEM.
- PROVIDE CONDUIT AND CONDUCTORS AS REQUIRED TO CONNECT POWER FROM CU-1 TO MS-1 IN ELECTRICAL ROOM 103.

  POWER DISTRIBUTION ORIGINATES AT CU-1 AND EXTENDS TO THE INDOOR UNIT MS-1. INTERCONNECTING WIRING IS REQUIRED. COORDINATE EXTENSION OF CONDUITS TYHROUGH ROOF WITH INSTALLATION OF MECHANICAL PIPING.




ARCHITECTS INTERIORS

Atlanta Office:
5155 Peachtree Parkway
Building 300, Suite 3220
Norcross, Georgia 30092
770 209 9393 TELEPHONE
770 209 7050 FAX







FAYETTE COUNTY EOC

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or

reproduced in any form or by any m of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

*Date* 2013–09–23


*Job No.* 12070070

et Title

ROOF PLAN — POWER & LIGHTNING PROTECTION SYSTEM

Sheet No.

E-302





Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office:







110 Volunteer Way Fayetteville, Georgia 30215



## ©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.

Print Record 07/26/2013: 80% CD Set for Review

09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION


Revisions

2013-09-23

1207007000

FLOOR PLAN - LIGHTING

E-401





Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE





FAYETTE COUNTY

110 Volunteer Way Fayetteville, Georgia 30215



©2013, Wakefield Beasley & Associates Architects, Inc. These drawings
are protected by the copyright laws of the United States. These
drawings or any part thereof may not be used for any purpose or
reproduced in any form or by any means without the written consent
of Wakefield Beasley.

Print Record

07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013-09-23

1207007000

Sheet Title

ELECTRICAL RISER DIAGRAM -EXISTING & NEW WORK

Sheet No.

1. FLOOR OR WALL ASSEMBLY -- MIN 2-1/2 IN. THICK REINFORCED LIGHTWEIGHT OR NORMAL WEIGHT (100-150 PCF) CONCRETE. WALL MAY ALSO BE CONSTRUCTED OF ANY UL CLASSIFIED CONCRETE BLOCKS\*. MAX DIAM OF OPENING IS 30-7/8

2. THROUGH-PENETRANT -- ONE METALLIC PIPE OR CONDUIT TO BE INSTALLED EITHER CONCENTRICALLY OR ECCENTRICALLY WITHIN THE FIRESTOP SYSTEM. THE ANNULAR SPACE BETWEEN PIPE OR CONDUIT AND PERIPHERY OF OPENING SHALL BE MIN O IN. TO MAX 7/8 IN. PIPE OR CONDUIT TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF FLOOR OR WALL ASSEMBLY. THE FOLLOWING TYPES AND SIZES OF METALLIC PIPES OR CONDUITS MAY BE USED:


- A. STEEL PIPE -- NOM 30 IN. DIAM (OR SMALLER) SCHEDULE 10 (OR HEAVIER) STEEL PIPE. B. IRON PIPE -- NOM 30 IN. DIAM (OR SMALLER) CAST OR DUCTILE IRON PIPE.
- C. COPPER PIPE -- NOM 6 IN. DIAM (OR SMALLER) REGULAR (OR HEAVIER) COPPER PIPE. D. COPPER TUBING -- NOM 6 IN. DIAM (OR SMALLER) TYPE L (OR HEAVIER) COPPER TUBING. E. CONDUIT -- NOM 6 IN. DIAM (OR SMALLER) STEEL CONDUIT.
- F. CONDUIT -- NOM 4 IN. DIAM (OR SMALLER) STEEL ELECTRICAL METALLIC TUBING (EMT). 3. FILL, VOID OR CAVITY MATERIAL\* -- SEALANT -- MIN 1/2 IN. THICKNESS OF FILL MATERIAL APPLIED WITHIN THE ANNULUS, FLUSH WITH TOP SURFACE OF FLOOR OR WITH BOTH SURFACES OF WALL. AT THE POINT CONTACT LOCATION BETWEEN PIPE AND CONCRETE, A MIN 1/4 IN. DIAM BEAD OF FILL MATERIAL SHALL BE APPLIED AT THE CONCRETE/PIPE INTERFACE ON THE TOP SURFACE OF FLOOR AND ON BOTH SURFACES OF WALL.

LABORATORIES, INC. DECEMBER 04, 2001

HILTI CONSTRUCTION CHEMICALS, DIV OF HILTI INC -- FS -- ONE SEALANT \*BEARING THE UL CLASSIFICATION MARK

REPRODUCED BY HILTI, INC. COURTESY OF UNDERWRITERS


### HILTI\_FIRESTOP\_SYSTEM\_C-AJ-1291 $\sqrt{E-701}$ SCALE: NONE






SYMBOL: NOTE:


1. FURNISH AND INSTALL #4/O BARE COPPER GROUND CONDUCTOR.



### \INTERIOR\_GROUND\_RING\_WALL\_SUPPORT\_DETAIL E-701/SCALE: NONE




# SUB-SYSTEM GROUND BUS "SSGB" MOUNTING DETAIL




NOTE: BOND THE SHIELD OF SHIELDED CABLE AS REQUIRED.

### SUB-SYSTEM GROUND BUS "SSGB" DETAIL (E-701) SCALE: NONE SYMBOL: SB









NOTE: SIMILAR FOR LIGHT SWITCHES





### PEDESTAL GROUNDING EOC ROOM 110 E-701 SCALE: NTS





ARCHITECTS INTERIORS

Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX


Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE







110 Volunteer Way Fayetteville, Georgia 30215



## ©2013, Wakefield Beasley & Associates Architects, Inc. These drawings are protected by the copyright laws of the United States. These drawings or any part thereof may not be used for any purpose or reproduced in any form or by any means without the written consent of Wakefield Beasley.


Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions


2013-09-23 1207007000 Sheet Title

ELECTRICAL DETAILS

E-701







Γ																
				PANI	ELBOA	RD	SCHED	ULE	EL,	4 (NEW)						
TYPE							,	208Y/1	20	_ VOLTS		3	Ø	4	W	
MOUNTING: X SURFACE										100			_AMP MAIN	S: LUGS BREAKER		
							BRAN	СН	BREAKE	ERS						
ITEM	CONDUIT SIZE	WIRE SIZE	AMP RATING	PoLE	CIR. NO.	,	PH <i>A</i>		LOADIN B.	G C.	CI	R. P <sub>O</sub>	AMP RATING	WIRE SIZE	CONDUIT SIZE	ITEM
RECEPTS ROOF	1/2"	2#12,#12G	20	1	1	360	1200				2	1	20	2#12,#12G	1/2"	LTS RM 110
PROJECTION SCREENS	1/2"	2#10,#10G	20	1	3			′/x	1190		4	. 1	20	2#12,#12G	1/2"	LTS CORR 101, RM 103-107
RECEPTS RM 110, OUTSIDE NE	1/2"	2#10,#10G	20	1	5					900 1200	6	1	20	2#12,#12G	1/2"	LTS RM 102
RECEPTS CORR 101	1/2"	2#10,#10G	20	1	7	720	940				8	1	20	2#12,#12G	1/2"	LTS RM 102
RECEPTS RM 102,103 OUTSIDE S	1/2"	2#12,#12G	20	1	9			1080			10	0 1	20	2#10,#10(G)	3/4"	TV RECEPTS COMM RM 110
RECEPTS RM 105,106,107	1/2"	2#12,#12G	20	1	11					1080	1:	2 1	20	2#10,#10(G)	3/4"	TV RECEPTS ASMBLY RM 102
RECEPT FRIDGE	1/2"	2#12,#12G	20	1	13	750					1.	4 1	20			SPARE
RECEPT DISHWASHER	1/2"	2#12,#12G	20	1	15			1200			10	6 1	20			SPARE
RECEPT MICROWAVE	1/2"	2#12,#12G	20	1	17					1200	18	8 1	20			SPARE
RECEPTS OFFICE 104	1/2"	2#12,#12G	20	1	19	720					2	0 1	20			SPARE
RECEPTS RM104, CORR 101	1/2"	2#12,#12G	20	1	21			540			2	2 1				SPACE
SPARE	_	_	20	1	23					_	2	4 1				SPACE
RTU-1	3/4"	3#10,#10G	30	3	25	2580	2268	3			2	6 3	25	3#10,#10(G)	3/4"	RTU-2
					27			//	2268	V/////////////////////////////////////	2	8				
					29					2580 226	8 3	0				
					31						3	2				
					33						3	4				
					35						3	6				
					37						3					
					39						4	0				
					41						4	2				
	<u> </u>		'	'		5130	4408	6400	3458	5760 3468	3		<b>-</b>		<u>'</u>	
						953		985		9228		OTAL C	ONN. LOAD	28,624	VA	
IN	NTEGRATED	EQUIPMENT RATIN	G					10,000			AI	MPS RM	IS. SYM.			

						DD	SCHEDULE		UL	B (NEW)							
				PAN	ELBOA	KU		08Y/12				7		_	4		
TYPE								2001/12	20	VOLTS .					4\ X LUGS	V	
MOUNTING: X SURFACE										100				AMP MAIN	S: BREAKER		
							BRAN	СН	BREAK	ERS							
ITEM	CONDUIT SIZE	WIRE SIZE	AMP RATING	PoLE	CIR. NO.		PHA	T	LOADIN 3.	IG C.		CIR. NO.	PoLE	AMP RATING	WIRE SIZE	CONDUIT SIZE	ITEM
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	1		1440					2	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	3			1440	1440			4	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	5					1440 14	40	6	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	7	1440	1440			1440 14		8	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	9			<b>//1440</b>	11440	<i>\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\</i>	/////	10	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	11					1440 14	40	12	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	13	1440	1440			1440   14		14	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	15			1440	1440	360 .		16	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPT RM 103	1/2"	2#12,#12G	20	1	17					360 .		18	1	20			SPARE
SPARE			20	1	19							20	1	20			SPARE
SPARE			20	1	21							22	1	20			SPARE
SPARE			20	1	23							24	1	20			SPARE
SPARE			20	1	25							26	1				SPACE
SPARE			20	1	27							28	1				SPACE
SPARE			20	1	29						,,,,,	30	1				SPACE
				1	31							32					
					33							34					
					35	_ \//////		X///////				36					
					37			- <del>\////////////////////////////////////</del>				<del>- 38</del> _					
					39							40					
					41							42					
		4320			0 4320 3240 2880												
		86	40	864	8640 6120			TOTAL CONN. LOAD VA									
I		10,000							_ AMPS RMS. SYM.								

PANELBOARD SCHEDULE ELB (NEW)																
TYPE																
MOUNTING: SURFACE									1	00		/	AMP MAIN	S: D BREAKER		
							BRAN	CH BREAK	KERS							
ITEM	CONDUIT SIZE	WIRE SIZE	AMP RATING	PoLE	CIR. NO.		PHA A.	SE LOAD	NG	C.	CIR. NO.	PoLE	AMP	WIRE SIZE	CONDUIT	ITEM
RTU-3	3/4"	3#10,#10G	25	3	1 3 5	2172	3012	2172   3012			2 4 6	3	35	3#8,#10G	3/4"	RTU-4
GATE CONTROLS	3/4"	3#10,#10G	20	1	7	864	2000				8	3	25	3#10,#10G	1/2"	WH-1
SPARE			20	1	9			200	0		10					
SPARE			20	1	11				ill de la comina de La comina de la comi	2000	12					
SPARE			20	1	13	///////////////////////////////////////	- ////////////////////////////////////				14	1	15	2#12,#12G	1/2"	EF-1
SPACE				1	15			1308				1	20	2#12,#12G	1/2"	CU-1 / MS-1
SPACE				1	17						18	1				SPACE
SPACE				1	19	///////////////////////////////////////					20	1				SPACE
SPACE				1	21						22	1				SPACE
SPACE				1	23				// //		24	1				SPACE
SPACE				1	25	(////////	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				26	1				SPACE
SPACE				1	27						28	1				SPACE
SPACE				1	29				<i></i>	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	30	1				SPACE
					31						32					
					33						34					
					35						36					
					37						-38_					
					39						40					
					41						42					
	,		,	•	•		5012	2172 6320 8492	2172	2 5012 84	TOTA	L CON	IN. LOAD	23,724	VA	
				10,000			AMPS RMS. SYM.									



Atlanta Office: 5155 Peachtree Parkway Building 300, Suite 3220 Norcross, Georgia 30092 770 209 9393 TELEPHONE 770 209 7050 FAX Jacksonville Office: 208 Ponte Vedra Park Drive Ponte Vedra Beach, Florida 32082 904 245 6565 TELEPHONE

1708 Peachtree St. Suite 210 Atlanta, GA 30309 404/355-9334 main 404/835-1118 fax



FAYETTE COUNTY

110 Volunteer Way Fayetteville, Georgia 30215



Print Record 07/26/2013: 80% CD Set for Review 09/23/2013: RELEASE FOR BID 12/02/13 FOR CONSTRUCTION

Revisions

2013–09–23 Sheet Title 1207007000

ELECTRICAL PANELBOARD SCHEDULES

E-801

TYPE							2	208Y/12	20	_ VOL	TS	3		ø	4 v	V	
☐ FLUSH MOUNTING: ☒ SURFACE										100	)			AMP MAIN	X LUGS S: ☐ BREAKER		
							BRAN	СН	BREAKE	ERS							
ITEM	CONDUIT SIZE	WIRE SIZE	AMP RATING	PoLF	CIR. NO.		PHA A.	T	LOADIN 3.	G	C.	CIR. NO.	Po <sub>L</sub>	AMP RATING	WIRE SIZE	CONDUIT SIZE	ITEM
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	1	1440	1440					2	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	3			1440	1440			4	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	5					1440	1440	6	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	7	1440	1440					8	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	9			1440	1440			10	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	11					1440	1440	12	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	13	1440	1440					14	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPTS FLOOR MTD RM 110	1/2"	2#12,#12G	20	1	15			1440	1440			16	1	20	2#12,#12G	1/2"	RECEPTS FLOOR MTD RM 102
RECEPT RM 103	1/2"	2#12,#12G	20	1	17					360		18	1	20			SPARE
SPARE			20	1	19							20	1	20			SPARE
SPARE			20	1	21							22	1	20			SPARE
SPARE			20	1	23							24	1	20			SPARE
SPARE			20	1	25							26	1				SPACE
SPARE			20	1	27							28	1				SPACE
SPARE			20	1	29							30	1				SPACE
				1	31							32					
					33							34					
					35							36					
					37							38					
					39							40					
					41							42					
			4320 4320 4320														
		864	-0	8640	40 6120			TOTAL CONN. LOAD VA									
			10,000				_ AMPS	RMS	SYM.								