

June 11, 2026


**Subject: ITB #26136-B: Traffic Signal - Banks Rd & Ellis Rd Construction
Addendum #1**

Gentlemen/Ladies:

Below, please find responses to questions, clarification, or additional information for the above referenced ITB. You will need to consider this information when preparing your bid.

1. Could you please double check these two pay items quantities?
 - 682-9950 Directional Bore – 5 in 100 LF and
 - 682-6233 Conduit, Nonmetal, TP 3, 2 in 120 LF

Drawing 27-0003 only shows: Conduit, NM, TP 3, 2 IN, 4 EA. See below.



The quantity for Pay Item 682-6233, Conduit, Nonmetallic, TP 3, 2 IN (120 LF) represents the four (4) conduit runs between the proposed timber pole and the proposed signal cabinet located in the northeast quadrant of the intersection. The conduit is designated as Type 3 because the individual runs exceed 20 feet in length.

The quantity for Pay Item 682-9950, Directional Bore – 5 IN (100 LF) is associated with the installation of the electrical service crossing between the proposed power service point at the utility pole in the northwest quadrant and the proposed signal cabinet in the northeast quadrant. This directional bore is separate from the Type 3 conduit installation.

As noted in the plans, all materials, equipment, and work necessary to provide the power service connection shall be included in Pay Item 939-5010.

2. Pay Item 939-5010 on the LOM drawing (27-0004) states payment for “ALL” necessary components/equipment shall be included. Does this include any power company expenses such as transformer, pole, or raising of existing wires?
 - a. If yes per the traffic signal general notes, can the county provide a contact for the power company that is able to quote this work prior to the bid?

Fayette County has started coordination with the applicable utility company regarding the overhead power relocations identified for this project. As part of the utility relocation effort, the power utility has provided relocation plans, which are included as part of this addendum (Attachment 1).

No utility relocation costs associated with the overhead power relocations are anticipated to be the responsibility of the Contractor.

Following the NTP, utility coordination shall be performed in accordance with Section 105.06 of the project specifications. The Contractor shall remain responsible for coordinating with utility owners as necessary to complete the work, including compliance with Georgia 811 requirements.

3. The signal span wire will need to be below all power and possibly through existing telecommunications cabling. A power service drop crosses over the middle of the intersection. The NE leg of span crosses under primary power lines. If GDOT spec 17'-19' signal head height above the road surface and minimum 5% sag is to be maintained, will the county or the power company be responsible for the cost of any raising of power lines if necessary?
 - a. If no, can the county provide a contact for the power company and / or pole owner that is able to quote this work prior to the bid?
 - b. For reference: The distance between the NW & NE corner pole is approx. 172'. That's approximately 8.6' feet of sag from the attachment points. The phase 3 & phase 4 signal heads are almost at the center (lowest point) of the sag. Approx MINIMUM attachment point height is 29.6'.
 - c. Please verify that any necessary make ready work delay time will be added to completion time established in the bid.

Refer to Section 105.06 Cooperation with Utilities of the project specifications. Fayette County has initiated coordination with the applicable utility companies regarding the overhead power relocations identified for this project.

Should utility related delays occur after the NTP is issued that affect the Contractor's ability to perform the work, Fayette County will work with the Contractor to evaluate the impact on the project schedule and determine whether a contract time adjustment is warranted.

4. There is a pay item for a battery back up. The plans nor List of Materials state what type. Should this be internal or external BBS? This will determine what type of cabinet base is required.

The County intends for the Battery Backup System to be an external unit compatible with the specified Model 332 cabinet. The Battery Backup System shall include all equipment necessary for a complete installation, including cabinet, batteries, transfer switch, wiring, and associated hardware.

5. Traffic signal general note 13 references communication service. The plans do not specify a communication type. Should the contractor assume a 4G cellular router for bidding purposes as fiber optic is highly unlikely and include this cost in their bid?

Traffic Signal General Note 13 is a standard note intended to clarify maintenance responsibilities should communication service be installed in the future. No communication service is included as part of this project.

6. In the bid schedule it shows a line item labeled "Battery Backup", with no pay item number associated with it. I can't find anywhere in the plans where it calls for a battery backup unit to be installed alongside the new signal cabinet. Does the county want a BBU installed or was that line item on the bid schedule put there by mistake?

See Question #4.

Received by (Name): _____ Company _____


Note: If this addendum is not returned to the Fayette County Purchasing Department or if it is returned not signed, responding individuals, companies or other organizations will still be responsible for the requirements of this addendum and the specifications or changes herein.

The opening date for this ITB has not changed. **The opening time and date are 3:00p.m., Tuesday, June 23, 2026.** Bids must be received by the Purchasing Department at the address above, Suite 204, at or before the opening date and time.

The deadline for inquiries has passed, so the Purchasing Department will not be able to accept any additional questions after this time.

For administrative matters or questions about the procurement process, please contact Sherry White, Senior Contract Administrator at (770) 305-5314 or email at swhite@fayettecountyga.gov.

Sincerely,



Ted L. Burgess
Chief Procurement Officer

